WORK ORDER

NIHVA TECHNOLOGIES PVT. LTD.

Client:	
Ratnaroop Projects pvt ltd	
Address:	
202/203 , Amar Neptune Baner Road,Behind Baner food bazar baner pune-411045	

PO Number:	RPPL/HINJEWADI/02/MJB/2021-22	**W. O. No-**	SO/22-23/002
PO Dated :	28-03-2022	**W. O. Date**	05-04-2022
PO Received Date:	01-04-2022	**Sales Co ordinator**	Pradeep Shinde
Ref. Quotation:	SQT.21.22.0325 R1	**Front Sales Person**	Pradeep Shinde

Dispatch Address:

MJ Biopharm Pvt Ltd
Plot No 18 International bio tech park,
Near grand tamanna, Hinjewadi phase II Pune-411057

A Technical Terms:

Sr. No	Description of Goods	Technical Details	UOM	Qty.	Supply Rate	Installation Rate	Total Amount	Dwg. Approval Status
1	**Single Skin MS Motorised Rolling Shutter -1.2 mm slat thk - Indirect drive Motor 3mtr*3mtr**	**Description: Motorised** Rolling Shutter with MS Slats with thickness of 1.2 mm. **Mounting Location area :** Inside area / Outside area **Mounting Surface:** Side Brackets: Optional = On Concrete /Steel & Side **Curtain Panel:** The panel made of 1.2 mm thick MS **Curtain panel size:** 75mm wide **Curtain Profile:** Curved **Bottom Profile:** M. S. Plate 100 mm x 2.5 mm thick with angle stiffener **Side Guide Profile:** M.S." U" Shaped profile 65mm-150mm*3mm thick **Roller Shaft:** M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h **Side Brackets:** MS Plate 3 mm to 10 mm thick, as per the opening dimension. **Hood Cover:** Made of GI Sheet Thickness 0.9 mm. **Surface finish:** 2 Coats (each coat of 35 microns DFT) of EPOXY polyamide-based enamel finish of approved color and make over a Coat (each one coat 25 microns DFT) of EPOXY polyamide based red oxide zinc phosphate primer_Synthetic enamel paint **Drive Unit & Mounting Type:** Indirect drive motor -Chain sprocket arrengement - IP54 **Motor Weigh capacity** ;-400kg make jielong	**Nos**	**4**		**Included**	-	**Pending**
						Total	-	

Non standard items/extra requirement, if any:	

B Commerical Terms:

1	**Payment Terms:**	30% Advance along with PO, 60% Against material at site and balance 10% after Installation & completion certificate issued by client within 1 week		
2A	**Delivery Date as per PO:**	within 3-4 week	**2B. Required Delivery Date:**	
3A	**Transportation Scope:**	Included	**3B. Transportation Charges:**	
4	**P&F Charges:**	NIL		
5A	**Loading Scope:**	NIHVA	**5B. Loading Charges:**	
6A	**Unloading Scope:**	NIHVA	**6B. Unloading Charges:**	
7A	**Lifting Equipments Scope:**	CLIENT	**7B. Available Lifting Equipments:**	
8	**Warranty:**	12 months from the date of supply.		
9A	**Height arrangement Scope:**	CLIENT	**9B. Available Equipments for working at Site:**	
10	**Electricity Supply:**	CLIENT		
11	**GST:**	As Applicable		
12A	**Installation Scope:**	NIHVA	**12B. Installation required date:**	
13	**Mode of import:**	NA		
14	**HSS:**	No		
15	**Documentation Required:**	Standard Handover Documents		
16A	**Total site visits required:**		**16B. Site visit charges:**	

Certified that the above work order finalised in presence of:

AGM	SALES		Operation	PROJECT	DESIGN	Date & Time
A.K.	**V.T.**		**S.B.**	**S.M.**	**S.BR.**	**05-04-2022**