NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

ITD CEMENTATION INDIA LIMITED (Myanmar Branch
C/O, ADANI YANGON INTERNATIONAL TERMINAL COMPANY LTD
Project code No: 048619DM .Plot No23 G/R, 23 R/2A,
Near Thit Taw Bus Stop, Ahlone TSP, Yangon, Myanmar

Date : 21.12.2020
Quote NO : SQT.20.21.2775 R
Kind Attn : Mr. Pramod Ch. Upadhyaya
Email Id : pramod.upadhyaya@itdcem.co.in
Contact No: +95-9958552291

Project Name & Location: Adani Project at Myanmar

Subject : NIHVA Make Dock Leveller - 15 Ton

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Condtions	2

A) Commercial Offer

Sr No	Description	Size	Qty	Supply Charges in USD			
		Size (in mm)	(Nos)	Unit Price	Total Amount		
1	**NIHVA Make Dock Leveler - 15 Ton**	(W) 2000 x (L) 2500	6	4,167	25,002		-
2	**Delivery charges**		6	800	4,800		
3	**Installation charges per Dock Unit**		6	398	2,388		
			Total		**25,002**		**-**
2	P&F Charges on Total Supply Value		3%		**750**		
			Total Without Taxes		**25,752**		**-**
	GST Extra @ 18%				**Client Scope**		-
			Total With Taxes				**-**
3	Transportation Charges				**NIHVA Scope**		
4	Unloading Charges @ Site				**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification -

Dock Leveler





Sr. No.	Description	Specifications
1	Capacity	15 Ton
2	Dock operation mode	AC power pack hydraulically operated
3	Lip operation mode	Hydraulic
4	Operation control	Through panel
5	Loading platform height from road	1250mm
6	Travel above & below dock level	(+) 600 / (-) 300 mm
7	Platform Size (W x L)	2000 mm x 2500 mm
8	Lip size (W x L)	2000 x 400 mm
9	Shut Height	480 mm
10	Maximum slope can be achieved	10%
11	Clear Pit dimensions (W x L x D)	(W) 2050mm x (L)2500 mm x (D)480 mm
12	Hydraulic power pack	Standard
13	Driver type	Direct by electric Motor
14	Motor Ratings	1 H.P
15	Pump design flow	2.5 LPM
16	Pump pressure	120 bar Operating 200 bar Max.
17	Safety valve set pressure	120 Kg/cm²
18	Pump Type	Gear
19	Volume of oil receiver	7 Lit
20	No Of Deck cylinder	2 No
21	Lip Cylinder	1 No
22	Pair of Dock Bumper	Included

D) Terms & Conditions

Price	**: CIF YANGON Port, Myanmar**
Delivery	:7 - 8 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.
Payment	: 100% Advance along with Confirmed Purchase Order.
Validity	: Validity of Offer is 15 days from the date of quotation
Warranty	: 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Shrikant Mirkute on 8551098333.**

With Best Regards
Smita Khare
9637991333
For NIHVA Technologies Pvt Ltd