**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

# NIHVA Sales Quotation

**Nima Enterprises**
Ahmedabad

**Date :** 11.12.2021
**Quote NO :** **MHE_21.22.0048**
**Kind Attn :** Mr. Ketan
**Email Id :** ketan@nimaenterprises.com
**Contact No:** 9930258280

**Project Name & Location: Nima Enterprises, Ahmedabad**

**Subject : Quotation for Loading/Unloading Conveyor**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**

| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 2 |
| D. | Terms & Conditions | 2 |

**A) Commercial Offer**

| Sr No | Description | Qty | Supply Charges in INR | | Installation considering 03 people for 03 days per conveyor in INR | |
|---|---|---|---|---|---|---|
| | | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | **Telescopic Truck Loader/Unloader Conveyor for 20ft container**<br>• Total Length- 10 mtr<br>• Capacity- 20-30 boxes/min | 1 | 14,00,000 | 14,00,000 | 50,000 | 50,000 |
| 2 | **Take Up Conveyor**<br>• Inclined Height: 5.5 mtr | 1 | 5,75,000 | 5,75,000 | 35,000 | 35,000 |
| | | Total | | 19,75,000 | | 85,000 |
| 3 | GST Extra @ 18% | 18% | | | | Extra At Actual |
| 4 | P&F Charges | 3% | | | | Extra At Actual |
| 5 | Transportation Charges | | | | | Extra At Actual |
| 6 | Insurance Charges | | | | | Extra At Actual |
| 7 | Unloading Charges @ Site | | | | | In Client Scope |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**

**Telescopic Truck Loader/Unloader Conveyor**

| Sr. No. | Parameters | Specification |
|---|---|---|
| 1 | Material to be conveyed | Bags/Boxes |
| 2 | Maximum Weight of Box/Bag | 22 Kg max. |
| 4 | Capacity | 30 boxes/min |
| 5 | Size of Belt | 750 mm |
| 6 | Belt Type | PVC belt |
| 7 | Conveyor Type | Collapsible boom type hinged Telescopic belt conveyor |
| 8 | Length Of Conveyor | Fixed Length : 5000 mm<br>Telescopic (Expanded) : 9000 mm<br>Total : 14000 mm |
| 9 | Main Body Of Conveyor | MS Powder coated |
| 10 | Lifting Mechanism | Hydraulic power packs |
| 11 | Drive Motor & Gear Box | SEW/ Equivalent Make |

**Take Up Conveyor**

| Sr. No. | Parameters | Specification |
|---|---|---|
| 1 | Material to be conveyed | Bags/Boxes |
| 2 | Maximum Weight of Box/Bag | 22 Kg max. |
| 3 | Capacity | 10 bags/min |
| 4 | Size of Belt | 750 mm |
| 5 | Belt Type | PVC belt |
| 6 | Inclined Height | 5.5 mtr |
| 7 | Length Of Conveyor | 9 mtr |
| 8 | MOC | MS Powder coated |

**C) General Conditions**

1 Installation will start after receiving of Site Readiness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 After 1 year warranty, Non comprehensive AMC will be provided by NIHVA, which will be cost you extra.

**D) Terms & Conditions**

**Price** : Ex Works Pune.

**Delivery** : 10-12 weeks from the date of receipt of confirmed Purchase Order, Advance Payment & Drawing approval.

**Payment** : 80% Advance along with Confirmed Purchase Order & Balance 20% against readiness of material before dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation.

**Warranty** : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Hiren Joshi on 855100 92333**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd