NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

RATILAL BHAGWANDAS CONSTRUCTION COMPANY
Pune

Date : 29.07.2020
Quote NO : SQT.20.21.0028R
Kind Attn : Ms. Seema Zambre
Email Id : tender.rbcc@ratilal.in
Contact No:

Project Name & Location: Seco

Subject : Quotation for Rolling Shutter

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Motorised Rolling Shutter	3020	4000	1	1,17,000	1,17,000	20,000	20,000
2	Motorised Rolling Shutter	3290	4000	1	1,23,000	1,23,000	20,000	20,000
3	Motorised Rolling Shutter	3000	4000	2	1,16,000	2,32,000	20,000	40,000
				Total		**4,72,000**		**80,000**
4	P&F Charges			3%		**14,160**		
	Total Without Taxes					**4,86,160**		**80,000**
	GST Extra @ 18%			18%		87,509		14,400
	Total With Taxes					**5,73,669**		**94,400**
5	Transportation Charges					**Extra at Actual**		
6	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Motorised Rolling Shutter

Sr .No.	Description	Specification
1	Rolling Shutter	Motorised Rolling Shutter with GI Laths with thickness of 1.2 mm.
2	Mounting Location area	Inside area / Outside area
3	Mounting Surface	Side Brackets: Optional = On Concrete /Steel & Side
4	Curtain Panel	The panel made of 1.0mm thick MS.
5	Curtain panel size	75mm wide
6	Curtain Profile	Curved
7	Bottom Profile	"140 MM & 2.5 MM THK M.S BOTTOM PROFILE 35 X 35 X 6 MM angle on one side up to 5 Mtr. wide Shutters and on both sides for Shutters exceeding 5 Mtr. width."
8	Side Guide Profile	(2.5mm) Thick 75MM Deep for Shutters up to 4 Mtr. Wide.
9	Roller Shaft	For Shutters up to 2.00 Mtr. width – 75mm dia OD Heavy Class pipe. Width 2.00 Mtr. to 3.00 Mtr. -75mm OD Heavy Class pipe. Width 3.00 Mtr. to 6.00 Mtr. -100mm OD Heavy Class pipe.
10	Side Brackets	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	Hood Cover	hood made of 0.90 mm thick G.I.
12	Surface finish	One coat of zinc chromate primer and two coats of synthetic enamel (Low VOC paint of approved color
13	Drive Unit & Mounting Type	Indirect Drive, Electric Motor
14	EMERGENCY Operation	IN CASE OF EMERGENCY MANUAL CHAIN IS PROVIDED FOR OPERATION

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6 - 7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Bhavin Jain on 8551092333**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd