NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/18-19/0575R1 **Date : 16-07-2019**

IKEA India Pvt Ltd
Indospace Industrial Park-Chakan II/III,
Talawade Chakan Road,Mahalunge,
Pune, Maharashtra-41050

Kind Attn Mr. Rahul Borate
Email ID Rahul.Borate@IKEA.com
Mob No 7020097007

Project Name And Location :

Subject : Revised Quote for Traffic Signalling Systems & Tower Lamp System

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr.No	Description	Location	Qty	Rate In INR	Total Amount
A	**New Supply - Traffic Signalling Systems**				
1	**Includes following** • One set of any color Lamp head (140 mm) with Metal Housing. • Number of high bright LED's : 60 no's and consumption 4 Watts only. • Brightness : 10000 MCD to 12000 MC • Viewing Angle : 23 Degrees • Wave Length : Red – 625 Nm , Green : 495 Nm to 497 • LEDs are mounted on glass epoxy fire retardant pcb. • The lamp heads are supplied with all mounting blackheads and clamps suitable for 2inch to 6 inch dia Pole. •Electrical Interlocking & Electrical Cabling • Limit Switch	**Chakan - 2**	20	12,500	250,000
					250,000



GST Pune	27AAECN0437H1ZM

SAC: 998732

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	@3% of total suply value
3	**Freight Notes**	:	Extra as applicable + Taxes
4	**Delivery**	:	2 -3 weeks from the date of receipt of confirmed purchase order, Advance Payment
5	**Payment**	:	80% Advance along with Confirmed Purchase Order & Balance before dispatch.
6	**Insurance**	:	Extra As applicable
7	**Taxes**	:	GST Extra @ 18%
8	**Validity**	:	Validity of Offer is 15 days from the date of quotation
9	**Warranty**	:	12 months from the date of supply.

With Best Regards

Varsha

8551091333

For NIHVA Technologies Pvt Ltd