NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Crane Process Flow Technology Pvt Ltd
Satara

Date : 9.10.2020
Quote NO : SQT.20.21.2747
Kind Attn : Abdul Chinchanikar
Email Id : projectsupport@wanigroup.com
Contact No: 8149707826

Project Name & Location: Satara

Subject : Quotation for Motorised Rolling Shutter

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Motorized Rolling Shutter	3500	3600	1	116,000	116,000	20,000	20,000
2	Motorized Rolling Shutter	3000	3200	2	101,000	202,000	20,000	40,000
3	Motorized Rolling Shutter	4000	3000	1	113,000	113,000	20,000	20,000
4	Motorized Rolling Shutter	3000	3000	5	98,000	490,000	20,000	100,000
5	Motorized Rolling Shutter with Grill	3000	3000	1	115,000	115,000	20,000	20,000
6	Sectional Doors (horizontal Lift)	3000	3000	1	330,000	330,000	20,000	20,000
7	Sectional Doors (horizontal Lift)	4000	3000	1	350,000	350,000	20,000	20,000
8	High Speed Doors	3000	3000	1	658,000	658,000	20,000	20,000
9	High Speed Doors	4000	3000	1	686,000	686,000	20,000	20,000
10	Automatic Sliding Gate	12000	1500	1	563,000	563,000	20,000	20,000
11	Automatic Sliding Gate	10000	1500	1	500,000	500,000	20,000	20,000
12	Wicket Gate	1200	1200	1	30,000	30,000	10,000	10,000
13	Wicket Gate	1000	1350	1	25,000	25,000	10,000	10,000
14	Boom Barrier		5000	6	120,000	720,000	20,000	120,000
15	Boom Barrier		4000	6	120,000	720,000	20,000	120,000
				Total		**5,618,000**		**580,000**
16	P&F Charges			3%		**168,540**		
	Total Without Taxes					**5,786,540**		**580,000**
	GST Extra @ 18%			18%		1,041,577		104,400
	Total With Taxes					**6,828,117**		**684,400**
17	Transportation Charges					**In Client Scope**		
18	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Motorized Rolling Shutter with Grill

Sr .No.	Specification	GI Motorized Rolling Shutter
1	Description:	Motorised Rolling Shutter with GI Laths with thickness of 1 mm.
2	Mounting Location area	Inside area / Outside area
3	Mounting Surface	On Concrete /Steel
4	Curtain Panel	The panel made of 1.0mm thick MS.
5	Curtain panel size	75mm wide
6	Curtain Profile	Curved
7	Bottom Profile	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	Side Guide Profile	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	Side Brackets	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	Hood Cover	Made of GI Sheet Thickness 0.9 mm
12	Surface finish	Powder Coating
13	Honeycomb Grill	600mm grill at 3000mm height from Bottom.
14	Drive Unit & Mounting Type	Electric Motor - Indirect Mounting - Sprocket chain arrangement – IP54 Protection

NIHVA ASSA ABLOY Sectional Door

Sr. No	Description	Specification
1	Model No	ASSA ABLOY OH1042P
2	Opening Direction & Mounting	Standard (Horizontal)
3	Opening/Closing Speed	CDM9 0,28 m/s
4	Door Material	Steel
5	Panel Thickness	42 mm Square Grid, steel sheet
6	Filling	CFC-free polyurethane
7	Door sealent	All door sealants made of EPDM rubber, temperature resistant - 30/+70
8	Water Penetration	EN 12425 class 3
9	Air Permealibity	EN12426 class 3
10	Thermal Transittance	EN 12428 1.10W /m2K
11	Bottom sealing	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber
12	Door saftey	Doors equiped with spring break device
13	Incase of Power failuer	Doors to be equiped with quick release fuction
14	Operator power conumption	Operator to have a maximum power consumption of 0,37kW and a standby consumption of Maximum 15W
15	Drive Unit & Mounting Type	Single phase 230V direct drive on shaft
16	Emergency Operation	by Disengagement rope manual
17	Operating Switch	Up/Down Keypad + stopbutton
18	Locks : Lock bolt	The Lock bolt locks the door from the inside, without the use of a key. The Lock bolt is not visible from the outside.
19	Environmental Green Product	As per ISO 14025 and EN 15804

High Speed Door Albany Rapid Rollup Door RR300I

Sr. No	Description	Specification
1	Construction:	High-Speed Roller Door with transparent curtain and reinforcement stripes according to the following RAL
2		Side frames: Side frames galvanized, bottom rail profile made of aluminium
3	Drive Unit:	Motor IP 55, either RH or LH as an option, with control cable (standard length = height of door)
4	Control system :	Controls ACS 50, IP 55 for opening / closing speed approx. 1,0 m/s. Control box with Up-Stop-Down button.
5	Power supply:	3/(N)/PE/230/400/415 V, 50 Hz.
6	Safety features:	Safety edge, safety photocell Transmitter / Receiver inside side frames, emergency crank and mechanical

Motorized Sliding Gate

Sr .No.	Specification	Motorized Sliding Gate
1	Door type	Motorized Sliding Gate
2	Opening Direction	Horizontal - from left to right or reverse
3	Mounting Location area	Inside area
4	Design Pattern	Standard Tubular Design Pattern
5	Outer Tube	100 X 50 X 4 mm THK SQ. TUBE
6	For Post	100 X 50 X 4 mm THK SQ. TUBE
7	Inner Vertical Flat	50 X 10 mm FLAT
8	Gap Between Tubes	125mm
9	Bottom Rail on ground	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
10	Bottom Rollers	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
11	Guide Rollers supporter during Gate	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
12	Painting	2 Coats of EPOXY polyamide based enamel finish of approved colour
13	El motor make	BFT – Italy (100% imported)
14	Emergency Operation	Manual after turn the switch
15	Operating Switch	Push Button from inside
16	Safety	Photocells, Flashing Light

Boom Barrier

Sr .No.	Description	Specifications
1	Size	4 meter / 5 meter
2	Make	BFT
3	Opening time	3S
4	Motor Power Supply	24V
5	Type of limit Switch	Electronic
6	Safety	Photocell sensor, Flashing Light With Buzzer
7	Operated	Remote Control / Push Button Pedant

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 4-5 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% along with confirmed purchase order & Balance before dispatch

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Ravindra Kharat on 7410169333.**

With Best Regards
Shailesh Bhoir
7219206333
For NIHVA Technologies Pvt Ltd