AAR INDAMER TECHNICS PVT LTD
PLOT NO. 2A,2B,2C,SEC-9,MIHAN SEZ
KHAPRI,NAGPUR,MAHARASHTRA 441108 INDIA.
Tel No : 91-22-26613552 91-22--26615661 91-22-26613824 Fax No : 91-22-26613626
E-Mail Address : yogendrak@aarindamertechnics.com

PURCHASE ORDER

TO,
NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad, Pune – 411019

PO NO	**PO/INDAAR/20-21/194**
DATE :-	26-Dec-2020
Quote No	**SQT.20.21.2850 R2**
	Dt 21/12/2020

Billing Address -
AAR INDAMER TECHNICS PVT LTD
PLOT NUMBER 2A,2B,2C,SEC-09,MIHAN SEZ
KHAPRI,NAGPUR 441108
INDIA.
GSTIN:27AAECI0772Q2Z1

Shipping Address -
AAR INDAMER TECHNICS PVT LTD
PLOT NUMBER 2A,2B,2C,MIHAN SEZ
KHAPRI,NAGPUR 441108
INDIA.
GSTIN:27AAECI0772Q2Z1

PO for 2 Hours Fire rated Rolling Shutter.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A	**Commercial Offer**	**1**

Sr No	Description	Size		Qty	Supply Charges in		Installation	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**2 Hrs Fire Rated Rolling Shutter (100% Imported)**	4000	4100	1	288,000	288,000	15,000	15,000
2	**2 Hrs Fire Rated Rolling Shutter (100% Imported)**	8134	5500	1	679,000	679,000	15,000	15,000
3	**2 Hrs Fire Rated Rolling Shutter (100% Imported)**	5700	4100	1	388,000	388,000	15,000	15,000
	Total					**1,355,000**		**45,000**
4			P&F Charges	0%		-		
			Total Without Taxes			1,355,000		45,000
			GST under LUT @ 18% Exp	18%		0.00		0
			Total With Taxes			**1,355,000**		**45,000**
5			Transportation Charges			In		
6			Unloading Charges @ Site			In Client Scope		

B) Technical Specification

Sr .No.	Specification	2 Hour Fire Rated Rolling Shutter
1	Certification	• BS 476 Part 22 & MS 1073 Part 3 1988• Tested in Warrington Fire Reasearch Centre UK & Sirim Malasiya
2	Test	UL - 10B Tested
3	Shutter Slats	Zinc coated steel solid slats
4	Shutter Curtain	Roll formed from 1st grade BHP Zincalume steel SKB-A7 curve slatcurtain
5	Guide Rail	Fabricated from hot-dipped galvanised steel of 3.0 mm with one piece design surface mounted type.
6	Bottom Bar	Assembled of 2 Pieces of 38 x 38 x 3 mm galvanised steel angle bolted 800 mm pitch with galvanised bolts and nuts or 2 pieces of 40 x 40 x 6 mm steel flat bar.
7	Shutter Enclosure Box	Pressed Galvanised steel sheet to suite box size comply to fire test approved thickness.
8	Operation Control	Gear motor with Thermal protector, limit switches, manual overide, c/w push button switch with keys lockable.
9	Motor Drive Unit	Power Source: 110v 60Hz 1 phase 220v 60Hz 1 phase 230v 50Hz 1 phase 400v 50Hz 3 phase Manual Chain Override One unit push button switch Gravity drop level Auto close by relay switch after receive of 24vdc fire signal
10	Fire Mode	Fire Shutter will auto close via upon receiving of 24VDC fire signal

C) General Conditions

1) Installation will start after receiving of Site Readyness Photographs or written Email communication.
2) We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation
3) For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.
4) If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Please find below List which are in Client Scope

SR No.	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

1	**Price**	: Ex Works Pune
2	**Delivery**	: 4-5 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.
3	**Payment**	: 50% Advance along with Confirmed Purchase Order & Balance 50% after material is reached at site.
4	**Validity**	: Validity of Offer is 15 days from the date of quotation
5	**Warranty**	: 12 months from the date of supply.

Prepared by : Rohan Dhumal

Approved: PRAJAY PATEL

Prajay Patel

AAR INDAMER TECHNICS PVT. LTD. MIHAN NAGPUR