NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Swedish Trading Company Pvt Ltd
Sri Lanka

Date : 23.12.2024
Quote NO : RR_24.25.0140R
Kind Attn : Mr. Dushmantha Senanagake
Email Id : dusho@swedishtradngltd.com
Contact No: 94112734015

Subject : Commercial Offer for Fixed Aluminium Fabric Hanger Tent

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	1
C.	General Conditions	2
D.	Terms & Condtions	2

A) Commercial Offer

Sr No	Description	Size (mtr)	Qty	Supply Charges in INR (CIF Charges - till Colombo Sea port)	
			(Nos)	Unit Rate	Total
1	**NIHVA Make - Fixed Aluminium Fabric Hanger Tent - Opt - 1**	**(W)20 x (L) 50 Meter X (Center H) 6m , Total Area = 1000 Sq. Mtr.**	1	61,00,000	**₹ 61,00,000**
2	**NIHVA Make - Fixed Aluminium Fabric Hanger Tent - Opt-2**	**(W)20 x (L) 80 Meter X (Center H) 6m , Total Area = 1600 Sq. Mtr.**	1	86,50,000	**₹ 86,50,000**
3	**Total without Taxes**				
4	GST Extra @ 18%			**not applicable**	
5	P&F Charges @ 3%		3%	**Extra At Actual**	
6	Transportation Charges			**In NIHVA Scope**	
7	Unloading Charges @ Site			**In Client Scope**	

Note :- Installation charges will be quoted extra at actuals.

B) Technical Specification

This is Aluminium Structure due to Marine environment
20 MTR. Hanger having TRUSSES with PERLINS in each duely anodised .
A Rafter Beam fitted with C clamps to Hold PERLINS with HIgh Tensile Bolt , PILLAR / VERTICALS ,
D GABLE Support as per requirement , E CENTER & SIDE PERLINS, INTERMEDIATE PERLINS

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) Profiles & Connections:

* Main Beam / Column: 180 mm x 100 mm x 5 mm thickness
* Gable end beam/ Gable end Column/ Centre Purlin/ Side Purlin: 100 mm x 70 mm x 4 mm
* Square Purling: 60 mm x 60 mm x 3 mm

D) Tube Material:

* Hard pressed extruded Aluminum tubes
* Profile Finish – Anodized aluminum tubes 6061/T6

E) Fittings:

MS fitting- galvanized
* Canter V-Joint
* Pillar Plates
* Base Plates
* Bracing Pipes

F) Accessories:

* Cross Pipes
* Nuts Bolts and all other galvanized hardwar

G) Cover

* Top Fabric : 830white Blackout FR/UV , Lacquered Coated 7 yrs limited warranty from the date of supply
* DI: 650 GSM white Blackout FR/UV , Lacquered Coated 7 yrs warranty Side Coverings with gable ends

D) Terms & Conditions

Price :	CIF Charges - till Colombo Sea port
Delivery :	6-8 weeks from the date of receipt of confirmed Purchase Order, Advance Payment & Drawing Approval.
Payment :	100% advance with order
Validity :	Validity of offer is 15 days from the date of quotation.
Warranty :	12 months from the date of supply. It only covers damage caused due to mechanical system not due to natural calamity.

Business terms :

1 In case of change in size, it will be charged accordingly.
2 Civil work to be completed by you as per drawings.
3 Crane, Hydra, Scaffolding as required, to be provided by you at site
4 Electricity to be provided up to point of installation.
5 Safe place for storing our material and equipment's to be provided at site.
6 Accommodation & transportation to be provided to our technicians
7 Local authority permission if required, to be procured by you
8 Require Secure & Safe Work Place

With Best Regards

Priyanka Pachange

7410169333
NIHVA Technologies Pvt Ltd