**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

## NIHVA Sales Quotation

**Gestamp Automotive India Pvt.ltd**
E1 (Part), Chakan MIDC Phase-III, Village Nighoje,
Mhalunge, Kharabwadi, Pune- 410501

**Project, Location : Chakan**

**Date :** 19.02.2021
**Quote NO :** SQT.20.21.3041
**Kind Attn :** Mr. Omprakash Chaudhari
**Email Id :** ochaudhari@in.gestamp.com
**Contact No:** 9673337705

**Subject : Quotation for Fold-up Doors and Rapid Roll-up Door**

Dear Sir,

**Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.**
**This has reference to your above mentioned requirement, please find below our Solutions.**

| Sr. No | Description | Pages |
|---|---|---|
| A. | Commercial Offer | 1 |
| B. | Technical Specification | 2 |
| C. | General Conditions | 3 |
| D. | Terms & Condtions | 3 |

**A) Commercial Offer**

| Sr No | Description | Size | | Qty | Supply Charges in INR | | Installation Charges in INR | |
|---|---|---|---|---|---|---|---|---|
| | | Clear Width (mm) | Clear Height (mm) | (Nos) | Unit Price | Total Amount | Unit Price | Total Amount |
| 1 | **Fold-up Doors** | 4500 | 5000 | 2 | 304,000 | 608,000 | 20,000 | 40,000 |
| 2 | **Rapid Roll-up Doors** | 3000 | 3000 | 1 | 286,000 | 286,000 | 20,000 | 20,000 |
| | **Total** | | | **3** | | **894,000** | | **60,000** |
| 3 | P&F Charges | | | 3% | | 26,820 | | |
| | **Total Without Taxes** | | | | | 920,820 | | 60,000 |
| | GST Extra @ 18% | | | 18% | | 165,747.60 | | 10,800 |
| | **Total With Taxes** | | | | | **1,086,568** | | **70,800** |
| 4 | Transportation Charges | | | | | Extra at atcual | | |
| 5 | Unloading Charges @ Site | | | | | In Client Scope | | |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**B) Technical Specification**



| Sr. No. | Description | Specification |
|---|---|---|
| 1 | Product | High Speed Door-Fold up type ( All Imported Components ) |
| 2 | Opening Direction | Vertical |
| 3 | Mounting Location | Inside of the bay, inside the building |
| 4 | Opening/Closing Speed | 0.5m/Sec. -1.0m/Sec. |
| 5 | Wind Resistance | 90km/h – 110 km/h |
| 6 | Curtain Material | Curtain is in PVC made by anti-tear polyester fabric |
| 7 | Curtain Weight | 680 gr/sqm |
| 8 | Tensile Strength Warp/Weft (N/5Cm) | DIN 53354 - DIN EN ISO 1421/met. 1 – 2500/2500 N/50 mm |
| 9 | Stiffeners | Polycorbinate pipes |
| 10 | Tear Strength | Warp/Weft DIN 53363 – 250/250 N |
| 11 | Temperature range | -30°C +70°C |
| 12 | Flame Resistance | reaction in class 1 or 2 |
| 13 | Vision Panel | One row of transparent PVC windows, in rectangular size, assures a good visibility |
| 14 | Fabric Color | Standard Blue, Grey, Red, Optional with various colors |
| 15 | Fold Up Arrangement | Segmented PVC curtain is folded up through lifting belt & tube mechanism |
| 16 | Roller Shaft | Tubular pipes with lifting belts |
| 17 | Side Guide Rails | Self supporting Galvanized steel structure |
| 18 | Bottom Profile | PVC profile |
| 18 | Side Brackets | Galvanized steel brackets with bearings |
| 19 | Hood Cover (Optional) | Galvanized steel |

**Rapid Roll-up Doors**

| Sr. No | Description | Specifications |
|---|---|---|
| 1 | Use | Internal Door |
| 2 | Speed | Inverter Motion system to adjust different speeds, with progressive control of acceleration & deceleration during braking |
| 3 | Opening speed | upto 3 m/s |
| 4 | Closing speed | 0.8 m/s |
| 5 | Control Panel | 4 Push Button operated |
| 6 | Security Features | EN 13241-1 Standard |
| 7 | Resistance to wind load | EN12424 upto class 1 |
| 8 | Curtain | Fabric Transparent PVC section |
| 9 | Guide Material | Aluminum |
| 10 | Hood Cover | GI |
| 11 | Motor Cover | GI |
| 12 | Operator & Control | German Make Motor |
| 13 | Connecting Voltage | 220V , 1Ph , N |
| 14 | Open-Stop-Close Button | Standarad |
| 15 | Protection Category | IP 54 / IP 65 |
| 16 | Power Consumption | 0.75 kw Motor |
| 17 | Emergency Off Button | Standard |
| 18 | Closing Zone Monitoring | Optical Safety edge |
| 19 | External Route Monitoring | Photocell |
| 20 | Emergency Opening | Crank Handle |

**NIHVA Technologies Pvt. Ltd.**
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

**An ISO 9001:2015 Certified Company**

**GST Pune : 27AAECN0437H1ZM**

**C) General Conditions**

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

**Note: Please find below List which are in Client Scope**

| Sr. No | Description |
|---|---|
| 1 | Secured and fully covered Store area to keep the material |
| 2 | Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site |
| 3 | Electrical Supply on the site single phase/three phase points at different places. |
| 4 | Any civil / masonry/structural work required |
| 5 | All structure support required |
| 6 | In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage. |
| 7 | Conduits, Cables required |

**D) Terms & Conditions**

**Price** : Ex Works Pune

**Delivery** : 8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

**Payment** : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

**Validity** : Validity of Offer is 15 days from the date of quotation

**Warranty** : 12 months from the date of supply.

Please feel free to Contact **Mr. Ravindra Kharat on 7410169333** For any further Clarification /Information in this Concern.

**With Best Regards**
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd