NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Endurance
Pune

Project, Location :

Date : 4.2.2021
Quote NO : SQT.20.21.2976
Kind Attn : Mukund Patil
Email Id : mypatil@endurance.co.in
Contact No: 0240-2569000

Subject : Quotation for Fire Rated Door with Door Frame

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**P/F Insulated fire rated door with Door Frame**	1200	2350	2	50,000	100,000	10,000	20,000
	Total			**2**		**100,000**		**20,000**
2	P&F Charges			3%		3,000		
	Total Without Taxes					103,000		20,000
	GST Extra @ 18%			18%		18,540.00		3,600
	Total With Taxes					**121,540**		**23,600**
3	Transportation Charges					Extra at atcual		
4	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

P/F Insulated fire rated door with Door Frame

Sr .No.	P/F Insulated fire rated door with Door Frame
1	Size width 1200 mm X height 2350 mm
2	Fire Resistant Door Single Leaf Hinge Type (1 Hr Fire Rated)
3	0.80 mm thick GI Sheet cladded 46mm thick shutter infill material Mineral Wool (Density - 96 Kg/M3) complete with GI frame
4	(Single Rebate – 100 x 57mm) made from 1.20mm thick GI Sheet
5	Fixing arrangements AS PER BS 476 PART- 20 & 22
6	Finish – Paint Finish (RAL 9002)
7	Panic Exit Device for Single Leaf Door
8	Heavy Duty Door Closer (Dorma Make)
9	Vision Panel with Fire Glass of Size: 200 x 300mm (6mm Thick Fire Glass)
10	External Trim Bar (Panic Latch)

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 5 - 6 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Bhavin Jain on 8551092333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd