BUDGETARY QUOTATION

PROPOSAL NO: WARADE/QTN/16-17/2055 **DATE: 20/03/2017**

To,
NIHVA Technologies Pvt Ltd.
187, G-Block, 1st floor,
Thermax chowk, MIDC,
Above Renault showroom,
Chinchwad, Pune 411 019

Kind Attention: Mr. Vijay M. Tarak (Director) & Mr. Mayur Derle (Asst. Sales Manager)

Subject: Offer for SACHET BAGGING SOLUTION Secondary & Tertiary Packing for End of Line Automation.

Dear Sir,

This refers to recent discussion & visit had at your facility for Sachet bagging solution machine. Please find quotation for the same as below.

We trust, enclosed offer is in line with your requirement & you will soon inform us about further proceedings in this project.

If you need any further information or clarification in this regard, Please feel free to revert back to us.

We now look forward in receiving your positive reply on this proposal enabling us to proceed further.

Thanks & Best Regards,

Ravindra Rothe
Director – Sales & Marketing
Warade PackTech Pvt. Ltd.
(Formerly Known as Warade Automation Solutions Pvt. Ltd.)
4 To 9 & 14 To 17, Dhadge Estate, Survey No.14, Nanded Village,
Sinhgad Road, Pune – 411 041. Ext. 203 Mob: +91 98222 67494
Tele.: 020-24393780 / 83088 49211 / 12 / 13.
Web: www.warade.in, www.checkweigher.in,
Email: ravi@warade.in, sales@warade.in

1. REQUIREMENT:

Secondary & Tertiary Packing – For Up to 10 Secondary Pouches/Min

- String MAT transfer inclined conveyor, turn table & manual collation.
- Packing of collated string MAT into LDPE bags, transfer through cleated conveyor to pick fill seal machine.
- Check weigher for LDPE bag.
- Packing of LDPE bags in to HDPE bag.
- Portable stitching machine for HDPE bag.

2. DATA FROM CUSTOMER:

ANNEXURE 1

Primary packaging					Secondary packaging					
SKU (g)	Type of Packaging	Speed primary Pouch/min	Pouches/String	No of Strings/Min	Type of packaging	No of strings per Sec. pack	No of Pouches	Wt of Sec. Pack Gms	Speed of sec. pack formation	X4 Machines
8	Laminate center sealed Pillow pouch	100	10	10	LDPE Film	6	60	480	1.66	6.64
10	Laminate center sealed Pillow pouch	100	10	10	LDPE Film	6	60	600	1.66	6.64
12	Laminate center sealed Pillow pouch	100	10	10	LDPE Film	5	50	600	2	8
20	Laminate center sealed Pillow pouch	100	10	10	LDPE Film	6	60	1200	1.66	6.64





- Product/pouch dimension - 100mm X 80mm (8gm pouch)
- 4 head FFS machine in which string MAT of 1X10 i.e. 10 or 5 pouches are coming out from single chutes.
- Pouch variants weight – 8, 10, 12, 20 gm.
- MAT L * W * – Customer to confirm.
- Total speed of the machine is 100PPM X 4 i.e. 400PPM maximum for 8gm pouch.
- String MAT of 1X10 is collated manually. MAT matrix customer to confirm.
- In one LDPE bag 6 or 5 MATS will be packed.
- Manually leaflet insertion in LDPE bag.
- LDPE bag dimension – 355mm X 300mm
- HDPE bag dimensions -
  950mm X 350mm X 200mm (Gusseted) (10, 50, 100 & 200gm variants)
  1130mm X 350mm X 200mm (Gusseted) (Turmeric powder)
- Matrix in HDPE bag & position – Customer to confirm.

3. WARADE SCOPE OF SUPPLY:

LDPE bag packing machine consisting of below units for 8, 10, 12, & 20GM POUCHES ONLY & FOR UP TO 10 POUCHES/MIN.

- Take up conveyor.
- Turn table buffer unit.
- Cleated conveyor for collated strings
- LDPE bag packing machine - Pick fill seal machine
- Check weighing unit with rejection system for LDPE bags.

HDPE bag packing machine consisting of below units for 8, 10, 12, & 20gm pouches only.

- Conveyor for packed LDPE bag.
- LDPE bag counting & hopper dumping system.
- Manual loading of HDPE bag.
- Stitching machine for HDPE bag.

4. LIST OF BOUGHT OUT ITEMS:

- PLC and 5.7" HMI- AB.
- Pneumatics: Festo.
- Motor and Gearbox: Bonfiglioli.
- MOC: MS painted/ Powder Coated.
- Bearings: SKF.
- Control panel: MOC MS, Warade Manufactured.
- Air pressure at site required 5 to 7 bars.
- Flow wrap system
- Portable stitching machine – Revo

5. SEQUENCE OF OPERATIONS:

- Input to the system will be vertically dropped strips at 100PPM from 1 head. We will receive string MAT of 1X10 i.e. 10 pouches from one output chute.
- These strings will be conveyed using take up conveyor to turn table.
- The strings are manually collated and dropped into cleated conveyor. The required strings are dropped into a single cleat. A leaflet is manually inserted along with the strings.
- The cleat conveyor transfers the string to pick fill seal system for packing into LDPE bag.
- At the end of pick fill seal system the LDPE bag is weighed on checkweigher system before feeding into HDPE bag.
- LDPE bag counting is done before dumping into hopper for HDPE bagging.
- The HDPE bag - operator will load a empty bag to hopper unit & counted LDPE bags are transferred into HDPE bag.
- HDPE bag is stitched manually.

6. SCOPE OF WORK:

- Machine Design & manufacture
- Assembly
- Trials
- Commissioning
- Training.

7. CUSTOMER SCOPE:

- Consumables.
- Air piping & air source,
- Input power supply to the control panel.
- All civil work & foundation,
- Unloading on site & storing of materials on receipt will be customer's responsibility.
- Material handling equipments at the site,
- Samples of all variants: FOC to our plant for trials.

NOTE: We are submitting budgetary offer, offer will be revised after actual physical verification of pouch, string, LDPE bag & HDPE bag details, dimensions, quality & site visit.

BUDGETARY COMMERCIAL ASPECT

PROPOSAL NO: WARADE/QTN/16-17/2055 **DATE: 20/03/2017**

SR.NO.	DESCRIPTION	QTY	OEM PRICE INR
1	Secondary & Tertiary Packing of Sachet Pouch String – Up to 10 pouches/min only.		4,487,000
2	Commissioning & Site Supervision		100,000
3	Packing & Forwarding – Bubble Sheet Wrapping		50,000
4	Transportation to your plant		Extra to your account
	GRAND TOTAL		**4,637,000**

NOTE: THIS OFFER IS BASED ON ABOVE INFORMATION ONLY, ANY CONSTRAINT CAN ALTER THIS TECHNO COMMERCIAL SCOPE.

TERMS AND CONDITIONS:-

PRICE	Ex-works WPPL, Pune
PACKING & FORWARDING	Structure will be wrapped in bubble sheet.
TRANSPORT	Extra to be paid by Customer
TRANSIT INSURANCE	Customer scope
UNLOADING	Customer scope
EXCISE DUTY	Extra As applicable
SERVICE DUTY	Extra As applicable
CST/VAT	Extra As applicable, Current Rate is CST -2% against Form "C" If C form is not issued then 13.50% VAT will be applicable
LOCAL TAXES	Extra As applicable
QUOTATION VALIDITY	30days
SHIPMENT	12 - 14weeks from the date of receipt of PO and advance at WPPL. Commissioning period will be max. 3 to 4 days from date of actual start of work by WPPL Engineers, provided all pre-installation requirements are ready at site. Contract labor should be provided by customer and WPPL engineers will do supervision work during installation. Consideration – All technical data is being received by WPPL along with PO and there shall be no change in specifications till the end of project.
PAYMENT TERMS	• 50 % advance along with PO; • 40 % along with all taxes after FAT and before delivery. • 10 % after installation & commissioning immediately.

Thanks & Best Regards,

Ravindra Rothe
Director – Sales & Marketing
Warade PackTech Pvt. Ltd.
(Formerly Known as Warade Automation Solutions Pvt. Ltd.)
4 To 9 & 14 To 17, Dhadge Estate, Survey No.14, Nanded Village,
Sinhgad Road, Pune – 411 041. Ext. 203 Mob: +91 98222 67494
Tele.: 020-24393780 / 83088 49211 / 12 / 13.
Web: www.warade.in, www.checkweigher.in,
Email: ravi@warade.in, sales@warade.in