NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

SPACONS EPC Pvt.Ltd.
52 & 53, 1st Floor, Aditya Shagun Mall
NDA-Pashan Road, Bavdhan
Pune – 411 021

Date : 25.09.2020
Quote NO : SQT.20.21.2720 R
Kind Attn : Mr.Raghvendra , Mr.Avinash Hole
Email Id : avinashhole@spacons.com
Contact No: **7020775427**

Project Name & Location: Faurecia, Chakan

Subject : Quotation for GI Rolling Shutter

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	NIHVA Make GI Motorised Rolling Shutter (Single Skin - Indirect Drive Motor)	4500	5000	1	185,000	185,000	20,000	20,000
				Total		**185,000**		**20,000**
2	P&F Charges			0%		-		
	Total Without Taxes					**185,000**		**20,000**
	GST Extra @ 18%			18%		33,300		3,600
	Total With Taxes					**218,300**		**23,600**
3	Transportation Charges					**In Client Scope**		
4	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

GI Motorised Rolling Shutter

Sr .No.	Specification	Motorized Rolling Shutter
1	Description:	Motorised Rolling Shutter with GI Laths with thickness of 1 mm.
2	Mounting Location area	Inside area / Outside area
3	Mounting Surface	Side Brackets: Optional = On Concrete /Steel & Side
4	Curtain Panel	The panel made of 1.0mm thick MS.
5	Curtain panel size	75mm wide
6	Curtain Profile	Curved
7	Bottom Profile	M. S. Plate 140 mm x 2.5 mm thick
8	Side Guide Profile	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	Side Brackets	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	Hood Cover	Made of GI Sheet Thickness 0.9 mm GF mm with 25x25x3mm
12	Surface finish	Powder coated
13	Drive Unit & Mounting Type	Indirect Drive, Electric Motor - Direct Mounting - Sprocket chain arrangement
14	3 Station Push Button	Included

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope
8	Electrical - Input supply =230 volts ,single phase 3 core x 2.5 sq.mm cable required Cable length – depend on end client site and electric supply	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 3 -4 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment :

Option 1	20 % advance alongwith techno commercially clear PO ; 10% alongwith GA drawing ; 30% against material readiness and before dispatch 10% after Inspection 10% on Site readiness 20% immediate after Installation	**Option 2 :**	40 % advance alongwith techno commercially clear PO 10% alongwith GA drawing 20% against material readiness and before dispatch 5% after Inspection. 5% on Site readiness 20% immediate after Installation

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For additional 12 months INR 10,000/- will be applicable extra

For any further Clarification /Information in this Concern, Please feel free to Contact **Ms. Sneha Bharane on 8551035333**

With Best Regards
Smita Khare
9637991333
For NIHVA Technologies Pvt Ltd