NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Finearc Systems Pvt. Ltd
21, F-2 Block, MIDC, Pimpri
Pune - 411018
Maharashtra, India

Date : 03.11.2020
Quote NO : SQT/20-21/0030R3
Kind Attn : Mrs Minal Kelkar
Email Id : meenal_kelkar@finearcsystems.com
Contact No: +91 9822431753

Subject : Quotation for High Speed Door RP300 - Ex Works Germany

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR (Ex Works Germany)		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Albany make Machine Protection Door RP300**	2000	2000	3	4,75,000	14,25,000	In client scope	
				Total		**14,25,000**		-

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Sr. No	Description	Details
		Albany make Machine Protection Door RP300
1	Door version:	**Vertical Rapid Roller Door for machine protection.**
2	Side Frames:	**Aluminum anodized two parts, to have easy access to switches and service.**
3	Door blade:	**Rolltex Plus Curtain with RAL Blue 5002**
4	Bottom beam	**Aluminium anodized.**
5	Drive unit:	**Drive unit IP 55, either RH or LH as an option, with control cable (standard length = height of door)**
6	Opening / closing speed:	**Approx. max. 2,4 / 1,7 m/s**
7	Control system:	**MCC Vector Control**
8	Power suppy:	**3/(N)/PE 230/380/400/415 V, 50 Hz**
9	Safety features:	**Safety edge with cable chain integrated in side frames, pre running photocell.**
10	Safety features:	**Pre Running Photocell**
11	Safety limit switch:	**1 Schmersal safety limit switch PL e EN ISO 13849-1, SIL 3 EN 62061 on drive side integrated in the side frame to save space.**
12	Window Type	**700 x 500 mm Anti UV Type**
13	Window Qty	**1 No**
14	Hood Cover	**Top roll cover anodized aluminium**
15	Motor Cover	**Motor cover, powder coated silver (RAL 9006) for standard drive unit.**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1. Above prices are excluding all other structural members required for installation of the door and Taxes.
2. Complete structural design, build are in client scope.
3. **Above prices are Ex Works prices which are without any Freight, Custom duty, Custom Clearance, Local Transport**
4. **Above prices are of only Supply Charges.**
6. **Supply PO will be generated in the name of - " ASSA ABLOY Entrance Systems - Am Mondschein 25-D-59557 Lippstadt "**
5. **Installation charges will be extra Rs. 20,000/Each Door**

D) Terms & Conditions

Price	: Ex Works Germany
Delivery	: 5 - 6 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.
Payment	: 100% Advance along with Confirmed Purchase Order.
Validity	: Validity of Offer is 15 days from the date of quotation
Warranty	: 12 months from the date of supply.

Please feel free to Contact **Mr. Vijay Tarak on 8551093333** For any further Clarification /Information in this Concern.

With Best Regards
Arjun Patil
8551096333
For NIHVA Technologies Pvt Ltd