
Mantion S.A.S.
Mumbai Branch Office (Registered Office)
A-204, Girnar Towers, G.D. Ambekar Marg, Opp. P.T. Road Post Office, Ambawadi, Kalachowki, Mumbai – 400033. India. Tel: +91 (022) 24 71 81 33.
Warehouse: CCI Logistics Park, Survey No-123A, Village Kolkhe Palaspa Phata, Panvel, Raigad District, Navi-Mumbai - 410206, Maharashtra. India.

QUOTATION

Date: 25th April, 2016	**Quotation Number:**
NIHVA Technologies Pvt. Ltd	**Delivery Address**
Samir plaza, 1st floor, G block, Thermax Chowk, Chinchwad, Pune - 411019. Tel: +91 20 6630 4033.	Delivery address to be mentioned in detail with comments if any
Kind Attn.: Mr. Vijay M Tarak (Mob: 855 109 1333)	

Code	Product Description	Image	Price	Quantity	Total (INR)
Cantilever Gate: 8m clear opening. Maximum Weight 650kgs in the opening. Total width 12m. Total weight of the gate 894kgs					
9070/600	Galvanised Steel Track of 6 metres. 90mm x 110mm. **Zmg200 protection.**		40177.20	2	80354.40
9978PAF	Hanger for cantilever gate with steel wheels mounted on ball bearings with backlash adjustment		34421.40	2	68842.80
1070E	End guide - required for resting the gate. One each on either end of the gate		1981.80	2	3963.60
1071G	End wheel - required for resting the gate. One each on either end of the gate		3356.40	2	6712.80
1065L35	Adjustable long upper guide with four adjustable nylon olives, Ø 40 for 40 to 105 mm tube. Length : 350 mm.		4329.00	2	8658.00
1314SO	Narrow cane bolt 23 mm. Welding type Length : 300 mm - Ø 14 mm.		1344.60	1	1344.60
1297	Steel Handle on plate		1035.00	1	1035
				Sub Total	170911.20
				Add: VAT	21363.90
				Total	192275.10
				Add:	0.00
				Grand Total	**192275.10**

E&OE

Note: Taxes and other government levies (Octroi/LBT) additional as applicable. CST @ 2% will be applicable on submission of 'C' form in advance only. Else a deposit equivalent to 12.5% CST will have to be given which will be refunded.

Payment Terms: 100% Advance with Purchase Order or written confirmation with approval on quotation and Annexure - 1
Annexure - 1: Please refer to the Annexure 1 for terms and conditions of sale
Payment to be issued in the name of **"Mantion SAS"**
Note: At no given point of time the order once given can be revoked or advance payments will be refunded.
***Octroi/Levies:** This amount will be levied at actual as per the Octroi Invoice. Amount is for indicative/understanding purposes.
Delivery: Within 2 weeks from the date of PO or advance payment whichever is later.
Price Validity: 30 days from the date of the quotation
Transportation: NOT included in the cost.
Installation: NOT Included in the cost.
Civil Work: Required for installation will be carried out by the client. We will give the specifications for the same.
Wiring: Electrical wiring for providing single/three-phase supply though a separate MCB up to point of installation will be done by the client. Cable Conduit & Cable trays required for installation of accessories will be provided by the client. Client shall provide a stabilized, uninterrupted power supply with a Voltage stabilizer /spike buster to the automation system.
Standard Packaging: Included in cost. Special request of packaging will be additionally charged.
Loading Unloading at site: Not included in the cost. To be managed by the client.
All the sliding systems from Mantion SAS, France adhere to EN 1527 standard. The products covered by this document are of CE preferential origin, except where otherwise clearly indicated.
The use and implementation of the analyses come under the sole responsibility of the user, who alone is obliged to check the implementation specifications.