NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

JMC Projects (India) Limited
Kalpataru Synergy, Opp. Hotel Grand Hyatt,
Santacruz (E), Mumbai 400 055

Project, Location :

Date : 20.02.2021
Quote NO : SQT.20.21.3045
Kind Attn : Muzaffar Madni
Email Id : muzaffar.madni@jmcprojects.com
Contact No: 8291349534

Subject : Quotation for Rolling Shutter, Sliding Gate and Automatic Sliding Glass Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Gear Operated Rolling Shutter**	4000	4000	1	107,000	107,000	20,000	20,000
2	**Gear Operated Rolling Shutter**	4000	5000	1	126,000	126,000	20,000	20,000
3	**Automatic Sliding Glass Doors**	1740	2100	2	260,000	520,000	20,000	40,000
4	**Motorized Single Leaf Sliding Gate**	12000	2000	1	505,000	505,000	20,000	20,000
	Total			**5**		**1,258,000**		**100,000**
5	P&F Charges			3%		37,740		
	Total Without Taxes					1,295,740		100,000
	GST Extra @ 18%			18%		233,233.20		18,000
	Total With Taxes					**1,528,973**		**118,000**
6	Transportation Charges					Extra at atcual		
7	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Gear Operated Rolling Shutter

Sr .No.	Specification	MS Gear Operated Rolling Shutter
1	**Description**	Gear Operated Rolling Shutter with MS slats with thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete
4	**Curtain Panel**	The panel made of 1.0mm thick GI.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick.
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm GF mm
11	**Surface finish**	2 Coats (each coat of 35 microns DFT) of EPOXY polyamide-based enamel finish of approved color and make over a Coat (each one coat 25 microns DFT) of EPOXY polyamide based red oxide zinc phosphate primer
12	**Operation**	Gear Assembly.

Motorized Single Leaf Sliding Gate

Sr .No.	Specification	Motorized Single Leaf Sliding Gate
1	Door type	Motorized Sliding Gate
2	Opening Direction	Horizontal - from left to right or reverse
3	Mounting Location area	Inside area
4	Design Pattern	Standard Tubular Design Pattern
5	Outer Tube	72 x 72 x 3.2mm MS SQ. TUBE
6	For Post	72 x 72 x 3.2mm MS SQ. TUBE
7	Innear Tube	38x38x3.20mm/40x40x3.2 MS SQ. TUBE
8	Gap Between Tubes	125mm
9	Bottom Rail on ground	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
10	Bottom Rollers	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
11	Guide Rollers supporter during Gate movement	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
12	Painting	2 Coats of EPOXY polyamide based enamel finish of approved colour
13	El motor make	BFT – Italy (100% imported)
14	Emergency Operation	Manual after turn the switch
15	Operating Switch	Push Button from inside
16	Safety	Photocells, Flashing Light

Sr .No.	Specification	Automatic Sliding Glass Door
1	**Operator Type**	Bi part operator.
2	**User Modes**	Auto, Open, In,Out, Locked, Partial opening
3	**Operator Dimension**	125 x 168 mm
4	**Installer Settings**	Opening speed, Closing Speed,Hold Open Time, Half Opening distance, Opening, Direction, Installer Password, User Password
5	**Obstacle Detection**	Permanent obstacle detection in both opening and closing cycles
6	**Surface Treatment:**	Silver Anodized
7	**Safety**	3D infrared curtain Photocell, Radar, opening radar with integrated curtain photocell, Energy saving EN16006
8	**Glass**	12 mm Toughened Glass
9	**Interlocking**	Two doors can be operated using interlocking mode
10	**Compatibility**	Compatibilty with Fire alarm and access control system
11	**Energy Saving**	Short braking distance during opening and closing cycle for Energy saving
12	**Fault Monitoring**	Error codes are shown on the digital position selector screen
13	**Class of Protection**	IP 22

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Shrikant Mirkute on 8551098333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd