A37 Design, fabrication, supply, erection, testing and commissioning of factory fabricated four leaf horizontal telescopically sliding (for both ways : left and right) steel door with motorised operation for a clear opening size as mentioned below with suitable overlap alround as per the following specifications.

a) The door shutter frames shall be fabricated with suitable structural steel members (vertically/ horizontally /diagonally) covered with 3.15mm thick MS skin plate for the outside of the shutter and 2mm thick MS skin plate for inside of the shutter. The doors shall be designed and fabricated suitably to withstand the prevailing wind pressure at APEP Aluva.

b) The door frame structure shall be provided with suitable wheel assemblies, jacking plates, motor and gear fixing platforms etc.,

c) The door shall be provided with suitable wheel assemblies at the bottom with forged and machined wheels, bearings, shafts, grease nipples, cover plates etc., and necessary bright square bar rail laid along with suitable supporting beam / channel embedded in the floor as required and complete.

d) The door shall be provided with necessary top guide arrangement including guide rollers with bearing, shafts, structural steel Beams/Channels, Plates, Brackets etc., for smooth movement of the doors as required and complete.

Item No	Description of Item	Quan
	e) The doors shall be provided with necessary driving mechanism with suitable capacity 3 phase motor, gearbox, couplings, shaft, limit switches, stoppers, control panel and locking arrangement. The control panel shall consist of open, close push buttons and emergency stop push button etc., as required and complete. The door shall be operated at a speed of 5m/min. The control panel shall be located at suitable location to enable the operator to have full view of the area during operation of the door. The control panel shall be provided with key switch to prevent un-authorised operation of the door. The door shall have provision for manual operation in case of power failure. f) The doors shall be provided with necessary DSL cabling (festoon type) and wheel trolley arrangement running on separate track with push button starters and end limit switches with additional safety sensors and overload safety relay for motor etc., as required and complete. g) The door shall be provided with necessary airound rubber padding to make the system airtight and dust proof in closed condition. h) The entire door shall be furnished with two or more coats of Epoxy Paint of approved colour as per manufacturers specifications including one coat of epoxy primer after preparation of the entire surface and complete. The entire work shall be executed and completed as required and as directed by Engineer in Charge. Note : The successful tenderer shall submit detailed design and drawings pertaining to all the Mechanical / Structural components of doors for department's approval before fabrication of the doors.	
	i) Door clear opening upto 14000 x 5000mm (Four leaf)	1.00

A38 Design, fabrication, supply, erection, testing and commissioning of factory fabricated two leaf horizontal telescopically sliding steel door with motorised operation for a clear opening size as mentioned below with suitable overlap alround as per the following specifications.

a) The door shutter frames shall be fabricated with suitable structural steel members (vertically/ horizontally /diagonally) covered with 3.15mm thick MS skin plate for the outside of the shutter and 2mm thick MS skin plate for inside of the shutter. The doors shall be designed and fabricated suitably to withstand the prevailing wind pressure at APEP Aluva.

b) The door frame structure shall be provided with suitable wheel assemblies, jacking plates, motor and gear fixing platforms etc.,

c) The door shall be provided with suitable wheel assemblies at the bottom with forged and machined wheels, bearings, shafts, grease nipples, cover plates etc., and necessary bright square bar rail laid along with suitable supporting beam / channel embedded in the floor as required and complete.

d) The door shall be provided with necessary top guide arrangement including guide rollers with bearing, shafts, structural steel Beams/Channels, Plates, Brackets etc., for smooth movement of the doors as required and complete.

e) The doors shall be provided with necessary driving mechanism with suitable capacity 3 phase motor, gearbox, couplings, shaft, limit switches, stoppers, control panel and locking arrangement. The control panel shall consist of open, close push buttons and emergency stop push button etc., as required and complete. The door shall be operated at a speed of 5m/min. The control panel shall be located at suitable location to enable the operator to have full view of the area during operation of the door. The control panel shall be provided with key switch to prevent un-authorised operation of the door. The door shall have provision for manual operation in case of power failure.

f) The doors shall be provided with necessary DSL cabling (festoon type) and wheel trolley arrangement running on separate track with push button starters and end limit switches with additional safety sensors and overload safety relay for motor etc., as required and complete.

No

g) The door shall be provided with necessary airound rubber padding to make the system airtight and dust proof in closed condition.

h) The entire door shall be furnished with two or more coats of Epoxy Paint of approved colour as per manufacturers specifications including one coat of epoxy primer after preparation of the entire surface and complete.

The entire work shall be executed and completed as required and as directed by Engineer In Charge.

Note : The successful tenderer shall submit detailed design and drawings pertaining to all the Mechanical / Structural components of doors for department's approval before fabrication of the doors.

i) Door clear opening upto 7000 x 5000mm (Two leaf)