NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

WAGO Private Limited
C-27, Sector-58, Phase-III, NOIDA
Uttar Pradesh-201301, India

Date : 25.03.2020
Quote NO : SQT.19.20.2374R2
Kind Attn : Mr. Sachin Sharma
Email Id : Sachin.Sharma@wago.com
Contact No: **9999181989**

Subject : Quotation for Sectional Door, High Speed Door & Double Wall Rolling Shutter

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2, 3, 4
C.	General Conditions	5
D.	Terms & Condtions	5

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	High Speed Door (ASSA ABLOY - Albany)	4000	4500	7	6,59,000	46,13,000	15,000	1,05,000
2	High Speed Door (ASSA ABLOY - Albany)	3000	4000	3	6,07,000	18,21,000	15,000	45,000
3	Sectional Door (ASSA ABLOY - Crawford)	4000	4500	10	3,03,000	30,30,000	15,000	1,50,000
4	Sectional Door (ASSA ABLOY - Crawford)	3000	4000	1	2,53,000	2,53,000	15,000	15,000
5	Double Wall Rolling Shutter (100% Imported)	4000	4500	2	6,78,000	13,56,000	15,000	30,000
6	Dock Leveller (ASSA ABLOY - Crawford) **Capacity 6 T**	2000	2500	3	3,47,000	10,41,000	15,000	45,000
	Total for Product (1, 2, 3, 4, 5,6)					**1,21,14,000**		**3,90,000**
	P&F Charges			0%		-		
	Total Without Taxes					**1,21,14,000**		**3,90,000**
	GST Extra @ 18%			18%		21,80,520		70,200
	Total With Taxes					**1,42,94,520**		**4,60,200**
	Total Supply + Installation with Taxes							**1,47,54,720**
7	Transportation Charges			**Extra**		**Rs 170,000**		
8	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

ASSA ABLOY High Speed Door



Sr. No.	Description	Specification
1	Door type	RR300 Plus
2	Description	Flexible High Performance Door, opening in vertical direction for interior use in wind-protected areas
3	Side frames	Made of Steel
4	Door curtain	Made of transparent PVC with fabric reinforcement stripes, ultramarine (similar to RAL 1021)
5	Top roll	Made of anodized aluminum
6	Wind protection	wind tabs on the door curtain
7	Wind resistance	Class 1 (EN 12424).
8	Bottom profile	anodized aluminum
9	Drive unit	Hollow shaft gear motor
10	Protection	IP 55
11	Control system	Frequency converter control system MCC Vector Control, based on vector control including boost function at start-up. Graphic
12	Supply voltage	3L(N)PE/380/400/415/440/480V;50/60Hz Transformer necessary for 220/230/500V
13	Safety devices	electrical safety contact edge, evaluation via integrated cable chain, door line photocell in the side frames, drop down
14	Manual activation	By releasing the brake at ground level. Depending on width/height ratio the door opens up to max. 2.0 m
15	Opening / closing Speed	(open/close) up to max. 2,2/0,9 m/s,
16	Magnetic loop detactor, Pull chord switch, Key switch, Aditional Push Button	Included
17	Safety Photocell, Light Grill sensor, Optical wired edge sensor	Included
18	Flashing Light with alaram & motor Cover	Included

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019


An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

ASSA ABLOY Motorised Sectional Door







Sr. No	Description	Specification
1	Model No	ASSA ABLOY OH1042P
2	Opening Direction & Mounting	Standard
3	Opening/Closing Speed	CDM9 0,28 m/s
4	Door Material	Steel
5	Panel Thickness	42 mm Square Grid, steel sheet
6	Filling	CFC-free polyurethane
7	Door sealent	All door sealants made of EPDM rubber, temperature resistant -3
8	Water Penetration	EN 12425 class 3
9	Air Permealibity	EN12426 class 3
10	Thermal Transittance	EN 12428 1.10W /m2K
11	Bottom sealing	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber
12	Door saftey	Doors equiped with spring break device
13	Incase of Power failuer	Doors to be equiped with quick release fuction
14	Operator power conumption	Operator to have a maximum power consumption of 0,37kW and a standby consumption of Maximum 15W
15	Drive Unit & Mounting Type	Single phase 230V direct drive on shaft
16	Emergency Operation	by Disengagement rope manual
17	Operating Switch	Up/Down Keypad + stopbutton
18	Locks : Lock bolt	The Lock bolt locks the door from the inside, without the use of a key. The Lock bolt is not visible from the outside.
19	Environmental Green Product Declaration Certification	As per ISO 14025 and EN 15804
20	Structure	Included
21	Safety Photocell & Optical wired safety edge sensor	Included

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

Double Wall Rolling Shutter (100% Imported) From Germany



Sr. No.	Description	Specification
1	Roller. D Curtain profile Type	Thermo Teck Steel Filled with Pu Foam
2	Size	4000mm (W) X 4500mm (H)
3	Roller door Surface outside	Galvanised with Protective fill
4	Building Structure	Concrete
5	Buttom profile	ET-1 for Teckentrup Thermotreck
6	Guide Rail	FS 85 Steel
7	Drive Type	Direct drive TAR 3.30KU 400 V/Ph AWG 12U/min; Ip54; 60% ED
8	Drive Mounting	Inside Left, Standing
9	Emergency Drive Operation	Emergency Hand Crank
10	Control Unit	CS 310 (Dead Man) With Built in Triple button CEE Plug with Wire
11	Wind Load Class	Wind Load Class Resistance Class 2

NIHVA ASSA ABLOY Dock Leveler

Sr no	Description	Unit	Specification
1	Basic Capacity	kg	6000
2	Dock Leveler Size Length	mm	2500
3	Dock Leveler Size Width	mm	2000
4	Dock Leveler Size Height	mm	600 / 700
5	Working Range Above/Below	mm	(+)520/ (-)350
6	Slope	degree	0.125
7	Tilt Compensation	mm	100
8	Lip size	mm	2000(w)X400(L)
9	Power Pack	Hp	1 HP
10	Control Panel operating Push button details	Nos	Two push Button
11	Colour	RAL sed	RAL5010
12	Top Surface thickness in	mm	8
13	Lip Surface thickness in	mm	8
14	Power pack pump make ,type & model	NA	Assa Abloy
15	Control panel switch gear makes	Na	NA
16	Working pressure	Bar	100
17	Control panel IP protection	NA	IP54
18	Input supply Requirement	3 Phase voltage & Current	3 Phase - 400 volt, 2.5 A
19	PIT W L H	MM	2040 X2520X605
20	TRAILER HT CONSIDERED	M	1300
21	Hose Burst Value / NRV	NA	Included
22	Bumpers 2 nos	Nos	Included
23	Maintenance work safety stopper	NA	Included

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope
8	Steel structure for Dock House & Sectional Door	In Client Scope

D) Terms & Conditions

Price : For Site

Delivery : 10 - 12 weeks for High Speed Doors & Rolling SHutter, 16-17 Weeks for Dock Leveler & Sectional Door from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Bhavin Jain on 8551092333**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd