NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Ce

GST Pune : 27AAECI

NIHVA Sales Quotation

SUROJ BUILDCON PVT. LTD.
Bungalow No. 3, Liberty Society Phase-I,
North Main Road,
Koregaon Park, Pune 411 001,
Maharashtra, India.

Date : 04.09.2019
Quote NO : SQT/19-20/2013
Kind Attn : Kamini Karma
Email Id : kkarma@suroj.in
Contact No: 020 41355999

Subject : Quotation for Rolling Shutter,Motorized Sliding Gate and Wicket Gate. (Project - Hiranandani Group, Chennai's Oragadam)

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Cl
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price
1	MS Motorized Rolling Shutter	3000	3000	1	86,000	86,000	20,000
2	MS Motorized Rolling Shutter	5000	5000	20	1,91,000	38,20,000	20,000
3	MS Motorized Rolling Shutter	7000	8000	12	4,17,000	50,04,000	20,000
4	MOTORISED SINGLE LEAF SLIDING GATE	6000	1800	4	3,91,000	15,64,000	20,000
5	WICKET GATE	1000	2400	1	31,000	31,000	10,000
				Total		**105,05,000**	
6	P&F Charges			3%		3,15,150	
	Total Without Taxes					108,20,150	
	GST Extra @ 18%			18%		19,47,627.00	
	Total With Taxes					**127,67,777**	
7	Transportation Charges					In Client Scope	
8	Unloading Charges @ Site					In Client Scope	

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Ce

GST Pune : 27AAECI

B) Technical Specification

Sr .No.	Specification	MS Motorized Rolling Shutter
1	Description:	Motorised Rolling Shutter with MS Laths with thickness of 1 mm.
2	Mounting Location area	Inside area / Outside area
3	Mounting Surface	Side Brackets: Optional = On Concrete /Steel & Side
4	Curtain Panel	The panel made of 1.0mm thick MS.
5	Curtain panel size	75 mm wide
6	Curtain Profile	Curved
7	Bottom Profile	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	Side Guide Profile	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	Side Brackets	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	Hood Cover	Made of GI Sheet Thickness 0.9 mm GF mm with 25x25x3mm angle stiffener
12	Surface finish	PU paint or Powder coated
13	Drive Unit & Mounting Type	Electric Motor - Indirect Mounting - Hand Crank

NIHVA make – Motorized Sliding Gate	
Door type	**Motorized Sliding Gate**
Clear Opening gate dimension	(W) 6000 x (H) 1800…in mm
Opening Direction	**Horizontal - from left to right or reverse**
Mounting Location area	Inside area
Design Pattern	Standard Tubular Design Pattern
Outer Frame Tube Sizes	72x72x3.2mm MS SQ. TUBE
Internal Vertical Tube Sizes	40x40x2mm MS SQ. TUBE
Gap Between Tubes	125mm
Bottom Rail on ground	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
Bottom Rollers	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
Guide Rollers supporter during Gate movement	**Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate**
Painting	2 Coats of EPOXY polyamide based enamel finish of approved colour
El motor make	BFT – Italy (100% imported)
Emergency Operation	Manual after turn the switch
Operating Switch	Push Button from inside
Safety	Photocells, Flashing Light
Metal Rack	zinc plated metal rack

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Ce

GST Pune : 27AAECI

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the T

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 5 - 6 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Arjun Patil on 8551096333** For any further Clarification /Information in this Concern.

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd

ertified Company

N0437H1ZM

harges in INR

Total Amount
20,000
4,00,000
2,40,000
80,000
10,000
7,50,000
7,50,000
1,35,000
8,85,000

ertified Company

N0437H1ZM

ertified Company

N0437H1ZM

Team.