NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

RIL
Mumbai.

Project, Location : Vrindavan, Mumbai

Date : 03.08.2021
Quote NO : SQT.21.22.0009R4
Kind Attn : Bhrigu Kalita
Email Id : Bhrigu.Kalita@ril.com
Contact No: 7718815452

Subject : Revised Quotation for Single Leaf Sliding Gate and Wicket Gate

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Automatic Single Leaf Sliding Gate**	3900	2000	1			Inclusive	
2	**Automatic Single Leaf Sliding Gate**	3500	2000	1			Inclusive	
3	**Bi-Parting Swing Gate**	3500	2000	1			Inclusive	
3	**Manual Sliding & Folding Gate**	5500	2000	1			Inclusive	
4	**Manual Wicket Gate**	1400	2000	1			Inclusive	
	Total			**5**		-		-
5	P&F Charges			0%		-		
	Total Without Taxes					-		-
	GST Extra @ 18%			18%		-		-
	Total With Taxes					-		-
6	Transportation Charges					Inclusive		
7	Unloading Charges @ Site					Inclusive		

NIHVA TECHNOLOGIES PVT. LTD.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NOTES

Gate motor selection done by considering weight of both side cladding of 100kg/m2 & gate height of 4.5 meter .

Provided gate weight estimation is only for gate height of 2000 mm.

Gate sections are considered at approx. 1000 mm along length & height . If special design needed, kindly share layout of gate leaf .

All Cladding material , fixing & work related to cladding is in client scope .

If any changes required in gate leaf for cladding , additional cost will be required . Provided cost is only for gate leaf & automation system .

For modification of gate height to 4500 meter , additional cost will be required .

Gate finish - Hot deep galvanising of 80 Micron

Automation has been considered as per 4.5 meter height. (Except Sliding & Folding gate height will be 2000mm)

B) Technical Specification

Motorized Single Leaf Sliding Gate

Sr .No.	Specification	Motorized Single Leaf Sliding Gate
1	Door type	Motorized Sliding Gate
2	Opening Direction	Horizontal - from left to right or reverse
3	Mounting Location area	Inside area
4	Design Pattern	Standard Tubular Design Pattern
5	Outer Tube	150X150X4 MS SQ. TUBE
6	For Post	150X150X4 MS SQ. TUBE
7	Innear Tube	100x100x4 MS SQ. TUBE
8	Bottom Rail on ground	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
9	Bottom Rollers	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
10	Guide Rollers supporter during Gate movement	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
11	Surface Finish	HDG80 Micron
12	El motor make	NICE – Italy (100% imported) with 4 TON Capacity
13	Emergency Operation	Manual after turn the switch
14	Operating Switch	Push Button from inside
15	Safety	Photocells, Flashing Light, Vertical Safety Edge and Heavyweight bearings to take load of 3 ton
16	Accessories	Remotes

Wicket Gate

Sr .No.	Specification	Wicket Gate
1	Door type	Manual Single Leaf Wicket Gate
2	Size considered	Clear opening - (W)1400 mm x (H)2400 mm & (W)1400 mm x (H)2100 mm
3	Mounting Location area	Inside area
4	Design Pattern	Standard Tubular Design Pattern
5	Outer Tube	150X150X4 MS SQ. TUBE
6	Innear Tube	100x100x4 MS SQ. TUBE
7	Surface Finish	HDG80 Micron
8	Operation	Manually Opening

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price	: Ex Works Mumbai
Delivery	: 8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.
Payment	: 40% Advance (against non-dated Cheque of equal amount in the name of Issuing company valid till material received at site) + 50% Immediate after delivery (within 3 days) + 5% against installation + 5% Retention for 12 months from the date of Installation (can be released against submission of PBG)
Validity	: Validity of Offer is 15 days from the date of quotation
Warranty	: 12 months from the date of supply for electric motors and 24 months for Structures.

Please feel free to Contact **Mr. Shrikant Mirkute on 8551098333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd