NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No -SQT/16-17/0528 **Date : 02-02-2017**

Siemens Limited
E-76, Waluj MIDC Area,,
Aurangabad
Maharashtra,India

Kind Attn : Mr. Vipul Kulkarni
Email : Vipul.kulkarni@siemens.com
Contact : 9960635441

Subject : Quotation for Maintainanace Platform, Bowl Feeder, Conveyors & Scissor Lift tilting mechanism

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.This has reference to your above mentioned requirement as well as our subsequent communication.Please find below our best offer.

Commercial Offer

Sr. No	Description	Qty	Unit	Rate In INR	Net Amount INR
1	**Maintainance Platform** **Specifiations :** > Size : 1000 x 1000mm > Platform Height : 5000mm > Extention : Horizontal-750mm > Capacity : 250Kg	1	No.s	3,90,000.00	3,90,000.00
	Total				**3,90,000.00**
2	Vibratory Bowl Feeder with Height Adjustable Stand For Vibratory Feeder	1	No.s	95,000.00	95,000.00
	Total				**95,000.00**
3	**Scissor Lift for Tilting Mechanism** **Specifications :** > Platform Size : 700 x 500mm > Lifting Height : 1500mm > Close Height : 300mm with Locking System & claster Wheels	1	No.s	2,25,000.00	2,25,000.00
	Total				**2,25,000.00**
4	**Manual Conveyor**				
	Manual with Full Roller	1	Mtr	42,000.00	42,000.00
	Manual with Half Roller	1	Mtr	37,000.00	37,000.00
5	**Motorised Conveyor (Stop & Go Type)** > PU Coated Rollers on 100mm pitch. > Jumping Chain & sprocket arrangement. > Pneumatic stoppers at each station. > Authorization pendant at each station. > MS fabricated & painted side structure. > Side guide rails to guide pallet throughout length. > Levelling Arrangement. > Gear box & Motor for drive. > VFD for speed adjustment. > Control Panel (PLC) Delta > Proxy sensor on each station to sense port.	10	Mtr	5,00,000.00	5,00,000.00
	Total				**5,00,000.00**

6	PLC with field wiring & ducting	1	pc	1,05,000.00	1,05,000.00
	Total				**1,05,000.00**
7	**POP Station for both-Manual Conveyor & Motorised Conveyor :** **>** Ball cage arrangement for cross transfer **>** Total 40 No.s of Ball cage in 4 rows. **>** Hydraulic cylinder for lifting stroke 50mm **>** linkage Mechanism for lifting stroke 50mm **>** MS fabricator & parted standard **>** Provision for Integration	1	No.s	1,00,000.00	1,00,000.00
	Total				**1,00,000.00**
8	**Pallet** : Used for carrying Product (Suitable for conveyors with warepad on guilded conveyor track)	1	No.s	9500	9,500.00
	Total				**9,500.00**

VAT TIN :	27545250455 V
CST TIN :	27545250455 C
Service Tax No:	AAECN0437HSD001

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	@3% of Total Supply Value
3	**Freight Notes**	:	Extra as applicable + Taxes
4	**Delivery**	:	4-6 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% Advance alongwith Confirmed Purchase Order & Balance before dispatch
6	**Insurance**	:	Extra As applicable
7	**Sales Tax**	:	Extra as applicable at the time of dispatch. Presently @13.5% VAT (supply withing Maharshtra OR @2% CST against Form C (Outside Maharashtra)
8	**Service Tax**	:	Extra @ 15%
9	**Validity**	:	Validity of Offer is 15 days from the date of quotation
10	**Warranty**	:	12 months from the date of supply.

Please feel free to Contact **Mr.Mayur Derle** on 07709209333 For any further Clarification /Information in this Concern.

With Best Regards

Monika Kidgaonkar

020-66304033 / 08551091333

For Nihva Technologies Pvt Ltd