NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

DCM SHRIRAM
KOTA- RAJASTAN

Date : 06.11.2024
Quote NO : RR_24.25.0131
Kind Attn : Mr Anklesaria sir
Email Id : aanklesaria@dcmsr.com
Contact No: 9929590821

Project Name & Location: SPINY AREA

Subject : Commercial Offer for Manual operated Slidding frame.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	1
C.	General Conditions	2
D.	Terms & Condtions	2

A) Commercial Offer

Options	Description	Size (mtr)	Qty		
			(Nos)	Unit Rate	Total
1	**Manual operated slidding mechanism frame (Only Top track no bottom Track)**	• 10000 (L) X 1500 mm (HT) • 7 Panels • 3mm thick solid celar compact polycarbonate sheet • centre opening • Installation Inclusive	1	₹ 9,66,000	**₹ 9,66,000**
2	GST Extra @ 18%		18%		Extra
3	P&F Charges @ 3%		3%		Extra
4	Transportation Charges				Extra
5	Unloading Charges @ Site				Inclusive
6	Material Shifting Charges @ Site				Inclusive
7	Height/ Crane arrangement				In client scope

B) Technical Specification

1. 3mm solid clear compact polycarbonate sheet
2. Profile : 6063 series Aluminium
3. Guide : 6063 Aluminium Guide
4. Interlocking with High grade Nylon Material
5. EPDM Gaskets and sealants
6. SS Fastners
7. Special design of Bearing Housing Mechanism
8. SMC Shock Absorber Assembly at bottom of Aluminium frame.
9.Anodising Surface tratement for Aluminium Profile
10.With Polymide Handle.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1. Continuous uninterrupted access to installation section or as agreed seperately.
2. Provision of 230 V power supply for hand tools.
3. A dry and secure area, not in direct sunlight is to be provided for storage of product component
4. Access to site between 7 am to 8 pm should be provided.
5. Any storage costs for material due to delay outside of NIHVA, will be in client scope.
6. The project time indicated does not take into account adverse weather conditions that may prevent safe and efficient working practice. We reserve the right to extend the period accordingly.
7. Installation will start after receiving of Site Readiness Photographs or written Email communication.
8. We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation.
9. For any reason if we need to stop our installation and demobilize the team without completing the work, then extra cost will be applicable for Remobilizing the Team.
10. If any change in dimension on actual site, quoted price will affect accordingly which will be in client scope.
11. After 1 year warranty, Non comprehensive AMC will be provided by NIHVA at an additional cost.

Note: Please find below List which are in Client Scope

Sr. No	Points	Remark
1	Secured and fully covered Store area	Should be provided by client
	Safely Material Keeping in that Area	In NIHVA Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site.	In NIHVA Scope
3	One point of input single phase supply	Should be provided by client
	From that supply point to terrace area or roof mounting area- supply cable and electical point	In NIHVA Scope
4	Any civil / masonry/structural work required.	In Client Scope
5	In Case of any changes in the layout as per site requirements after the shipment of material, the additional quantities and wastage	NIHVA should be provided with extra cost
6	Conduits, Cables required	In NIHVA Scope

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 8-10 weeks from the date of receipt of confirmed Purchase Order, Advance Payment & Drawing Approval.

Payment : 70% Advance along with Confirmed Purchase Order.
25% After material Delivery at site.
5% After Installation.

Validity : Validity of offer is 15 days from the date of quotation.

Warranty : 12 months from the date of supply. It only covers damage caused due to mechanical system not due to natural calamity.

With Best Regards
Pranav Marne
7758820333
NIHVA Technologies Pvt Ltd