Sales Quotation

Quotation No - SQT/20-21/2722 R **Date : 28.09.2020**

PMG Engineering Private Limited
A-224, A Block, Sector 83,
Noida, Uttar Pradesh 201305

Kind Attn: Disha Sinha
Email: disha.sinha@pmg.engineering
Contact No: 8417932086

Project Name And Location : Big Muscle Protein Powder, Faridabad

Subject : Quotation for Z type Take up Belt Conveyor

Dear Sir
Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication. Please find below our best offer.

Commercial Offer

Sr. No.	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**Z type Take Up Conveyor** **(Supply + Installation)**				
	Technical Specifications : • Conveyor Type : Z type Conveyor • Product : Sack • Product Size : (L) 550 x (W) 350 x (H) 120 • Product Weight : 25 Kg • Product Capacity : 1.5 THP • Conveyor Infeed Height : 900 mm • Conveyor Outfeed Height : 900 mm (From mezzamine) • Contact Speed : Up to 5 mtr/min • Contact parts : MS Powder coated • Non Contact parts : MS Powder coated • Gear Motor : Bonfiglioli • Foot : Spectra type/ equivalent • Belt : PVC Green Belt (2M10-U0-V10) • Belt Make : Chiorino (Italy) • Belt Width : 450 mm • Conveyor Width : 600 mm approx • Finish : Powder coated • Conveyor height adjustment : 50 mm • Speed Control : Through VFD - optional	1	No	340,588	340,588
a)	**Z type Take Up Conveyor - With VFD** **(Supply + Installation)**				
	• Speed Control : Through VFD	**1**	**No**	393,588	393,588
B)	**Flat Belt Conveyor** **(Supply + Installation)**				
	Technical Specifications : • Product : Pouches & Bottles • Product Size : As per URS • Product Weight : As per URS • Product Capacity : As per URS • Conveyor Infeed Height : 900 mm • Conveyor outfeed Height : 900 mm • Conveyor Capacity : Up to 50 kgs • Conveyor Speed : Up to15 mtr/min • Contact Parts : MS Powder coated • Non Contact Parts : MS Powder coated • Gear Motor : Bonfiglioli • Foot : Spectra/ equivalent • Belt with Bottom K Profile : PVC Green Belt (2M10-U0-V10) • Belt make : Chiorino (Italy) make • Belt Width : 450 mm • Conveyor Width : 510 mm approx • Finish : Powder Coated • Speed Control : Through VFD Optional • Conveyor Height Adjustment : 50 mm • Side guard adjustment : 200 mm from each side	1	No	104,340	104,340
b)	**Flat Belt Conveyor - With VFD** **(Supply + Installation)**				
	Technical Specifications : • Speed Control : Through VFD	1	No	147,340	147,340
	Total				**985,856**

GST Pune	27AAECN0437H1ZM

TOTAL BASIC AMOUNT	**985,856**

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	3 % Extra as applicable
3	**Freight Notes**	:	Extra as applicable + Taxes
4	**Delivery**	:	6- 8 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% Advance along with Confirmed Purchase Order and Balance before Dispatch.
6	**Insurance**	:	Extra As applicable
7	**Taxes**	:	GST Extra as applicable
9	**Validity**	:	Validity of Offer is 15 days from the date of quotation
10	**Warranty**	:	12 months from the date of supply.

Please feel free to contact **Mr.Vijay Tarak - 8551093333** For any further Clarification /Information in this concern.

With Best Regards

Smita Khare
9673991333
For NIHVA Technologies Pvt Ltd