NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Indamer
Mumbai Operation Gate No. 8, Militry Camp,
Kalina, Santacruz (E), Mumbai - 400 029

Project, Location :

Date : 1.12.2021
Quote NO : SQT.20.21.2943
Kind Attn : Rohan Dhumal
Email Id : rohand@aarindamertechnics.com
Contact No: 9579622491

Subject : Quotation for Bollards

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Diameter (mm)	Shaft Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
	(Option-I)							
1	Hydraulic Bollard - shaft height 600 mm and diameter 275 mm -	275	600	16	525,000	8,400,000	20,000	320,000
2	PERSEO CBE 230.P SD: Control unit			4	90,000	360,000		-
3	Dual Channel Metal Detector			4	45,000	180,000		-
	(Option-II)							-
4	Electromechanical Bollard - shaft height 500 mm and diameter 219 mm.	219	500	16	275,000	4,400,000	20,000	320,000
5	PERSEO CBE 230.P SD: Control unit			4	90,000	360,000		-
6	Dual Channel Metal Detector			4	45,000	180,000		-
	(Option-II)							-
7	Semi-Automatic Bollards Operated by Gas Spring - shaft diameter 115 mm and height 500 mm.	115	500	16	145,000	2,320,000	20,000	320,000
	Total			**64**		**16200000**		**960,000**
8	P&F Charges			3%		486,000		
	Total Without Taxes					16,686,000		960,000
	GST Extra @ 18%			18%		3,003,480.00		172,800
	Total With Taxes					**19,689,480**		**1,132,800**
5	Transportation Charges					Extra at atcual		
6	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NOTE : **Every Bollards needs Civil Pits.**
Civil Pits work in Clients Scope.





Hydraulic Bollard - (Option-I)

Sr No	Description	Specification
1	Voltage	230v
2	Shaft height	600 mm
3	Shaft diameter	275
4	Raising time	5 sec
5	Operator type	hydraulic bollards
6	Control unit	PERSEO CBD 230.P SD
7	Breaking resistance	250000 J
8	Frequency of use	3000 op/day
9	Type of limit switch	reed magnetic sensor
10	Impact resistance	20000 J
11	Manual operation	reversible with no power
12	Ambient conditions	-40°C +60°C

Electromechanical Bollard - (Option-II)

Sr No	Description	Specification
1	Shaft diameter	219 mm
2	Shaft height	500 mm
3	Raising time	6 sec
4	Control unit	PERSEO CBD
5	Impact resistance	10500 Joule
6	Breaking resistance	150000 J
7	Slowdown	yes
8	Lock	electric brake
9	Manual operation	reversible with no power
10	Frequency of use	intensive 1500 movements per day
11	Ambient conditions	-20°C +60°C
12	Movement	with slowdown in opening and closing
13	Supply voltage	230v ± 10% 50/60 Hz

Semi-Automatic Bollards Operated by Gas Spring - (Option-III)

Sr No	Description	Specification
1	Shaft size	0115 mm H:500 mm
2	Shaft thickness	4 mm
3	Impact resistance	5000 Joule
4	Breaking resistance	30000 Joule
5	Shaft treatment	cataphoresis
6	Shaft movement	with internal gas spring
7	Surface finish	grey paint RAL 7015 + rear-reflecting film
8	Shaft locking	with triangle key
9	Operation	Each Bollard needs to operate manually

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Vijay Tarak on 8551093333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd