NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Narsi & Associates
522, Laxmi Mall, Bldg. No. 5, Laxmi Ind. Estate,
New Link Road, Andheri (W), Mumbai – 400 053.

Date : 26.02.2021
Quote NO : SQT.20.21.3025R2
Kind Attn : Gaurangi Kawali
Email Id : procurement@narsi.in
Contact No: 022-42505555 ext.529

Project Name & Location: PUNE

Subject : Revised Quotation for Pit Mounted Scissor Lift

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size	Qty	Supply Charges in INR		Installation Charges in INR	
		Working Platform (in mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Pit Mounted Scissor Lift**	(W) 2300 mm X (L) 3000 mm	1	615,000	615,000	Inclusive	
			Total		**615,000**		-
2	P&F Charges on Total Supply Value		0%		-		
	Total Without Taxes				**615,000**		-
	GST Extra @ 18%		18%		110,700		-
	Total With Taxes				**725,700**		-
3	Transportation Charges				**In NIHVA Scope**		
4	Unloading Charges @ Site				**In NIHVA Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification -

Pit Mounted Scissor Lift

Sr. No	Description	Specifications
1	Capacity	4.5 Ton
2	Platform size	(W) 2300 mm X (L) 3000 mm
3	Shut ht	600 mm
4	Max ht	2100 mm
5	Lift ht	1500 mm
6	Power pack	7.5PH 3Phase
7	Safety Railing	900 mm only at length side.
8	Hydraulic Lip	1100 x 1800 mm (one width side only)
9	Paint (RAL 1004)	Golden Yellow
10	Control Unit	Push button pendent on railing.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	NIHVA Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6 - 7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Ravindra Kharat on 7410169333.**

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd