Sales Quote

NIHVA TECHNOLOGIES PVT. LTD.

An ISO 9001:2008 Certified Company

Quote No: SQT.18-19.770 **Date:01/10/2018**

Arvind Cotsyn (I) Ltd

Gat no. 251 to 253, 248/1 & 263, Kolhapur Road,
Mangaon, Tal. Hatkanangale, Dist. Kolhapur
Kolhapur -
Maharashtra -India

Kind Attention: Mr. L D Yadav

Phone: +91-7972010860-
Email ID: ldyadav@acilich.com

Project Name And Location : Telescopic conveyor At Kolhapur

Subject : Quote for - Telescopic Conveyor

Dear Sir,

Thank you for your opportunity and trust shown on “NIHVA.” your preferred partner for innovative solutions.This has reference to your above mentioned requirement as well as our subsequent communication. Please find below our best offer.

Commercial Offer :-

Sl.No.	Description	Price	Qty	Total
1.	Telescopic Conveyor Conveyor Length :- 10 Meter Mechanical structure:- 1) MS Sq tube (50x50x3.2 Meter) 2) Ms Plates (90 kg) 3) Roller (Dia 60.3 x 1.6) (1000) 4) Chain (42 Meter) 5) Drive Motor (Bonfiglioli) (IE2) (4 nos) 6) Electrical Control Panel 7) Conveyor height from ground = 800 mm (Supply + installation)	₹ 1,827,500.00	2	₹ 3,655,000.00

Grand Total **₹ 3,655,000.00**

GST Pune	27AAECN0437H1ZM

General Pre requisite at site

1 Finished Flooring after curing (Without Water)
2 Electrical Supply on the site single phase/three phase points at different places
3 Provide electrical cables near to the installation machinery
4 Fork lift/crane to be provided if required

Sales Quote

An ISO 9001:2008 Certified Company

Quote No: SQT.18-19.770 **Date:01/10/2018**

5 Scaffolding require for Installation it is in client scope

Limit of Supply

1 Provide place to store the material to be installed
2 Be responsible for the safe custody of all material
3 Provide place to safely store all the tools of installation
4 Provide change & rest room for the workers

Quote/Supply is based on

1 BOM is calculated as per standard quantity measurement
2 In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account
3 Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1 Unloading from truck placement on site
2 Electrical connection for control panel

Client Scope

1 Once our project gets complete for any additional work to & fro loading & boarding of our service technicians is in client scope
2 Any civil / masonry/structural work required to support are in client scope
3 All structure support is in client scope
4 NIHVA Will provided structure drawing only if required
5 Existing/Repair/ Modification/ Refurbishment charges will be extra

Terms & Conditions
1 **Price** : Ex works Pune
2 **P & F Charges**: @3% of Total Supply Value
3 **Freight Notes**: Extra as applicable
4 **Payment**: 80% Advance along with confirm purchase order & Balance 20% before dispatch
5 **Taxes**: GST @ 18%
6 **Validity**: Validity of Offer is 15 days from the date of quotation.
7 **Warranty**: 12 months from the date of supply
8 **Delivery** : 10-12 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval
9 **Insurance :** Extra As applicable

Please feel free to Contact **Mr. Ravi Ranjan Prasad - +91-7709586333** for any further Clarification /Information in this Concern.

With Best Regards

Pratiksha Prajapati
+91-7219207333
For Nihva Technologies Pvt Ltd