WORK ORDER

NIHVA TECHNOLOGIES PVT. LTD.

Client:	
Ronak Buildwell pvt Ltd	
Address:	
B-1003/1004 , Empire Business Hub Opp.Shakti Arcade , Science city road Sola,Ahmedabad Gujrat India -380060	

PO Number:	RBPL/ABM/PO/202204/0001	W. O. No-	SO/22-23/001
PO Dated :	02-04-2022	W. O. Date	04-04-2022
PO Received Date:	02-04-2022	Sales Co ordinator	Pradeep Shinde
Ref. Quotation:	SQT.21.22.0354 R1	Front Sales Person	Yogesh Kulkarni

Dispatch Address:

AB Mauri India Pvt Ltd . Plot No 26/27 , Fanidhar Mega Food Park , Jotana , Mehsana Gujrat

A Technical Terms:

Sr. No	Description of Goods	Technical Details	UOM	Qty.	Supply Rate	Installation Rate	Total Amount	Dwg. Approval Status
1	GI Rolling Shutter 1.0 mm Motorised 3.0 x 3.0mtr Direct Drive Motor	**Description: Motorised** Rolling Shutter with GI Slats with thickness of 1.0 mm. **Mounting Location area :** Inside area / Outside area **Mounting Surface:** Side Brackets: Optional = On Concrete /Steel & Side **Curtain Panel:** The panel made of 1.0 mm thick GI **Curtain panel size:** 75mm wide **Curtain Profile:** Curved **Bottom Profile:** M. S. Plate 100 mm x 2.5 mm thick with angle stiffener **Side Guide Profile:** M.S." U" Shaped profile **Roller Shaft:** M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h **Side Brackets:** MS Plate 3 mm to 10 mm thick, as per the opening dimension. **Hood Cover:** Made of GI Sheet Thickness 0.9 mm. **Surface finish:** Powder Coated **Drive Unit & Mounting Type:** European Make Electric Motor - Direct Drive motor Mounting -Manual chain for Emg opening	Nos	1		Included	-	Pending
2	GI Rolling Shutter 1.0 mm Motorised 3.0 x 4.0 mtr Direct Drive Motor	Same as above	Nos	2		Included	-	Pending
3	GI Rolling Shutter 1.0 mm Motorised 3.0 x 4.5 mtr Direct Drive Motor	Same as above	Nos	1		Included	-	Pending
4	GI Rolling Shutter 1.0 mm Motorised 3.0 x 2.4 mtr Direct Drive Motor	Same as above	Nos	1		Included	-	Pending
						Total	-	

Non standard items/extra requirement, if any:	

B Commerical Terms:

1	Payment Terms:	50% Advance along with PO, 40% Against dispatch and balance 10% immediate after Installation		
2A	Delivery Date as per PO:	within 25 days from drawing approval	2B. Required Delivery Date:	
3A	Transportation Scope:	Extra at actual	3B. Transportation Charges:	
4	P&F Charges:	NIL		
5A	Loading Scope:	NIHVA	5B. Loading Charges:	
6A	Unloading Scope:	CLIENT	6B. Unloading Charges:	
7A	Lifting Equipments Scope:	CLIENT	7B. Available Lifting Equipments:	
8	Warranty:	12 months from the date of supply.		
9A	Height arrangement Scope:	CLIENT	9B. Available Equipments for working at Site:	
10	Electricity Supply:	CLIENT		
11	GST:	As Applicable		
12A	Installation Scope:	NIHVA	12B. Installation required date:	
13	Mode of import:	NA		
14	HSS:	No		
15	Documentation Required:	Standard Handover Documents		
16A	Total site visits required:		16B. Site visit charges:	

Certified that the above work order finalised in presence of:

AGM	SALES		Operation	PROJECT	DESIGN	Date & Time
A.K.	V.T.		S.B.	S.M.	G.P.	04-04-2022