Sales Quotation

NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Quotation No - SQT/19-20/1789 R2 **Date : 14/08/2019**

KINGFA Science and Technology India Ltd.
208,2nd Floor,Gera Garden II, 7A Koregaon Park
Pune -411001

Kind Attn: Mr. Vivek Thigle
Email: vivekt@kingfaindia.com
Contact No: 9028812358

Project Name & Location: Chakan Project, Pune

Subject : Quotation for Scissor Lift

Dear Sir
Thank you for the opportunity and trust shown on "NIHVA", your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; Please find below our best offer.

Commercial Offer

Sr. No.	Description	Qty	Unit	Rate In INR	Total Amount INR
A	**NIHVA make SCISSOR LIFT** **(Supply + Installation)**				
1	• Capacity : 2 ton • Platfrom Size : (L) 4200 mm x (W) 2700 mm • Power pack : 5HP, 3PH • Shut Height : 700 mm • Max Height : 5000 mm • Lift ht : 4300 mm • Railing : 1000 mm height only length side (4200 mm) • Color : Golden Yellow (RAL 1004) Guide Rollers provide due to max height	1	No	715,000	715,000
	Total				**715,000**

GST Pune	27AAECN0437H1ZM	**Total**	**715,000**

General Prerequisites Required at Site

1 Finished Flooring after curing (Without Water)
2 Electrical Supply on the site single phase/three phase points at different places.
3 Provide electrical cables near to the installation machinery
4 Fork lift/crane to be provided if required .
5 Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1. **Price** : Ex Works Pune
2. **P & F Charges** : @3% of total supply value
3. **Freight Notes** : Extra As applicable
4. **Delivery** : 5 -6 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.
5. **Payment** : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.
6. **Insurance** : Extra As applicable
7. **Tax** : GST Extra @ actual
8. **Validity** : Validity of Offer is 15 days from the date of quotation
9. **Warranty** : 12 months from the date of supply.

Please feel free to Contact **Mr. Bhavin Jain** on 8551092333 For any further Clarification /Information in this Concern.

With Best Regards

Smita Khare
9637991333
For NIHVA Technologies Pvt Ltd