Sales Quotation

Quotation No - SQT/19-20/1779 **Date : 03.07.2019**

SUROJ BUILDCON PVT. LTD.
Bungalow No. 3, Liberty Society Phase-I, North Main Road,
Koregaon Park, Pune 411 001, Maharashtra, India.

Kind Attn: Mr. Nikhil Bakane
Email ID: nbakane@suroj.in
Contact No: 020 4135 5926

Project Name And Location : M/s Perstorp Industries India Pvt Ltd , Saykha Village Dahej in Bharuch district, Gujarat.

Subject : Quotation for Motorized Sliding Gate and Wicket Gate.

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.


Sr. No	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**MOTORISED SINGLE LEAF SLIDING GATE** **(Supply + Installation)**				
	Sliding Gate -(W) 9000 mm X (H) 1800 mm **• For Post- 72 x 72 x 3.2mm MS SQ. TUBE** **• Outer Frame- 72 x 72 x 3.2mm MS SQ. TUBE** **• Inner Frame - 38x38x3.20mm/40x40x3.2 MS SQ. TUBE** **• MASTER LEAF SIZE - 10500 X 1800mm** **• GAP BETWEEN INNER TUBES- 125 MM**				
1	**Size : (W) 9000 mm X (H) 1800 mm**	1	No	436,000	**436,000**
B	**MANUAL BI-PARTING SLIDING GATE** **(Supply + Installation)**				
	• For Post- 72 x 72 x 3.2mm MS SQ. TUBE **• Outer Frame- 72 x 72 x 3.2mm MS SQ. TUBE** **• Inner Frame - 38x38x3.20mm/40x40x3.2 MS SQ. TUBE**				
1	**Size : (W) 19000 mm X (H) 1800 mm**	1	No	459,000	**459,000**
2	**Size : (W) 15000 mm X (H) 1800 mm**	1	No	373,000	**373,000**
	Total				**832,000**
C	**MANUAL DOUBLE LEAF SWING GATE** **(Supply + Installation)**				
	Sliding Gate -(W 2000 mm X (H) 1800 mm **• For Post- 72 x 72 x 3.2mm MS SQ. TUBE** **• Outer Frame- 72 x 72 x 3.2mm MS SQ. TUBE** **• Inner Frame - 38x38x3.20mm/40x40x3.2 MS SQ. TUBE** **• MASTER LEAF SIZE - 910 X 1800mm = 2 NOS** **• GAP BETWEEN INNER TUBES- 125 MM**				
1	**Size : (W) 2000 mm X (H) 1800 mm**	1	No	69,000	**69,000**


D	**MANUAL SINGLE LEAF SLIDING GATE** **(Supply + Installation)**				
	Sliding Gate -(W) 10000 mm X (H) 1800 mm **• For Post- 72 x 72 x 3.2mm MS SQ. TUBE** **• Outer Frame- 72 x 72 x 3.2mm MS SQ. TUBE** **• Inner Frame - 38x38x3.20mm/40x40x3.2 MS SQ. TUBE** **• MASTER LEAF SIZE - 11200 X 1800mm** **• GAP BETWEEN INNER TUBES- 125 MM**				
1	**Size : (W)10000 mm X (H) 18000 mm**	1	No	335,000	**335,000**
E	**WICKET GATE** **(Supply + Installation)**				
	Wicket Gate - (W) 1370 mm X (H) 1200 mm				
1	**Size : (W)1370 mm X (H) 1200 mm**	1	No	43,000	**43,000**
F	**Motorized Rolling Shutter** **Technical Specifications:** **•GI Slat : 1.0 mm Thick** **• Profile : Curved Type Profile with heavy duty Shaft** **• Guide : 2.5 mm Thick MS Guide** **• Hood Cover & Motor Cover : 0.9 mm Thick GI material** **• Indirect Drive** **• With Painting** **(Supply + Installation)** 				
1	Size (W) 3000 mm x (H) 4500 mm	6	Nos.	124,000	744,000
2	Size (W)4000 mm x (H) 3500 mm	3	Nos.	121,000	363,000
3	Size (W) 3000 mm x (H) 3500 mm	7	Nos.	104,000	728,000
4	Size (W) 3000 mm x (H) 3000 mm	3	Nos.	100,000	300,000
5	Size (W) 2500 mm x (H) 3000 mm	1	Nos.	90,000	90,000
6	Size (W) 3000 mm x (H) 2400 mm	1	Nos.	88,000	88,000
	Total				2,313,000

G	**Dock Leveler (NIHVA Make)** **2 cylinder for Deck & 1 cylinder for LIP Operator by Standard Control Panel (Deck Up / Down / Lip Up / Down) Rubber Bumpers.**				
1	**Dock Levelers Capacity 6 Ton** Size : (W) 2000mm X (L) 2500 mm (Supply + Installation)	4	No	255,000	**1,020,000**
Total					1,020,000

GST Pune	**27AAECN0437H1ZM**	**Grand Total**	**5,048,000**

Dock Leveler Image & Technical Specifications





Sr. No.	Description	Specifications
1	Capacity	6 Ton
2	Dock operation mode	AC power pack hydraulically operated
3	Lip operation mode	Hydraulic
4	Operation control	Through panel
5	Loading platform height from road	1250mm
6	Travel above & below dock level	(+) 300 / (-) 250 mm
7	Platform Size (W x L)	2000 mm x 2500 mm
8	Lip size (W x L)	2000 x 400 mm
9	Shut Height	480 mm
10	Overall length	2000mm x 2500mm + Lip Length (400mm)
11	Maximum slope can be achieved	10%
12	Clear Pit dimensions (W x L x D)	(W) 2050mm x (L) 2550 mm x (D)485 mm
13	Hydraulic power pack	Standard
14	Driver type	Direct by electric Motor
15	Motor Ratings	1 H.P
16	Pump design flow	2.5 LPM
17	Pump pressure	120 bar Operating 200 bar Max.
18	Safety valve set pressure	120 Kg/cm^2
19	Pump Type	Gear
20	Volume of oil receiver	7 Lit
21	No Of Deck cylinder	2 No
22	Lip Cylinder	1 No
23	Dock Bumper	Pair of Dock Bumper

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	@ 3% of Total supply value
3	**Freight Notes**	:	Extra as applicable
4	**Delivery**	:	5 - 6 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% Advance along with Confirmed Purchase Order & Balance before dispatch.
6	**Insurance**	:	Extra As applicable
7	**Tax**	:	GST Extra 18%
8	**Validity**	:	Validity of Offer is 15 days from the date of quotation
9	**Warranty**	:	12 months from the date of supply.

If there is any query please feel free to contact Mr.Bhavin Jain on 8551092333.

With Best Regards
Ulka Auti
7219206333
For NIHVA Technologies Pvt Ltd