Qualites Infrastrukture

WORK ORDER

To, NIHVA Technologies Pvt. Ltd., Thremax Chowk M.I.D.C. Chinhwad, Pune – 19 GST No: Kind Attn. – Mr. Ravindra Kharat Mobile – 7410169333 Project Name & Location: Tenneco Air India Pvt Ltd	W.O. No. : QI/PO/TEN/03/2020-21 Date : 25/8/2020 Reference : Ref Date : GST No. : 27AETPG9518E2Z4 PAN NO : AETPG9518E

Sr. No	Description	Size		Qty	Supply Charges in INR	Installation Charges in INR	
	Supply & Fixing	Clear Width	Clear Length	(Nos)	Unit Price	Unit Price	Total Amount
		(mm)	(mm)				
1.	Motorised Rolling Shutter	4500	4000	1	127000	15000	142000
	P& F Charges						
	Total Without Taxes				127000	15000	142000
	Gst Extra @18%						25560
	Total With Taxes						167560
	Transportation Charges						NILL

B) Technical Specification

NIHVA Rolling Shutter

Sr. No	Description	Specifications
1	Rolling Shutter	Motorised Rolling Shutter with mild steel of Thickness of 1 mm
2	Mounting Location area	Inside area
3	Curtain Panel	The panel made of 1 .0mm thick MS steel
4	Curtain Panel Size	75mm wide
5	Curtain Profile	Curved
6	Bottom Profile	M.S. Plate 100 mm x 2.5 mm thick with angle stiffener
7	Side Guide Profile	M.S."U" Shaped profile 65 mm -150 mm x 3 mm thick (as per te opening dimension)
8	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Dia -100 to 300 mm as per w x h
9	Side Brackets	M.S Plate 3 mm to 10 mm thick, as per the opening dimension
10	Hood Cover	Made Of GI sheet Thickness 0.9 mm GI mm with 25x25x3mm angle stiffener
11	Surface Finish	Powder coated
12	Drive Unit & Mounting Type	Electric Motor- Indirect Mounting

C) General Specifications

1. You will mobilize the installation Team in 2 -4 working days, after receipt of all material at site
2. If Lifting Equipment's are in NIHVA Scope, then those will be used installation purpose only

Sr. No.	Description	Remark
1	Scaffolding/Hydra/Crane/Forklift etc-required for Installation At Site	By QI
2	Electrical Supply on the site single phase/three phase at one place.	BY QI
3	Any Civil/ masonry /structural work required	BY QI
4	All Structure support required	BY QI
5	Conduits, Cables if required	BY QI

D) Terms & Conditions

Price	Works Pune
Transportation	NIVHA SCOPE
Delivery	4 days from the date of receipt of confirmed purchase order
Payment	i) Rs 20000/- Advance paid ii) Rs 1.2 lakh immediate after receipt of material at site and inspection and before installation iii) Rs 27560 immediate after commissioning, testing and installation.
Warranty	12 months from the date of a satisfactory completion certificate from client

With Best Regards,

Bibhishan P Ovhal
For Qualites Infrastrukture