NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Patvin Engineering Private Limited
Patvin House, W-193, TTC Industrial Area,
MIDC Khairane, Navi Mumbai - 400 709

Project, Location : MSIL-Gurgaon

Date : 21.08.2021
Quote NO : SQT.20.21.2669R5
Kind Attn : Mr. Pranav Vaidya
Email Id : pranav_vaidya@patvin.co.in
Contact No: 8828198478

Subject : Revised Quotation for Fire rated Sliding Door at Maruti Suzuki Plant

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Sliding Type Door (Fire Rated 120 min)	1700	2100	1	135,000	135,000	Inclusive	
	Total			**1**		**135,000**		**-**
2	P&F Charges			0%		-		
	Total Without Taxes					135,000		-
	GST Extra @ 18%			18%		24,300		-
	Total With Taxes					**159,300**		**-**
3	Transportation Charges					Extra at atcual		
4	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Fire Rated Sliding Door

Sr. No	Description	Specification
1	**Description**	BS 476 part(20 & 22)tested at CBRI :Central Building Research Institute, Roorkee Fire Resistant Door Fusible link (Rated for 68 deg. C) based Auto Sliding type (2 hours fire rated) complete with fixing arrangements including fusible link, wire rope, guide rail, counter weight, pulleys as per BS 476, Part 20 & 22 and standard accessories included. An overlapping of 100 mm in height and 200 mm in width is considered while calculating the sizes of the doors and is mandatory to restrict fire from escaping from the gaps between the wall and the shutters.
2	**Wall Opening(w)- mm**	1700 mm
3	**Wall Opening(H)- mm**	2100 mm
4	**Insulation**	Honeycomb/Rockwool
5	**Frame & Shutter Material**	GI
6	**Frame & Shutter Finish**	Powder Coating
7	**Fire rating**	120 Minute (2 Hours) for Integrity and stability.
8	**Accessories Included**	Fusible link, wire rope, guide rail, counter weight, pulleys as per BS 476, Part 20 & 22 and standard accessories included

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune
Delivery : 4 - 5 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.
Payment : 30% Advance along with Confirmed Purchase Order, 60% Balance before dispatch and 10% after Installation.
Validity : Validity of Offer is 15 days from the date of quotation
Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Shrikant Mirkute on 8551098333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd