Sales Quotation

Quotation No. SQT/18-19/1157R **Date : 03.05.209**

Pharmintech Turnkey Solutions Pvt.Ltd.
A-417, Tower-II, Lodha Supremus, Road no. 22
Wagle Estate, Thane - 400604
Maharashtra - India

Kind Attn : Mr. Mandip Sharma
Email : mandip.sharma@pharmintech.net
Contact No : 7400314145

Project Name And Location : Automotive Industry Project at Aurangabad

Subject :- Revised Quotation for ASSA ABLOY - ALBANY make High Speed Door - RR300+AL

Dear Sir

Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication; please find below our best offer.

Commercial Offer

Sr. No	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**ASSA ABLOY (Albany) Rapid Roll Up Door RR300+AL**				
Door panel:	Transparent PVC with Blue (RAL 5002) reinforcement stripes.				
Barrel:	Aluminium, anodized with shafts made of galvanized steel				
Wind Reinforcement:	Door Panel wind tabs for improved wind resistance				
Side Frames:	Aluminium profiles, anodised				
Drive Unit:	Motor IP 55, either RH or LH as an option, with control cable (standard length = height of door)				
Self-opening:	Standard - the door can be opened partially up to 1,8 m by releasing the brake manually.				
Bottom beam:	Anodized extruded aluminium.				
Control system:	MCC Vector Control - frequency converter control system for a dynamic, smooth door movement, located close to the drive unit Max. Opening Speed 2.2m/s Max. Closing Speed 0.9 m/s				
Safety features:	Safety edge, safety photocell (Transmitter/Receiver) inside side columns				



1	Size: (W)2000 mm X (H) 3000 mm	1	No	475,000	475,000
2	Size: (W) 1500 mm X (H) 3000 mm	1	No	464,000	464,000
				Total	**939,000**

Note: Door Mounting Structural Frame is in Client Scope.

GST Pune	**27AAECN0437H1ZM**

General Prerequisites Required at Site

1 Finished Flooring after curing (Without Water)
2 Electrical Supply on the site single phase/three phase points at different places.
3 Provide electrical cables near to the installation machinery
4 Fork lift/crane to be provided if required .
5 Scaffolding require for Installation it is in client scope.

Limit of Supply

1 Provide place to store the material to be installed .
2 Be responsible for the safe custody of all material.
3 Provide place to safely store all the tools of installation
4 Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site is in **Client Scope**
2. Electrical connection for control panel.
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	Ex-works Pune
2	**P & F Charges**	Nil
3	**Freight Notes**	Extra At Actual
4	**Delivery**	: 10 - 12 weeks for High Speed Door from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	: 80% Advance along with Confirmed Purchase Order & Balance before dispatch
6	**Insurance**	: Included
7	**Tax**	: GST Extra @ 18%
8	**Validity**	: Validity of Offer is 15 days from the of quotation
9	**Warranty**	: 12 months from the date of supply.

Please feel free to Contact **Mr. Ravindra Kharat** on **7410169333** for any further Clarification /Information in this Concern.

With Best Regards

Smita Khare

9637991333

For NIHVA Technologies Pvt Ltd