NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Hicon Engineering Co. Pvt. Ltd.
Plot no. – 108,109,152 & 153
Udyog Kendra (Toy City)
Ecotech III,Greater Noida, 201306

Date : 31.12.2019
Quote NO : SQT.19.20.2331
Kind Attn : Mr. Bhupendra Raghav
Email Id : doors@hicon.co.in
Contact No: **8467955777**

Subject : Quotation for Sectional Door, Dock Leveller, Dock Shelter.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Sectional Door (ASSA ABLOY)	2400	2700	1	2,52,000	2,52,000	20,000	20,000
2	Dock Leveller (NIHVA Make)	2000	2500	1	2,25,000	2,25,000	20,000	20,000
3	Dock Shelter (NIHVA Make)	3450	3600	1	1,35,000	1,35,000	15,000	15,000
				Total		**6,12,000**		**55,000**
	P&F Charges			3%		**18,360**		
	Total Without Taxes					**6,30,360**		**55,000**
	GST Extra @ 18%			18%		1,13,465		9,900
	Total With Taxes					**7,43,825**		**64,900**
	Total Supply + Installation With Taxes							**8,08,725**
4	Transportation Charges					**In Client Scope**		
5	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company


GST Pune : 27AAECN0437H1ZM

B) Technical Specification

ASSA ABLOY Motorised Sectional Door







Sr. No	Description	Specification
1	Model No	ASSA ABLOY OH1042P
2	Vision Windows	2 Nos at central panel
3	Opening Direction & Mounting	Standard
4	Opening/Closing Speed	CDM9 0,28 m/s
5	Door Material	GI Steel
6	Panel Thickness	42 mm Square Grid, steel sheet
7	Filling	CFC-free polyurethane
8	Door sealent	All door sealants made of EPDM rubber, temperature resistant -30/+70
9	Water Penetration	EN 12425 class 3
10	Air Permealibity	EN12426 class 3
11	Thermal Transittance	EN 12428 1.10W /m2K
12	Bottom sealing	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber
13	Door saftey	Doors equiped with spring break device
14	Incase of Power failuer	Doors to be equiped with quick release fuction
15	Operator power conumption	Operator to have a maximum power consumption of 0,37kW and a standby consumption of Maximum 15W
16	Drive Unit & Mounting Type	Single phase 230V direct drive on shaft
17	Emergency Operation	by Disengagement rope manual
18	Operating Switch	Up/Down Keypad + stopbutton
19	Locks : Lock bolt	The Lock bolt locks the door from the inside, without the use of a key. The Lock bolt is not visible from the outside.
20	Environmental Green Product Declaration Certification	As per ISO 14025 and EN 15804

Retractable Dock Shelter





Sr. No.	Description	Specification
1	Size (W X H)mm	3450 X 3600
2	Nominal depth	600 mm
3	Top curtain	1000mm
4	Side Curtain	600mm
5	Curtain Color	Black
6	Parking Guide	White, Yellow
7	Wall fixings	Concrete, sandwich, light concrete, load house, cavity, insulated pannel
8	Top & Side curtains	Double layer high quality polyster
9	Thickness	3mm
10	Continous Roof Cover	one layer high quality polyester
11	Thickness	0.5mm
12	Flammibility all curtains	DIN 75200

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

Dock Leveler



Sr. No.	Description	Specifications
1	Capacity	6Ton
2	Dock operation mode	AC power pack hydraulically operated
3	Lip operation mode	Hydraulic
4	Operation control	Through panel
5	Loading platform height from road	1250mm
6	Travel above & below dock level	(+) 300 / (-) 250 mm
7	Platform Size (W x L)	2000 mm x 2500 mm
8	Lip size (W x L)	2000 x 400 mm
9	Shut Height	480 mm
10	Overall length	2000mm x 2500mm + Lip Length (400mm)
11	Maximum slope can be achieved	10%
12	Clear Pit dimensions (W x L x D)	(W) 2050mm x (L) 2550 mm x (D)485 mm
13	Hydraulic power pack	Standard
14	Driver type	Direct by electric Motor
15	Motor Ratings	1 H.P
16	Pump design flow	2.5 LPM
17	Pump pressure	120 bar Operating 200 bar Max.
18	Safety valve set pressure	120 Kg/cm²
19	Pump Type	Gear
20	Volume of oil receiver	7 Lit
21	No Of Deck cylinder	2 No
22	Lip Cylinder	1 No
23	Dock Bumper	Pair of Dock Bumper

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 7 - 8 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Ravindra Kharat on 7410169333**

With Best Regards
Vivek
8350570333
For NIHVA Technologies Pvt Ltd