

NIHVA
NIHVA TECHNOLOGIES PVT. LTD.





Project Seabird Shipyard Project –MWC04
Covered Dry Berth (CDB)

Karwar, India



Quotation

ASSA ABLOY

ASSA ABLOY Entrance Systems

The global leader in
door opening solutions

NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No. SQT/19-20/2016A Date: 05/09/2019

Kind Attn: Mr. Mohan Kumar
Email:bcmohankumar@lntecc.com
Contact No: +91-8826322812

Project Name and Location: Project Seabird, MWC04, CDB

Subject: Quote for Supply and installation of Vertical Lifting Fabric Door.

Dear Sir,

Thank you for giving us an opportunity to participate with our offer on the above project. We enclose herewith our proposal which includes:

A. Requirement
B. Proposal
C. Terms and Conditions
D. Pricing

By choosing ASSA ABLOY Entrance Systems as the supplier of your door automation products, you will receive the following advantages:

- You are working with a Global Provider with financial strength and over 50 years' experience of the global market place in Entrance Solutions.
- World leading products ensure excellent reliability and life-cycle costs to give you peace of mind.
- Project support for both specification development and design suitability
- A comprehensive product helping to provide value engineered solutions

Major Benefits using Megadoor

- No floor track (and therefore no concrete grade beam) needed; a substantial saving in civil cost.
- Faster opening and closing time due to vertical lifting, resulting in a substantial reduction in loss of energy.
- Minimal side-room required (no “door pockets”); a substantial saving in space and cost of land, this is especially relevant, when a series of hangars are built adjacent to each other.
- The doors have very tight sealing, to protect against water, sand and dust ingress, which is essential for a maintenance hangar.

We wish you success with your project and hope that we may be part of your current & future projects as a solution provider. We will follow up this quotation with a call to you within the next few days.

If you have any questions after reading this proposal, or if you need more information, please do not hesitate to contact us.

Kind Regards,
Mr. Vijay Tarak
Director - NIHVA Technologies Pvt. Ltd
Mob: +91 8551093333
Email: sales@nihva.com

Commercial Offer: - Supply of **VL3190** Hangar door

Sr No.	Clear Size in mm (W) X (H)	Qty (in NO)	Unit Price (INR)	Total Supply & Installation Price (INR)
1	(W) 28000 mm X (H) 47500 mm	4	6,05,86,080	24,23,44,320
2	(W) 12 000 mm X (H) 10000 mm	4	61,60,920	2,52,43,680
	Total Supply and Installation Price for 8 doors (INR)			26,75,88,000

Price quoted includes the following:

- Design ,Production
- Sea freight from Sweden to India.
- Custom clearance and local transportation to Project seabird Karwar site, India.
- Installation team.

Price Excludes:
Custom Duty, GST and Installation Lifting Equipment's are not included in our pricing. List of required lifting equipment's and duration is attached here with for your consideration.

Scope of supply

The scope includes: Design, production, delivery and installation of door as per the tender specification.

For technical specifications, sketches, pictures and similar, please see Appendices.

A suitable structure should be available designed in accordance with final approval drawings issued by ASSA ABLOY. Tolerances/deflections of the support structure to be in accordance with the drawings.

I. Preliminary schedule

Time of delivery

Supplier provides design specification of the door system within 2 weeks from the receipt of the Purchaser's final specification.

Fabrication will not start until we have received full and final approval.

Supplier to manufacture the door system within 16-18 weeks from the date on which the Purchaser has confirmed the Supplier's design specification in writing. Should the Purchaser not confirm the design specification, the Supplier shall have no remaining obligations under this quotation. Installation time is subject to site readiness, clear working area and delays by others. Detailed program will be agreed with our project coordinator.

Delivery times mentioned herein are based on current situation and is therefore expected but not guaranteed.

Shipment time: 6 to 7 weeks.

Installation Time:

- 28m X 47.5m: Approx. 70 days per door
- 12m x 10m: Approx. 12 days per door

Preliminary Installation schedule for the big doors are attached here with. We can discuss and coordinate the installation schedule in detail.

Intermediate sales, holidays, seasonality and other circumstances may impact delivery time. Please make sure to re-confirm delivery time with us when the project time plan is available.

II. Delivery conditions

Delivery of material will be coordinated with the client written construction schedule. The contractor is responsible for notification to Megadoor of any expected or actual delays in the agreed delivery date at least fourteen (14) days prior to the scheduled delivery. Without timely notification of changes in delivery dates, the contractor or contractor's representative will assume the responsibility of unloading and storing the provided materials in a manner to prevent damage of the materials.

III. Drawings

We will issue a full set of shop drawings for approval within 2 weeks of receiving the confirmed order and finalized design details

IV. Compensation clause

Please note that in the event the buyer cancels an order, after the order is confirmed to us, it is binding to the buyer to pay NIHVA - ASSAABLOY a compensation of 25% of order value.

General Pre-Requisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery.

Limit of Supply

1. Provide place to store the material to be installed.
2. be responsible for the safe custody of all material unless other arrangement made between us.
3. Provide place to safely store all the tools during installation.
4. Provide change & rest room for the workers.

Client Scope

1. Any civil / masonry/structural work required to support are in client scope.

Terms & Conditions:

Payment	• 40% Advance along with confirmed Purchase order. • 50 % to be paid against Bill of lading and shipping documents. • 5% on completion of Installation. • 5% on Testing, Commissioning and Handover.
Tax	• GST @18% • Import Custom duty is not included in our pricing.
Validity	90 days from the date of offer
Insurance	Inclusive
Warranty	12 months from date of Installation and Commissioning.
Client scope	➢ Any masonry / structural work required to support are in client scope
Compensation clause	Please note that in the event the buyer cancels an order, after the order is confirmed to us, it is binding to the buyer to pay NIHVA - ASSAABLOY a compensation of 25% of order value.
Others	Need to provide by client - clear opening mounting structures, any Civil work, electrical points and cables till doors, Installation Equipment's and Scissor lifts, Material and equipment storage secured space, fabrication and assembly space.

General conditions:

1. Continuous uninterrupted access to any single door section or as agreed separately.

2. Suitable structure for installing the doors to be provided. Door Structure to be done as per the interface and load diagram that will be provided by us after the order confirmation.

3. Load testing of the steel structure to be done by the steel contractor after completion of structure. Report to be shared with our project manager for verification.

4. A clear floor area of 4 meters each side of the door leaf must be available during the curtain fitting process. The floor should be finished or if this is not possible, adequate temporary protection be made available to prevent damage to the curtain material.

5. 400 volt / 50Hz 3 phase isolator to be fitted to within 1 meter of the door main control panel. If not available at the start of installation, a temporary supply is acceptable. Any return visits to commission the doors due to permanent power not being available will be charged as appropriate.

6. Provision of 230 Volt power supply (by others) for hand tools.

7. A dry and secure area, not in direct sunlight, is to be provided for storage of the door components.

8. Access to site between 7 am to 6 pm six days per week. If this is not possible the installation programme may require amending.

9. Any storage costs for materials due to delays outside of Mega door's control will be charged to the main contractor.

10. The project time indicated does not take into account adverse weather conditions that may prevent safe and efficient working practices. We reserve the right to extend the period accordingly.

11. Any passes required for the project, are the responsibility of the Customer and Contractor and must be available, before commencement of the installation. Any delays caused by the non-availability of passes, will be charged accordingly.

Inclusions

1. Our proposal includes sea freight from Sweden to Site and installation of the door leaf, guide rails, weather seals, motors, control panel and electrical wiring. (Please refer Exclusion Below)

2. A pre-installation inspection will be carried out, by ASSA ABLOY Project Manager, before our installers travel to site, so as to verify that the structural steelwork and electrical installation are as per our requirements. Our Project Manager will also check that the installation equipment and facilities are ready for installers.

3. Please note that the control panels, motors and electrical wiring are in full compliance with Swedish regulations and specifications, any variations due to specific requirements for India must be notified to us at the time of ordering and may be subject to an increase in the price. Any variations notified to us, after material procurement, will be charged accordingly and may lead to production delays.

Exclusions

The following items are not within our scope of works and are to be provided by others at no cost to NIHVA - ASSAABLOY.

1. The structural support steel for the door head, jambs, motor plates and motors shall be furnished by others. Structural steel supports shall be installed in accordance with tolerances

shown on Megadoor shop drawings. The installation will not commence until these items are fully installed and tested (by steelwork contractor). The installation must be approved by the Megadoor Project Manager.

2. Any passes required for the project, are the responsibility of the Contractor and must be available, before commencement of the installation. Any delays caused by the non-availability of passes, will be charged accordingly.

3. All installation lifting equipment's are in Contractor scope. Details of required equipment's and duration per door are attached here with.

4. Power supply and isolators adjacent to the control panels (to be done by electrical contractor).

5. Any Civil work is in client scope.

6. Conduits and Cable trays from the control panel locations to the door distribution boxes, mullion hoist units and door hoist units be provided. (to be done by electrical contractor). These are to be installed prior to the commencement of door installation.

7. A 400/230 power supply (permanent or temporary) must be provided (FOC) by the main Contractor during the installation of the door for power tools and testing of the door sections during erection.

8. A safe storage / pre-assembly area for the door materials (by main contractor).

9. Any additional tests or certification, which are not within our scope of works but may be required by the Consultant or Client, these will be carried out or provided, subject to the actual requirements but will be at additional cost (by main contractor).

APPENDICES:

- Appendix 1: Technical Data
- Appendix 2: Load Diagram
- Appendix 3: Preliminary installation schedule.
- Appendix 4: List of Installation Lifting Equipment's required and duration per door.

Please feel free to Contact Mr. Ashish (+971-506320495)/ Mr. Vijay Tarak (+91-8551093333)/ for any further Clarification / Information in this concern.

With Best Regards
Vijay Tarak
Director
8551091333
For NIHVA Technologies Pvt Ltd

ASSA ABLOY Entrance Systems

One partner for all your automatic entrances

ASSA ABLOY Entrance Systems comprise world-leading products, maintenance programs and modernization services, ensuring total solutions for efficient flow of people, goods and vehicles. With comprehensive entrance solutions for the front, back and interior of your building, we put every automatic door equipment or service you need under one roof.

The perfect match for your building
ASSA ABLOY Entrance Systems' extensive product range, expert application knowledge and maintenance programs provide optimal entrance solutions for all needs and any demands in manufacturing, distribution & logistics, retail, healthcare, transportation, hospitality, private services, public services, mining and air & sea, and more.

Sustainable Solutions
We design, manufacture and service automatic entrance solutions that help you reach your sustainability goals for energy savings and minimal environmental impact.

Leading product brands backed by dedicated specialists
With our three specialized business areas; Pedestrian Door Solutions, Industrial Door & Docking Solutions and High-Performance Door Solutions, we offer market-leading product brands and a global service organization. With more than a century of aggregated engineering experience and application expertise ASSA ABLOY Entrance Systems is your ideal business partner to provide, maintain and modernize all of your automatic entrances.



Pedestrian Door Solutions

- swing doors
- sliding doors
- revolving doors



Industrial Door and Docking Solutions

- industrial doors
- complete docking systems
- hangar doors



High-Performance Door Solutions

- high speed roll doors
- doors for special applications such as clean rooms, machine protection and food processing