WORK ORDER

Client:	
SCON Projects Pvt Ltd	
Address:	
"SAMARTH HOUSE", S No. 116, Hissa No 3/1,3/3,3/10, Pune - Bangalore Highway, Near Shell Petrol Pump, Warje- 411058	

PO Number:	KSB-PO-HO-211029001	**W. O. No-**	SO/21-22/0108
PO Dated :	29-10-2021	**W. O. Date**	30-10-2021
PO Received Date:	30-10-2021	**Sales Co ordinator**	Shailesh
Ref. Quotation:	SQT.21.22.0129R10	**Front Sales Person**	Shrikant

Dispatch Address:

KSB Limited @ Sinnar
Plot no-E-3, MIDC Sinnar , water pump division ,
dist- Nashik-422103, Nashik, Maharashtra (India)
422103

A **Technical Terms:**

Sr. No	Description of Goods	Technical Details	UOM	Qty.	Supply Rate	Installation Rate	Total Amount	Dwg. Approval Status
1	Motorized Single Skin Rolling Shutter - Indirect Drive with Dead Man Control (W) 4500 mm X (H) 6000 mm	Description: Motorised Rolling Shutter with MS Slats with thickness of 1 mm. Mounting Location area : Inside area / Outside area Mounting Surface : Side Brackets: Optional = On Concrete /Steel & Side Curtain Panel : The panel made of 1.0mm thick GI. Curtain panel size : 75mm wide Curtain Profile : Curved Bottom Profile : M. S. Plate 100 mm x 2.5 mm thick. Side Guide Profile : M.S." T" Shaped profile 65 mm -150 mm x 3 mm thick. Roller Shaft : M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día - 100 to 300 mm as per w x h Side Brackets : MS Plate 3 mm to 10 mm thick, as per the opening dimension. Hood Cover : Made of GI Sheet Thickness 0.9 mm. Surface finish : 2 Coats (each coat of 35 microns DFT) of EPOXY polyamide-based enamel finish of approved color and make over a Coat (each one coat 25 microns DFT) of EPOXY polyamide based red oxide zinc phosphate primer Drive Unit & Mounting Type : Electric Motor - In-Direct Mounting - Sprocket chain arrangement – IP54 Protection Control Type : Dead Man Control	Nos	6		0	0	Pending
2	Motorized Single Skin Rolling Shutter - Indirect Drive with Dead Man Control (W) 4000 mm X (H) 5000 mm		Nos	1		0	0	Pending
3	Motorized Single Skin Rolling Shutter - Indirect Drive with Dead Man Control (W) 4000 mm X (H) 3800 mm		Nos	2		0	0	Pending
4	Motorized Single Skin Rolling Shutter - Indirect Drive with Dead Man Control (W) 3000 mm X (H) 3800 mm		Nos	1		0	0	Pending
5	MS Rolling Shutter Electrically Operated MOTORIZED FULLY GRILLED SINGLE SKIN DIRECT DRIVE EUROPEAN MAKE MOTOR , SIZE: WIDTH 4000mm X HEIGHT 4000mm,	Description: Motorised Rolling Shutter with MS Slats with thickness of 1 mm. Mounting Location area : Inside area / Outside area Mounting Surface : Side Brackets: Optional = On Concrete /Steel & Side Curtain Panel : The panel made of 1.0mm thick GI. Curtain panel size : 75mm wide Curtain Profile : Full Grill Bottom Profile : M. S. Plate 100 mm x 2.5 mm thick. Side Guide Profile : M.S." T" Shaped profile 65 mm -150 mm x 3 mm thick. Roller Shaft : M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día - 100 to 300 mm as per w x h Side Brackets : MS Plate 3 mm to 10 mm thick, as per the opening dimension. Hood Cover : Made of GI Sheet Thickness 0.9 mm. Surface finish : 2 Coats (each coat of 35 microns DFT) of EPOXY polyamide-based enamel finish of approved color and make over a Coat (each one coat 25 microns DFT) of EPOXY polyamide based red oxide zinc phosphate primer Drive Unit & Mounting Type : Electric Motor - Advance NICE Make,Direct Mounting - Sprocket chain arrangement – IP54 Protection Accessories : Advance Access Control, Card Reader on both side of door & Photocell	Nos	2		0	0	Pending
						Total	**0**	

Non standard items/extra requirement, if any:

B **Commerical Terms:**

1	**Payment Terms:**	20% Advance, 60% within 15days against delivery & balance 20% after 7 Days of receipt of Bill at HO with successful completion of work & submission of documents for handover at site.		
2A	**Delivery Date as per PO:**	On Or Before 29-Nov-21	**2B. Required Delivery Date:**	
3A	**Transportation Scope:**	NIHVA Scope	**3B. Transportation Charges:**	
4	**P&F Charges:**	NIL		
5A	**Loading Scope:**	NIHVA Scope	**5B. Loading Charges:**	
6A	**Unloading Scope:**	NIHVA Scope	**6B. Unloading Charges:**	
7A	**Lifting Equipments Scope:**	NIHVA Scope	**7B. Available Lifting Equipments:**	
8	**Warranty:**	12 months from the date of supply.		
9A	**Height arrangement Scope:**	Client Scope	**9B. Available Equipments for working at Site:**	
10	**Electricity Supply:**	Client Scope		
11	**GST:**	18%		
12A	**Installation Scope:**	NIHVA Scope	**12B. Installation required date:**	
13	**Mode of import:**	NA		
14	**HSS:**	NO		
15	**Documentation Required:**	Standard Handover Documents ,MTC		
16A	**Total site visits required:**		**16B. Site visit charges:**	

Certified that the above work order finalised in presence of:

AGM	SALES		Operation	PROJECT	DESIGN	Date & Time
A.K.	S.M.		S.B.	S.M.	G.P.	01-Nov