NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Gemba Concept
Bangalore

Date : 10.11.2022
Quote NO : **MHE_22.23.0031**
Kind Attn : Mr. Shivam Shrivastava
Email Id : shivam.s@gembaconcepts.com
Contact No: 9590495719

Project Name & Location: Gemba Concept, Bangalore

Subject : Quotation for Telescopic Truck Loading/Unloading Conveyor

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Conditions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation Charges in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Telescopic Truck Loading/Unloading Conveyor** • Total Length- 10mtr (Fixed-4mtr, Extended-6mtr) • Capacity- 30-40 bags/min • Belt Width - 650 mm	1	18,20,000	18,20,000	75,000	75,000
	TOTAL EXCLUDING TAXES			18,20,000		75,000
2	GST Extra @ 18%	18%				Extra At Actual
3	P&F Charges	3%				Extra At Actual
4	Transportation Charges					In Client Scope
5	Insurance Charges					Extra At Actual
6	Unloading Charges @ Site					In Client Scope

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Telescopic Truck Loading/Unloading Conveyor

Sr. No.	Parameters	Specification
1	Material to be conveyed	Cement Bags/carton box/buckets
2	Dimension of Bags(LxB)	600mm(L) x400mm (W) x 100 (H) (OVERALL)
3	Weight of box	25Kg and 50Kg
4	Capacity	50Kg/mtr
5	Belt Width	650 mm
6	Belt Type	2 Ply 3.2 mm PVC
7	Belt Speed	15-30 mtr/min
8	Telescopic Speed	8-10 mtr/min
9	Conveyor Type	Collapsible boom type hinged Telescopic belt conveyor
10	Length Of Conveyor	Fixed Length : 4000 mm Telescopic (Expanded) : 6000 mm Total Length : 10000 mm
11	Main Body Of Conveyor	MS Powder coated
12	Direction	Both Forward and Reverse direction
13	Working height	Min.950 mm and max. 1100 mm
14	Inclination Height	Max. 1200 mm
15	Speed adjustment	VFD (Schneider / Allen Bradley/Delta)
16	Gear Box	Bonfiglioli
17	Driven Motor Make	Bonfiglioli /CG/BBL , IE2
18	Movement	Movable (wheels provision)
19	Spot light	In front of the conveyor

C) General Conditions

1 Installation will start after receiving of Site Readiness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readiness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 After 1 year warranty, Non comprehensive AMC will be provided by NIHVA at an additional cost which will be 8-9% of total project amount.

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 8-10 weeks from the date of receipt of confirmed Purchase Order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch

Validity : Validity of Offer is 15days from the date of quotation.

Warranty : 12 months from the date of supply.

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd