NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

Sales Quotation

Quotation No - SQT/19-20/1837 **Date :19.07.2019**

J.J. Group ,
Ghatkopar,
Mumbai

Kind Attn: Mr. Rakesh Trivedi
Email: procurements@jj-group.in
Contact No: 9022714828

Project Name And Location : AAA Corp Exim Pvt Ltd.,Kalamgaon,Shahapur,Thane

Subject : Quotation for Modular Belt Conveyor System.

Dear Sir
Thank you for your opportunity and trust shown on "NIHVA." your preferred partner for innovative solutions.
This has reference to your above mentioned requirement as well as our subsequent communication. Please find below our best offer.

Commercial Offer

Sr. No.	Description	Qty	Unit	Rate In INR	Net Amount INR
A	**Modular Belt Input Conveyor with hopper** **(Supply + Installation)**				
1	Product : Modular Belt Take up Conveyor Size: 7000mm x 500 mm Loading Height : 300 mm Unloading Height : 1800 mm Width of conv : 500 mm Speed of conveyor 25m/min Product : 100 kg hopper Size : 1200 x 1200 Loading height : 1500 mm from ground	1	No	770,000	770,000
				Total	770,000
B	**Modular Belt Output Conveyor with hopper** **(Supply + Installation)**				
1	Out put conveyor Product : Modular Belt Take up Conveyor Size: 12000mm x 500 mm Loading Height : 1500 mm Width of conv : 500 mm Speed of conveyor 25m/min Product : 100 kg hopper Size : 1200 x 1200 Loading height : 1500 mm from ground	1	No	1,032,000	1,032,000
				Total	1,032,000

GST Pune	27AAECN0437H1ZM

TOTAL BASIC AMOUNT	**1,802,000**

General Prerequisites Required at Site

1. Finished Flooring after curing (Without Water)
2. Electrical Supply on the site single phase/three phase points at different places.
3. Provide electrical cables near to the installation machinery
4. Fork lift/crane to be provided if required .
5. Scaffolding require for Installation it is in client scope.

Limit of Supply

1. Provide place to store the material to be installed .
2. Be responsible for the safe custody of all material.
3. Provide place to safely store all the tools of installation
4. Provide change & rest room for the workers.

Quote/Supply is based on

1. BOM is calculated as per standard quantity measurement
2. In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage will be to customer account.
3. Billing will be as per the supply of material ,not as per site measurements

The supply included only those mentioned in the quote & does not include

1. Unloading from truck placement on site
2. Electrical connection for control panel.

Client Scope

1. Once our project gets complete for any additional work to & fro loading &boarding of our service technicians is in client scope
2. Any civil / masonry/structural work required to support are in client scope
3. All structure support is in client scope
4. NIHVA Will provided structure drawing only if required
5. Exiting/Repair/ Modification/ Refurbishment charges will be extra.

Terms and Conditions :

1	**Price**	:	Ex. Works Pune
2	**P & F Charges**	:	@3% of Total Supply Value
3	**Freight Notes**	:	Extra as applicable + Taxes
4	**Delivery**	:	8 - 9 weeks from the date of receipt of confirmed purchase order, Advance Payment, Drawing approval.
5	**Payment**	:	80% Advance along with Confirmed Purchase Order and Balance before Dispatch.
6	**Insurance**	:	Extra As applicable
7	**Taxes**	:	GST Extra as applicable
9	**Validity**	:	Validity of Offer is 15 days from the date of quotation
10	**Warranty**	:	12 months from the date of supply.

Please feel free to contact **Mr.Swapnil Kulat - 7219207333** For any further Clarification /Information in this concern.

With Best Regards

Pradip
7709586333
For NIHVA Technologies Pvt Ltd