GATE -2
SECURITY CABIN
08
WEIGH BRIDGE
FRISKING BUILDING
8a
STP
HAZARDOUS WASTE STORAGE
09
ETP
71550
4500
37500
4.5 MT WIDE ROAD
10360
GIDC WATER INLET UG TANK
FUTURE MODULAR TANK AREA
10
PUMP ROOM
30000
9000 MARGIN
4.5 MT WIDE ROAD
11
SCRAP YARD
60000
55000
SPACE FOR FUTURE CT & ADIABATIC CT
12
COOLING TOWER
13
SWITCH YARD
12.0 MT WIDE ROAD
TRUCK PARKING
1a
FUTURE SHED
01
RAW MATERIAL + CASTING LINE SHED
COPPER CASTING MACHINE
CHIMNEY & POLLUTION CONTROL SYSTEM
1b
15
DG SET
2000 KVA DG SET-1
2000 KVA DG SET-2
2000 KVA DG SET-3
2000 KVA DG SET-4
8.0 MT WIDE ROAD
9000 MARGIN
4b
PACKING, FINISH GOODS & DISPATCH
04
SLITTING SHED
EDGE TRIMMING
CTL
REWINDING
COIL TRANSFER TROLLEY
121410
6.0 MT WIDE ROAD
03
ANNEALING & PICKLING SHED
CRM SHED
PLANT OFFICE
LAB
ROLL ASSEMBLY AREA
WORKER FACILITY
HT ROOM
3b
COMPRESSOR ROOM
218910
8.0 MT WIDE ROAD
2b
UTILITY AREA
CASTING LAB
02
HRM SHED
SAW BLADE GRINDING MACHINE
SAWING MACHINE
STEPPER HEATING FURNACE 2-1
HOT ROLLING MILL 2-2
HOT ROLLING MILL POWER DISTRIBUTION ROOM
2# HIGH AND LOW VOLTAGE DISTRIBUTION ROOM
COPPER BELT WORKSHOP CIRCULATING WATER
BELL - TYPE ANNEALING FURNACE CONTROL ROOM
MILLING MACHINE CHIP COLLECTION ROOM
144 SLABS 0.26X5STACK
Ho=9m
2a
FUTURE SHED
323910
30000
06
CANTEEN
74850
4a
FUTURE SHED
3a
FUTURE SHED
351000
253500
SECURITY CABIN
07
GATE -1
12380
EMPLOYEE PARKING
VISITOR PARKING
ENTRANCE FACILITY
7a
16690
22300
52980
8.0 MT WIDE ROAD
9000 MARGIN
14
POND

01 **MASTER LAYOUT**
SCALE 1:900

🟦	PLANT BUILDING
🟨	UTILITY AREA
🟥	NON PLANT BUILDING AREA
▨	FUTURE BUILDING AREA
⬜	ROAD AREA
🟩	GREEN AREA

PLOT AREA (Sq. Mt.)		**212318.0**	
PERMISSIBLE GROUND COVERAGE (50%)		106159.0	
ROAD AREA		30135	2155
No.	**BUILDING NAME**	**"PHASE -1 AREA (Sq. Mt.)"**	**"FUTURE AREA (Sq. Mt.)"**
01	RM + CASTING LINE SHED	4445	7501
1b	RM + CASTLING LINE UTILITY	600	445
02	HRM SHED	16971	1740
2b	HRM UTILITY AREA	1040	-
03	ANNEALING & PICKLING	13806	15710
3b	ANNEALING UTILITY AREA	1843	1000
04	SLITTING SHED	6782	18995
4b	SLITTING UTILITY AREA	168	337
05	ADMIN	1267	-
06	CANTEEN	1075	-
07	SECURITY CABIN	160	-
7a	ENTRANCE FACILITY BUILDING	150	-
08	SECURITY CABIN	200	-
8a	FRISKING BUILDING	332	-
09	ETP, STP, HAZARDOUS STORAGE	2805	-
10	PUMP ROOM + M. TANK + UG TANK	1657	800
11	SCRAP YARD	1817	-
12	COOLING TOWER	1500	-
13	SWITCH YARD	1470	
14	POND	1200	-
15	DG SET	480	-
	COVERED PARKING	1000	
GROUND COVERAGE AREA		59568	46528
TOTAL GROUND COVERAGE AREA		**106096**	
GROUND COVERAGE PERCENTAGE		**49.97 %**	

THIS DRAWING & DESIGN IS THE SOLE PROPERTY OF VMS & SHALL NOT BE COPIED, TRACED OR REPRODUCED BY ANY MEANS WITHOUT PRIOR WRITTEN CONSENT OF THE FIRM.

GENERAL NOTES :

1. ALL THE DIMENSIONS ARE UNFINISHED DIMENSIONS.
2. ALL DIMENSIONS ARE IN MM AND LEVELS ARE IN MT, UNLESS OTHERWISE MENTIONED.
3. ALL THE DIMENSIONS SHALL BE READ & NOT TO BE MEASURED.
4. IN CASE OF ANY DISCREPANCY, BRING IT TO THE NOTICE OF THE ARCHITECT IMMEDIATELY.
5. DETAIL DRAWING PRECEDES THE GENERAL DRAWING

FOR TENDER

NO.	DATE	DESCRIPTION	DRAWN BY	CHECKED BY

REVISION HISTORY

REFERENCE DRAWINGS :
01. ARCHITECTURAL : -
02. STRUCTURAL : -
03. HVAC : -
04. ELECTRICAL : -
05. UTILITIES : -

-

MASTER LAYOUT

AGRAWAL METAL WORKS(P) LTD.

PROJECT NO.	**SCALE :** AS NOTED	DRAWN :	BHAKTI B.
3824		CHECKED:	DARSH D.
	DATE : **03-12-2024**	APPROVED:	DARSH D.
		COORDINATION CHECKED:	DARSH D.

VMS
ENGINEERING + ARCHITECTURE
VMS ENGINEERING & DESIGN SERVICES (P) LTD.
CHITRAKOOT FLATS, B/H TIMES OF INDIA, OFF ASHRAM ROAD,
AHMEDABAD-380 009. PHONE: +91 (079) 2658-8829, 4023-6236
WWW.VMSCONSULTANTS.COM

SHEET SIZE	DRAWING NO.	TENDER	REVISION:
600x 1200	**T.A.G.101**	**T**	**R0**