NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Gourav Engineers
Plot No W-32, 33. MIDC, Baramati
Dist : Pune - 413133

Date : 25.12.2019
Quote NO : SQT.19.20.2318
Kind Attn : Mr. Dnyaneshwar Raut
Email Id : da.raut@gouravgroup.com
Contact No: 9922998611

Project Name & Location: Barry Callebaut, Baramati

Subject : Quotation for High Speed Door, Al Double Wall Rolling Shutter, Dock Leveller, Dock Shelter.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2 , 3
C.	General Conditions	4
D.	Terms & Condtions	4

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**HIGH SPEED PVC ROLL UP DOOR**	3000	3000	7	327,000	2,289,000	18,000	126,000
2	**Al Double Wall Rolling Shutter**	6000	6300	1	551,000	551,000	18,000	18,000
2	**Al Double Wall Rolling Shutter**	4000	5000	6	314,000	1,884,000	18,000	108,000
2	**Al Double Wall Rolling Shutter**	3600	4000	1	239,000	239,000	18,000	18,000
2	**Al Double Wall Rolling Shutter**	4000	6300	1	384,000	384,000	18,000	18,000
3	**Dock Leveller - 15 Ton Capacity**	2200	2900	4	220,000	880,000	18,000	72,000
4	**Retractable Dock Shelter**	3200	3200	4	150,000	600,000	18,000	72,000
					Total	**6,827,000**		**432,000**
	P&F Charges			3%		204,810		
	Total Without Taxes					7,031,810		432,000
	GST Extra @ 18%			18%		1,265,726		77,760
	Total With Taxes					**8,297,536**		**509,760**
	Transportation Charges					**In Client Scope**		
	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

HIGH SPEED PVC ROLL UP DOOR




- Safe & for continous operations
- Self Supporting Construction with anti crash protection system for bottom profile
- Smooth & silent opening & closing
- Can be equipped with full vision PVC curtain
- Modular Interchaegable panels permit to replace worn & damged panels

Sr. No	Description	Specifications
1	Use	Internal Door
2	Speed	Inverter Motion system to adjust different speeds, with progressive control of acceleration & deceleration during braking
3	Opening speed	3 m/s
4	Closing speed	0.8 m/s
5	Control Panel	4 Push Button operated
6	Security Features	EN 13241-1 Standard
7	Resistance to wind load	EN12424 upto class 2
8	curtain	Fabric Transparent PVC section
9	Guide Material	Aluminum
10	Hood Cover	GI
11	Motor Cover	GI
12	Operator & Control	German Make Motor
13	Connecting Voltage	220V , 1Ph , N
14	Open-Stop-Close Button	Standarad
15	Protection Category	IP 54 / IP 65
16	Power Consumption	0.75 kw Motor
17	Emergency Off Button	Standard
18	Closing Zone Monitoring	Optical Safety edge
19	External Route Monitoring	Photocell
20	Emergency Opening	Crank Handle

B) Technical Specification

Aluminum Double Wall Rolling Shutter





Sr. No	Description	Specifications
1	Use	External
2	Opening Direction	Vertical - from bottom to Top
3	Curtain Material	Aluminum Non Insulated 19 mm thick profile
4	Guide Material	Aluminum - 100 x 2.5 mm thick
5	Curtain Profile	Curved
6	Bottom Profile	Aluminum bottom profile
7	Roller Shaft	M.S. Tubular Pipe with Flange & machined shaft
8	Side Brackets	MS Plate 3 mm to 10 mm thick , as per the opening dimension
9	Motor	Indirect Drive Motor
10	Motor Cover	GI - 0.8 mm thick
11	Hood Cover	GI - 0.8 mm thick
12	Open-Stop-Close Button	Standarad
13	Manual Operation	By Hand Crank


NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Dock Leveller





Sr. No	Description	Specification
1	Hydraulic Power pack	1 HP, 3PH
2	Control Panel	By push button Deck UP & Deck Down
3	Deck operation	By push button Deck UP & Deck Down
4	Lip operation	By push button Deck UP & Deck Down
5	Loading platform height from road Level	4 feet (1200 mm)
6	Travel above from Dock level height	350 mm
7	Travel below from Dock level height	200 mm
8	Deck platform size	2200mm (W) x 2900mm (L)
9	Lip sizes	400 mm
10	Clear Pit dimensions	2240mm (W) x 2900mm (L) x 485mm (H)
11	Drive type	Direct by electric Motor
12	Power Consumption	0.75 kw Motor
13	Degree of protection for motor	IP 55
14	Motor RPM	1410 rpm
15	Pump design flow	1.8 LPM
16	Pump pressure	200 bar
17	Safety valve set pressure	90 bar
18	Pump type	Gear
19	In built safety valve	Yes
20	Volume of oil receiver	8 Ltr
21	No of Deck Cylinders	2 Nos
22	Deck Plate Thickness	8 mm Chequered Plate
23	No of Lip Cylinders	1 No
24	Lip Plate	16 mm Thick Plate
25	Dock Bumpers	1 Pair included

B) Technical Specification

Retractable Dock Shelter



Sr. No	Description	Specification
1	Size	3200mm (W) x 3200mm (L)
2	Curtain colour	Black
3	Parking Guides	White, Yellow
4	Wall Fixings	Concrete, Sandwich light Concrete, Load house cavity, insulated panel
5	Top & Side Curtaiins	Double Layer High Quality Polyester
6	Thickness	3.0 mm
7	Weight	Approx 3400 g/m2
8	Continous Roof Cover	One layer high quality Polyester
9	Thickness	0.5 mm

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 9 - 10 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Arjun Patil on 8551096333**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd