NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Benzo Chem Industries Pvt. Ltd.
Jalgaon MIDC

Date : 28.02.2020
Quote NO : SQT.19.20.2471
Kind Attn : Mr. Prasenjit Bag
Email Id : civil@benzochem.co.in
Contact No: 6396687757

Subject : Quotation for Sliding Gate

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Condtions	2

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Motorised Single Leaf Sliding Gate	8500	1740	1	5,34,000	5,34,000	20,000	20,000
2	Motorised Single Leaf Sliding Gate	4580	1740	1	4,63,000	4,63,000	20,000	20,000
3	Motorised Single Leaf Sliding Gate	4880	1740	1	4,67,000	4,67,000	20,000	20,000
4	Motorised Single Leaf Sliding Gate	7000	1740	1	5,10,000	5,10,000	20,000	20,000
5	Manual Single Leaf Swing Wicket Gate	1500	1740	1	35,000	35,000	10,000	10,000
6	Manual Single Leaf Swing Wicket Gate	1200	1740	1	35,000	35,000	10,000	10,000
			Total Value			**20,44,000**		**1,00,000**
3			**P&F Charges**	3%		61,320		
			Total Without Taxes			**21,05,320**		**1,00,000**
			GST Extra @ 18%	18%		3,78,958		18,000
			Total With Taxes			**24,84,278**		**1,18,000**
4			Transportation Charges			**In Client Scope**		
5			Unloading Charges @ Site			**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) Technical Specifications

Sr. No	Description	Specifications
1	Door type	Motorised Single Leaf Sliding Gate
2	Clear Opening gate dimension	(W) 8500 mm X (H) 1740 mm (W) 4850 mm X (H) 1740 mm (W) 4880 mm X (H) 1740 mm (W) 7000 mm X (H) 1740 mm
3	Opening Direction	Horizontal - from left to right or reverse
4	Mounting Location area	Inside area
5	Design Pattern	Standard Tubular Design Pattern
6	Outer Frame Tube Sizes	72 x 72 x 3.2 mm
7	Internal Vertical Tube Sizes	32 x 32 x 2.6 mm
8	Gap Between Tubes	125 mm C/C
9	Bottom Rail on ground	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
10	Bottom Rollers	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
11	Guide Rollers supporter during Gate movement	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
12	Painting	Two Coats of Primer and Two Coats of Synthetic Enamel Paint
13	Safety	Flashing Light
14	Motor	100% Imported from Europe
15	Pair of Photocells with anodised aluminium vertical mountings	Included
16	Push Button	Included

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope
8	Lifting Equipements	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6 - 7 weeks from confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Ravindra Kharat on 7410169333**

With Best Regards
Vivek
8350570333
For NIHVA Technologies Pvt Ltd