NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

IKEA India Private Limited
10th Floor, Greenheart - Phase IV
Mfar Manyata Tech Park, Nagawara
Bangalore, Karnataka – 560045, INDIA

Date : 15.11.2019
Quote NO : SQT.19.20.1928R
Kind Attn : Mr.Atle
Email Id : atle.hovdenakk@ingka.ikea.com
Contact No: 70229 35388

Project Name & Location: Oasis, Mumbai

Subject : Quotation for Scissor Lift

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	Pit Mounted Scissor Lift	23000	30000	1	799,500	799,500	20,000	20,000
				Total		**799,500**		**20,000**
2			P&F Charges	3%		**23,985**		
			Total Without Taxes			**823,485**		**20,000**
			GST Extra @ 18%	18%		148,227		3,600
			Total With Taxes			**971,712**		**23,600**
3			Transportation Charges			**NIHVA Scope**		
4			Unloading Charges @ Site			**NIHVA Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

1 Pit Mounted Automatic Scissor Lift

Description	Specifications
Capacity	4.5 Ton
Platform Size	(W) 2300 mm x (L) 3000 mm
Shut Ht	600 mm
Max ht	2100 mm
Lift Ht	1500 mm
Power Pack	7.5 Hp, 3Phase
Safety Railing	900 mm only at length side
Color	A. Golden Yellow (RAL 1004) B. Ultra-Marine Blue (RAL 5002)
Hydraulic Lip	400 mm x 1800 mm (one side Only)

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax
chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different place	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6 - 7 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Arjun Patil on 8551096333**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd