NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Horizon Chutes Pvt. Ltd
11/16/2, Village Nanded,
Off Pune Sinhgad Road,
Pune – 411041

Date : 18.03.2020
Quote NO : SQT/19-20/2503
Kind Attn : Mr.Mahesh Limaye
Email Id : info@horizonchutes.com
Contact No: 98220 37079

Subject : Quotation for Hermetic Sealed Sliding Door and Sliding Door .

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specifications	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Automatic Hermetically Sealed Sliding Door.**	1400	2100	6	460,000	2,760,000	20,000	120,000
2	**Automatic Non Hermetically Sealed Sliding Door.**	1400	2100	4	310,000	1,240,000	20,000	80,000
				Total		**4,000,000**		**200,000**
3	P&F Charges			3%		120,000		
	Total Without Taxes					4,120,000		200,000
	GST Extra @ 18%			18%		741,600.00		36,000
	Total With Taxes					**4,861,600**		**236,000**
4	Transportation Charges					In Client Scope		
5	Unloading Charges @ Site					In Client Scope		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) **Technical Specifications** **Automatic Hermetic Sealed Sliding Door**

Laminate panel



Sr. No	Description	Specifications
1	**Passing space (PL)**	1400
2	**Passing space (PH)**	2100
3	**Door thickness**	60 mm
4	**Door frame**	Aluminium door frame
5	**Internal panel**	Core: extruded polystyrene plate Intermediate layer: MDF Surface cover: HPL laminate or stainless steel
6	**Seal**	Silicon
7	**Window**	600 x 400 mm [default dimensions] ø 400 mm [default dimensions]
8	**Handle**	Fixed handle: MAN 1 - MAN 2 * Mobile handle: MAN A1 - MAN A2 * Flush-fit handle: MAN I **
9	**Protection against radiation**	1, 2 or 3 mm thick lead strip

Valor HH

Sr. No	Description	Wings with hermetic seal
1	**Stroke control**	Encoder
2	**Power supply**	230 V AC / 50-60 Hz
3	**Power input**	0.041666667
4	**Operating temperature**	2°C / 55°C (2°C / 50°C with batteries)
5	**Protection rating**	IP 20
6	**Product dimensions (mm)**	150 x 300 x L
7	**Control panel**	EL32 (built-in)

B) **Technical Specifications** **Single leaf Automatic Sliding Door**

Sr. No	Description	Specifications
1	**Passing space (PL)**	1400
2	**Passing space (PH)**	2100
3	**Door thickness**	60 mm
6	**Density**	42kg/m3 with 0.6mm PPGI Finish .
7	**Vision Panel Size**	300 x 400 mm
8		PPGI Wall Frame , Heavy duty Aluminium Track, Aluminium Door Profile , SS 304 Door Opener & Closure, FDA Approved Gasket, Cladding , Canopy , SS 304 Integrated Pad Lock arrangement , both side push button and pull cord.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 10 - 11 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr.Arjun Patil on 8551096333** For any further Clarification /Information in this Concern.

With Best Regards
Ulka
7219206333
For NIHVA Technologies Pvt Ltd