GI Rolling Shutter - Salsette 27 Project - Mumbai

Schedule of Quantities and Prices

Sr. No.	Description	Unit	Quantity	Rate	Amount
1	Designing, providing, fabricating & fixing approved quality GI Motorized Rolling Shutter having two shutters (RS1 - 10.55m x 5.375m & RS2 - 4.135 x 5.375m) as given in drawings & instructions of architect including all leads, lifts, heights & required equipments, machines to complete the work. Following specifications to be followed for execution of work : Structural shape: Curved Shaft : Steel tube Bottom profiles : Bend-resistant aluminium profile for additional strength Weather resistant flexible EPDM tubular seal Noiseless operation Locking systems (applicable only for GI Bottom profile) : Internal & external locking Seals : On side guides Total Size of the gate : Width 14985mm x Height 5375mm Provision for other necessary features like emergency manual operation, sudden mechanical brake, etc. to be considered while designing the system Note: All GI / Steel sections needs to be provided with two coat of Zinc Chromate primer & one coat of Epoxy paint as per the colour approved by Architect. only one coat of primer needs to be done before dispatch & rest all the coats needs to be done at site.	M2	80.54	10,939	881,075
	Sub Total				**881,075**
	CGST @ 9%				79,297
	SGST @ 9%				79,297
	Total Amount including applicable taxes				**1,039,668**