NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Snowman Logistics Ltd
Snowman House 54, Old Madras Road,
Virgo Nagar, Bangalore, India - 560 049

Date : 10.06.2021
Quote NO : **MHE_21.22.0013**
Kind Attn : Mr. Rajdeep Bhoge
Email Id : rajdeep.bhoge@snowman.in
Contact No: 6366939008

Project Name & Location: Telescopic Conveyor, Bangalore

Subject : Quotation for Telescopic Conveyor

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Conditions	2

A) Commercial Offer

Sr No	Description	Qty	Supply Charges in INR		Installation Charges considering 03 people for 03 days in INR	
		(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Telescopic Conveyor (Total length 13 mtr)**	**1**	**12,10,000**	**12,10,000**	**75,000**	**75,000**
		Total		**12,10,000**		**75,000**
	P&F Charges	3%		**36,300**		
	Total Without Taxes			**12,46,300**		**75,000**
	GST Extra @ 18%	18%		**2,24,334**		**13,500**
	Total With Taxes			**14,70,634**		**88,500**
2	Transportation Charges					**Extra At Actual**
3	Insurance					**Extra At Actual**
4	Unloading Charges @ Site					**In Client Scope**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Telescopic Truck Loader/Unloader Conveyor

Sr. No.	Parameters	Specification
1	Collapsed Length	5000 mm
2	Telescopic Length	8000 mm
3	Total Length	13000 mm
4	No. of Extension Stages	3
5	Belt Width	500 mm
6	Belt Speed	30 mtr/min with (Variable through VFD)
7	Belt Direction	Bi-directional for loading and unloading
8	Power Supply	240 VAC, 50 Hz
9	Load Capacity	50 Kg/mtr

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

D) Terms & Conditions

Price : Ex Works Pune.

Delivery : 8 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 50% Advance along with Confirmed Purchase Order & Balance 50 % against readyness of material before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation.

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Rohit Kadgave on 7410175333.**

With Best Regards
Pratibha Mete
8530872333
For NIHVA Technologies Pvt Ltd