NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

GMR Hyderabad International Airport Limited
Hyderabad

Date : 09.06.2021
Quote NO : SQT.20.21.3111R2
Kind Attn : Sudheer Gokavarapu
Email Id : sudheer.gokavarapu@gmrgroup.in
Contact No: 9766711992

Project, Location : ECHO project, GMR, Hyderabad

Subject : Revised Quotation for Motorized Double Wall Rolling Shutter, Sectional Doors, Dock Leveler and Sliding Gate

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	2
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply + Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount
1	**Motorized Double Wall Rolling Shutter**	4000	5000	1	243,000	243,000
2	**Motorized Double Wall Rolling Shutter**	3600	3000	2	158,000	316,000
3	**Motorized Double Wall Rolling Shutter**	2400	3000	1	125,000	125,000
4	**ASSA ABLOY Sectional Door - Standard Lift (European Make) - OH1042P**	2400	2400	82	190,000	15,580,000
5	**Automatic Single Leaf Sliding Gate**	6000	3050	7	447,000	3,129,000
6	**Wicket Gate**	1200	2100	4	38,000	152,000
7	**Dock Leveler 6Ton**	2000	3000	32	190,000	6,080,000
	Total			**129**		**25,625,000**
8	P&F Charges			3%		768,750
	Total Without Taxes					26,393,750
	GST Extra @ 18%			18%		4,750,875
	Total With Taxes					**31,144,625**
9	Transportation Charges				**Extra at atcual**	
10	Unloading Charges @ Site				**In Client Scope**	

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Motorized Double Wall Rolling Shutter

Sr .No.	Specification	GI Motorized Double Wall Rolling Shutter
1	**Opening Direction**	Vertical - from bottom to Top.
2	**Mounting Location area**	Inside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete /Steel & Side
4	**Opening/Closing Speed**	0.1 m/sec
5	**Wind Resistance**	120 Km/hr
6	**Slats material**	insulated pre coated Galvanized steel (Polyurethane foam)
7	**Slat size**	95mm x 19mm with PU filled inside
8	**Curtain Panel**	The panel made of 1.0mm thick GI.
9	**Curtain panel size**	75mm wide
10	**Curtain Profile**	Curved
11	**Bottom Profile**	125mm x 15mm with extra angle support. (Optional - Rubber Bottom Seal)
12	**Side Guide Profile**	M.S." U" Shaped profile 125 x 40mm x 3 mm thick (as per the opening width dimension)
13	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
14	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
15	**Hood Cover**	Made of GI Sheet Thickness 0.8 mm with 25x25x3mm
16	**Surface finish**	Powder coated – Off white color.
17	**Drive Unit & Mounting Type**	Electric Motor (single phase / three phase) - Indirect Mounting - Sprocket chain arrangement
18	**Emergency Operation**	Option = Manual Hand Driven / Chain Wheel Drive

ASSA ABLOY Sectional Door - Standard Lift

Sr. No	Description	Specification
1	Model No	ASSA ABLOY OH1042P
2	Opening Direction & Mounting	Standard
3	Opening/Closing Speed	CDM9 0,28 m/s
4	Door Material	Steel
5	Panel Thickness	42 mm
6	Filling	CFC-free polyurethane
7	Door sealent	All door sealants made of EPDM rubber, temperature resistant - 30/+70
8	Water Penetration	EN 12425 class 3
9	Air Permealibity	EN12426 class 3
10	Thermal Transittance	EN 12428 1.10W /m2K
11	Bottom sealing	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber
12	Door saftey	Doors equiped with spring break device
13	Incase of Power failuer	Doors to be equiped with quick release fuction
14	Operator power conumption	Operator to have a maximum power consumption of 0,37kW and a standby consumption of Maximum 15W
15	Drive Unit & Mounting Type	Single phase 230V direct drive on shaft
16	Emergency Operation	by Disengagement rope manual
17	Operating Switch	Up/Down Keypad + stopbutton
18	Locks : Lock bolt	The Lock bolt locks the door from the inside, without the use of a key. The Lock bolt is not visible from the outside.
19	Environmental Green Product	As per ISO 14025 and EN 15804

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Motorized Single Leaf Sliding Gate

Sr .No.	Specification	Motorized Single Leaf Sliding Gate
1	**Door type**	Motorized Sliding Gate
2	**Opening Direction**	Horizontal - from left to right or reverse
3	**Mounting Location area**	Inside area
4	**Design Pattern**	Standard Tubular Design Pattern
5	**Outer Tube**	72 x 72 x 3.2mm MS SQ. TUBE
6	**For Post**	72 x 72 x 3.2mm MS SQ. TUBE
7	**Innear Tube**	38x38x3.20mm/40x40x3.2 MS SQ. TUBE
8	**Gap Between Tubes**	125mm
9	**Bottom Rail on ground**	dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
10	**Bottom Rollers**	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
11	**Guide Rollers supporter during Gate movement**	Nylon Rollers with Bearings both side mounted on column for support smooth movement of gate
12	**Painting**	2 Coats of EPOXY polyamide based enamel finish of approved colour
13	**El motor make**	BFT – Italy (100% imported)
14	**Emergency Operation**	Manual after turn the switch
15	**Operating Switch**	Push Button from inside
16	**Safety**	Photocells, Flashing Light

Wicket Gate

Sr .No.	Specification	Wicket Gate
1	Door type	Manual Single Leaf Wicket Gate
2	Size considered	Clear opening - (W)1200 mm x (H)2100 mm
3	Mounting Location area	Inside area
4	Design Pattern	Standard Tubular Design Pattern
5	Outer Frame Tube Sizes	80 x 80 x 3.2 mm
6	Internal Vertical Tube Sizes	40 x 40 x 2 mm
7	Gap Between Tubes	100 mm C/C
8	Painting	2 Coats of EPOXY polyamide based enamel finish of approved Colour
9	Operation	Manually Opening

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

Hydraulic Dock Leveler

Sr .No.	Specification	Specifications
1	**Capacity**	6 Ton
2	**Dock operation mode**	AC power pack hydraulically operated
3	**Lip operation mode**	Hydraulic
4	**Operation control**	Through panel
5	**Loading platform height from road**	1250mm
6	**Travel above & below dock level**	(+) 300 / (-) 250 mm
7	**Platform Size (W x L)**	2000 mm x 3000 mm
8	**Lip size (W x L)**	2000 x 400 mm
9	**Shut Height**	480 mm
10	**Overall length**	2000mm x 3000mm + Lip Length (400mm)
11	**Maximum slope can be achieved**	10%
12	**Clear Pit dimensions (W x L x D)**	(W) 2050mm x (L)3000 mm x (D)485 mm
13	**Hydraulic power pack**	Standard
14	**Driver type**	Direct by electric Motor
15	**Motor Ratings**	1 H.P
16	**Pump design flow**	2.5 LPM
17	**Pump pressure**	120 bar Operating 200 bar Max.
18	**Safety valve set pressure**	120 Kg/cm^2
19	**Pump Type**	Gear
20	**Volume of oil receiver**	7 Lit
21	**No Of Deck cylinder**	2 No
22	**Lip Cylinder**	1 No
23	**Yellow and Black Strips for Side Guide**	Included

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk,
MIDC, Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil / masonry/structural work required
5	All structure support required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 6 - 8 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 30% Advance along with Confirmed Purchase Order & 70% Balance before dispatch.

Validity : Validity of Offer is 30 days from the date of quotation

Please feel free to Contact **Mr. Shrikant Mirkute on 8551098333** For any further Clarification /Information in this Concern.

With Best Regards
Shailesh Bhoir
8551091333
For NIHVA Technologies Pvt Ltd