NIHVA
NIHVA TECHNOLOGIES PVT. LTD.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

JMC PROJECTS (INDIA) LIMITED
MOGHARPADA, Thane

Date : 12.10.2020
Quote NO : SQT.20.21.2758
Kind Attn : Mr. Muzaffar Madni
Email Id : Muzaffar.Madni@jmcprojects.com
Contact No: 8291349534

Project Name & Location: Thane, Maharashtra.

Subject : Quotation for Fire Rated Motorised Rolling Shutter and Gear Operated Rolling Shutter

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Gear Operated Rolling Shutter**	3000	4500	1	104,000	104,000	20,000	20,000
2	**Fire Rated Motorised Rolling Shutter**	4000	4000	1	300,000	300,000	20,000	20,000
3	**Fire Rated Motorised Rolling Shutter**	5500	6000	1	460,000	460,000	20,000	20,000
			Total Value			**864,000**		**60,000**
			P&F Charges	3%		25,920		
			Total Without Taxes			**889,920**		**60,000**
			GST Extra @ 18%	18%		160,186		10,800
			Total With Taxes			**1,050,106**		**70,800**
			Total (Supply + Installtion) with Taxes					**1,120,906**
4			Transportation Charges			**In Client Scope**		
5			Unloading Charges @ Site			**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) Technical Specifications





2 Hrs. Fire Rated Rolling Shutters - 100% IMPORTED

- **Shutter Slats: Zinc coated steel solid slats**
- **Slat Thickness: 1.0mm thick**
- **Shutter Guide: Galvanize Steel, 3mm thick**
- **Operated by: Motor with one unit push button switch & manual override**

Fire Rated Rolling Shutter

Sr .No.	Specification	Fire Rated Rolling Shutter
1	**Shutter Curtain**	Single Skin Design
2	**Guide Rail**	Powder coated
3	**Bottom Bar**	Powder coated
4	**Type of Mounting**	Standard
5	**Motor Drive Unit**	Power Source: 110v 60Hz 1 phase 220v 6OHz 1 phase 230v 50Hz 1 phase 400v 50Hz 3 phase Insulation Class E Manual Chain Override One unit push button switch Gravity drop level Auto close by relay switch after receive of 24vdc fire signal
6	**Standard RAL colors:**	RAL 9002

Gear Operated Rolling Shutter

Sr .No.	Specification	GI Gear Operated Rolling Shutter
1	**Description**	Gear Operated Rolling Shutter with GI Laths with thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete
4	**Curtain Panel**	The panel made of 1.0mm thick MS.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Día -100 to 300 mm as per w x h
10	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm GF mm with 25x25x3mm angle stiffener
11	**Surface finish**	2 Coats (each coat of 35 microns DFT) of EPOXY polyamide-based enamel finish of approved color and make over a Coat (each one coat 25 microns DFT) of EPOXY polyamide based red oxide zinc phosphate primer
12	**Operation**	Gear Assembly.

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	In Client Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Price Pune

Delivery : 10 - 11 weeks from confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% advance along with purchase order & balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 18 months from the date of Installation.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Ravindra Kharat on 7410169333.**

With Best Regards
Shailesh Bhoir
7219206333
For NIHVA Technologies Pvt Ltd