NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Shapoorji Pallonji & Co. Pvt. Ltd
Mumbai

Date : 16.10.2020
Quote NO : SQT.19.20.2769
Kind Attn : Ms. Nikita Lodha
Email Id : nikita.lodha@shapoorji.com
Contact No : 9518795636

Project Name & Location: Chennai Project

Subject : Quotation for Rolling Shutter,Sliding Glass Door, Sectional Door, Dock Leveller, Dock Shelter, Sliding Gate, Boom Barrier etc.

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	4

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**Fire Rated Motorised Rolling Shutter**	1600	5000	2	190,000	380,000	15,000	30,000
a)	**Fire Rated Motorised Rolling Shutter**	4000	4000	46	223,000	10,258,000	15,000	690,000
b)	**M S Motorised Rolling Shutter**	4600	5000	21	170,000	3,570,000	15,000	315,000
c)	**M S Motorised Rolling Shutter**	4600	4000	31	148,000	4,588,000	15,000	465,000
2	**BI Parting Metal Sliding Doors - 2 Panel Powder Coated 1.2 mm Galvanized**	3550	2100	1	190,000	190,000	15,000	15,000
3	**BI Parting Metal Sliding Doors - 2 Panel Powder Coated 1.2 mm Galvanized**	2130	2100	2	180,000	360,000	15,000	30,000
3	**NIHVA make Dock Leveller**	2200	3000	25	225,000	5,625,000	15,000	375,000
4	**Assa Abloy make Inflatable Dock Shelter**	3600	3755	25	403,000	10,075,000	20,000	500,000
5	**Sectional Doors**	4600	5000	6	290,000	1,740,000	20,000	120,000
6	**Motorised Sliding Gate**	6000	1500	4	366,000	1,464,000	15,000	60,000
a)	**Manual Wicket Gate**	1000	2000	4	36,000	144,000	15,000	60,000
7	**Boom Barrier - 6 Mtr**			4	120,000	480,000	15,000	60,000
				Total		**38,874,000**		**2,720,000**
8	P&F Charges			3%		**1,166,220**		
	Total Without Taxes					**40,040,220**		**2,720,000**
	GST Extra @ 18%			18%		7,207,240		489,600
	Total With Taxes					**47,247,460**		**3,209,600**
9	Transportation Charges					**In Client Scope**		
10	Unloading Charges @ Site					**In Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

M S Motorised Rolling Shutter

Sr .No.	Specification	Motorized Rolling Shutter
1	**Description:**	Motorised Rolling Shutter with MS Laths with thickness of 1 mm.
2	**Mounting Location area**	Inside area / Outside area
3	**Mounting Surface**	Side Brackets: Optional = On Concrete /Steel & Side
4	**Curtain Panel**	The panel made of 1.0mm thick MS.
5	**Curtain panel size**	75mm wide
6	**Curtain Profile**	Curved
7	**Bottom Profile**	M. S. Plate 100 mm x 2.5 mm thick with angle stiffener
8	**Side Guide Profile**	M.S." U" Shaped profile 65 mm -150 mm x 3 mm thick (as per the opening width dimension)
9	**Roller Shaft**	M.S. Tubular Pipe with Flange & machined shaft at the ends Pipe Dia -100 to 300 mm as per w x h
10	**Side Brackets**	MS Plate 3 mm to 10 mm thick, as per the opening dimension.
11	**Hood Cover**	Made of GI Sheet Thickness 0.9 mm GF mm with 25x25x3mm angle stiffener
12	**Surface finish**	PU paint or Powder coated
13	**Drive Unit & Mounting Type**	Indirect Drive, Electric Motor - Direct Mounting - Sprocket chain arrangement – IP54 Protection

Fire Rated Rolling Shutter

Sr .No.	Specification	Fire Rated Rolling Shutter
1	**Shutter Curtain**	Single Skin Design
2	**Guide Rail**	Powder coated
3	**Bottom Bar**	Powder coated
4	**Type of Mounting**	Standard
5	**Motor Drive Unit**	Power Source: 110v 60Hz 1 phase 220v 6OHz 1 phase 230v 50Hz 1 phase 400v 50Hz 3 phase Insulation Class E Manual Chain Override One unit push button switch Gravity drop level Auto close by relay switch after receive of 24vdc fire signal

Nihva Make Dock Leveller

Sr. No	Description	Specifications
1	Capacity	9 Ton
2	Dock operation mode	AC power pack hydraulically operated
3	Lip operation mode	Hydraulic
4	Operation control	Through panel
5	Loading platform height from road	1250mm
6	Travel above & below dock level	(+) 300 safe working height(+900 mm) / (-) 250 mm
7	Platform Size (W x L)	2200 mm x 3000 mm
8	Lip size (W x L)	2200 x 400 mm
9	Shut Height	480 mm
10	Overall length	3000mm + Lip Length (400mm)
11	Clear Pit dimensions (W x L x D)	(W) 2250mm x (L) 3000 mm x (D)480 mm
12	Hydraulic power pack	Standard
13	Driver type	Direct by electric Motor
14	Motor Ratings	1 H.P
15	Pump design flow	2.5 LPM
16	Pump pressure	120 bar Operating 200 bar Max.
17	Safety valve set pressure	120 Kg/cm²
18	Pump Type	Gear
19	Volume of oil receiver	7 Lit
20	No Of Deck cylinder	2 No
21	Lip Cylinder	1 No
22	Structure	Included
23	Maximum slope can be achieved	10%
24	Dock Bumper	Pair of Dock Bumper

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

ASSA ABLOY Motorised Sectional Doors

Sr .No.	Specification	Sectional Door -NIHVA Assa abloy
1	Model No	ASSA ABLOY OH1042P
2	Opening Direction & Mounting	Vertical
3	Opening/Closing Speed	CDM9 0,28 m/s
4	Door Material	Steel
5	Panel Thickness	42 mm Square Grid, steel sheet
6	Filling	CFC-free polyurethane
7	Door sealent	All door sealants made of EPDM rubber, temperature resistant -30/+70
8	Water Penetration	EN 12425 class 3
9	Air Permealibity	EN12426 class 3
10	Thermal Transittance	EN 12428 1.10W /m2K
11	Bottom sealing	Bottom of the door to be equiped with three lip sealing made of oil resistant EPDM rubber
12	Door saftey	Doors equiped with spring break device; Safety Photo cell, bottom safety edge, rope break mechanism etc.
13	Incase of Power failure	Doors to be equiped with quick release fuction
14	Operator power conumption	Operator to have a maximum power consumption of 0,37kW and a standby consumption of
15	Drive Unit & Mounting Type	Single phase 230V direct drive on shaft
16	Emergency Operation	by Disengagement rope manual
17	Operating Switch	Up/Down Keypad + stopbutton
18	Locks : Lock bolt	The Lock bolt locks the door from the inside, without the use of a key. The Lock bolt is not
19	Environmental Green Product Declaration	As per ISO 14025 and EN 15804
20	Structure	Included

Boom Barrier

Sr. No.	Description	Specifications
1	Size	6 Meter
2	Model No	Michealangelo 60
3	Opening Time	6 S
4	Slowdown	Adjustable
5	Motor Power Supply	24 V
6	Type of limit Switch	Electronic
7	Frequency of Use	Continuous Use
8	Protection Rating	IP54
9	Lock	Mechanical

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Assaabloy Inflatable Dock Shelter

Sr. No.	Description	Specifications
1	Door type	Dock Shelter DS6070B
2	Clear Opening dimension	Size:(W) 3600 mm x (H) 3755 mm
3	Curtain colour	Black
4	Parking Guides	White, Yellow
5	Wall Fixings	Concrete, Sandwich light Concrete, Load house cavity, insulated
6	Top & Side Curtaiins	Double Layer High Quality Polyester
7	Thickness	3.0 mm
8	Weight	Approx 3400 g/m2
9	Continous Roof Cover	One layer high quality Polyester
10	Thickness	0.5 mm
11	Weight	Approx 680 g/m2

Motorised Single Leaf Sliding Gate

Sr. No.	Description	Specifications
1	Opening Direction	Horizontal - from left to right or reverse
2	Mounting Location area	Inside area
3	Design Pattern	Standard Tubular Design Pattern
4	OUTER TUBE	72 x 72 x 3.2mm MS SQ. TUBE
5	FOR POST	72 x 72 x 3.2mm MS SQ. TUBE
6	INNEAR TUBE	38x38x3.20mm/40x40x3.2 MS SQ. TUBE
7	Gap Between Tubes	125mm
8	Bottom Rail on ground	Dia 20 mm round bright bar with heavy duty support ISMB 100 X 50 Beams
9	Bottom Rollers	Heavy Duty Bottom Wheel With both side Bearings (chorme plated)
10	Guide Rollers supporter during Gate	Nylon Rollers with Bearings both side mounted on column for support smooth movement of
11	Painting	2 Coats of EPOXY polyamide based enamel finish of approved colour
12	El motor make	BFT – Italy (100% imported)
13	Emergency Operation	Manual after turn the switch
14	Operating Switch	Push Button from inside
15	Safety	Photocells, Flashing Light

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2008 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: **Please find below List which are in Client Scope**

Sr. No	**Description**
1	Secured and fully covered Store area to keep the material
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site
3	Electrical Supply on the site single phase/three phase points at different places.
4	Any civil structural work required
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.
7	Conduits, Cables required

D) Terms & Conditions

Price	: Ex Works Pune
Delivery	: 1) 4 -5 weeks for sr.no. 1,2,3,6, 7 from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval. 2) 10-12 weeks for sr. no. 4 &5 from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval
Payment	: 40% Advance along with Confirmed Purchase Order & Balance against readyness of material before dispatch.
Validity	: Validity of Offer is 15 days from the date of quotation
Warranty	: 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr. Shrikant Mirkute on 8551098333 .**

With Best Regards
Smita Khare
9637991333
For NIHVA Technologies Pvt Ltd