NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

John Deere India Pvt Ltd
Sanasawadi
Pune - 412208

Date : 25.12.2019
Quote NO : SQT/19-20/2307R1
Kind Attn : Mr. Sachin Jadhav
Email Id : JadhavSachin@JohnDeere.com
Contact No: 9922924980

Subject : Quotation for High Speed Door RR 3000 ISO_High Sea Sale Pricing

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions.
This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Height (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**High Speed Door RR3000ISO**	4000	4500	5	9,70,000	48,50,000	15,000	75,000
2	**High Speed Door RR3000ISO**	6000	6000	1	12,65,000	12,65,000	15,000	15,000
3	**High Speed Door RR3000ISO**	4000	4000	2	9,27,000	18,54,000	15,000	30,000
4	**High Speed Door RR3000ISO**	4500	4500	1	9,85,000	9,85,000	15,000	15,000
5	**High Speed Door RR3000ISO**	3000	4400	1	8,95,000	8,95,000	15,000	15,000
			Total			**98,49,000**		**1,50,000**
6	P&F Charges			NIL				
	Total Without Taxes				98,49,000		1,50,000	
	GST Extra @ 18%			NA				
	Total With Taxes				**98,49,000**		**1,50,000**	
7	Transportation Charges				Included in above Prices			
8	Unloading Charges @ Site				NIHVA Scope			

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

Sr. No	Description	Details
		High Speed Door RR3000ISO
1	Door construction:	consists of highly thermally insulated sandwich lamellas consisting of foam (thickness 50 mm) covered by metal sheet trays in silver (RAL 9006). A doubled sealing system links the lamellas ensuring excellent wind and water tightness and a smooth run of the door
2	Side Frames	Made up with Galvanised Steel Profiles
3	Thermal transmittance:	Door blade 1,4 W/m²K Complete door min 1,5 W/m²K
4	Wind resistance:	class 2-3 (EN 12424) DW ≤ 5000 mm: class 3 DW > 5000 mm: class 2
5	Contactless Winding :	The innovative Disc Drive technology used in the Albany RR3000 ISO supports the door curtain movement thereby ensuring a long service life. The slats are wound onto windling discs without contact. Using this technology, the door can be opened and closed very quickly and with no wear.
6	Drive Unit :	Gear motor 1,1 KW. Chain drive to reduce mounting space to the side
7	Temperature range :	-20°C to +40°C (mounting side)
8	Protection :	IP55
9	Control system:	Albany MCC, with vector control technology and boost function at start-up. Graphic display and foil keypad for easy guided operation. Easy access to all important information for operation and service
10	Control Voltage	24 V DC
11	Power supply:	3/N/PE 380/400/415/440/480 V; 50/60 Hz.
12	Speed:	Opening / closing up to 2,1 / 0,7 m/s.
13	Safety device:	Door line photo-cell, drop down protection by integrated balancing system
14	Manual activation :	by releasing the brake at ground level. Partly opening by means of the pre-stressed tension springs.
15	Heat transfer coefficient :	Door blade 1,4 W/m²K
16	**Options :**	**Window slats: Lamellas with transparency window slats**

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015Certified Company

GST Pune : 27AAECN0437H1ZM

Special Note for High Sea Sale

1 Above prices are CIF prices by Sea which are without any custom duty, clearance and Taxes.

2 There will be High Sea Sales agreement between NIHVA and John Deere India ltd, this is to signed by both parties before arrival of equipment at Seaport

3 Since this is Sea consignment both the parties will have to take at most care during this transaction as the agreement is required to discharge in between the period of dispatch and receipt at sea port

4 For any reason if consignment gets hold at custom NIHVA will not be responsible for any delayed charged or penalty.

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	**Custom Duty + Custom Clearance, till site in clients Scope. NIHVA will handover BL to client for further all process & action till material reaches at site & unloads at required place.**	In Client Scope
2	Secured and fully covered Store area to keep the material	In Client Scope
3	Scaffolding/Hydra/Crane/Forklift Etc - Required for Installation at Site	NIHVA
4	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
5	Any civil / masonry/structural work required	In Client Scope
6	All structure support required	In Client Scope
7	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
8	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : CIF Nava Seva Mumbai

Delivery : 13 - 14 weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

Please feel free to Contact **Mr. Arjun Patil on 8551096333** For any further Clarification /Information in this Concern.

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd