
GENERAL NOTES:-

1. ALL DIMENSIONS ARE IN mm. & LEVELS ARE IN mts.
2. ALL DIMENSIONS & LEVELS SHALL BE CHECKED WITH ARCHITECTURAL DRAWING. ANY AMBIGUITY, IF FOUND, SHALL BE BROUGHT TO THE NOTICE OF THE ARCHITECT/ENGINEER BEFORE EXECUTION OF THE WORK.
3. THE CONTRACTOR SHALL REFER TO THE ARCHITECTURAL G.A., CIVIL, MECHANICAL G.A. AND ELECTRICAL G.A. DRAWINGS FOR CO-ORDINATE, SIZE AND LOCATION OF ALL OPENINGS, SLEEVES, CHASES, CONDUITS, DEPRESSED AREAS, FLOOR FINISHES, FILLS, ANCHORS, MASONRY DETAILS, HANGERS, POCKETS, CURBS, FOUNDATION BOLTS, INSERTS, MISCELLANEOUS STEEL, ETC. BEFORE PLACING CONCRETE.
4. THE CONTRACTOR SHALL GIVE DUE CONSIDERATION TO ALL SAFETY MEASURES DICTATED BY INDIAN CODES OF PRACTICE.
5. CONTRACTOR SHALL TAKE CARE OF ALL UNDER GROUND UTILITIES OF CIVIL, MECHANICAL, ELECTRICAL AND OTHER SERVICES AS THEY INTERFACE WITH STRUCTURAL FOUNDATIONS AND OTHER UNDERGROUND WORKS.
6. SAND/EARTH FILLING SHALL BE DONE SIMULTANEOUSLY ON BOTH SIDES OF WALL.
7. APPROVED EARTH FILLING SHALL BE DONE IN LAYERS NOT EXCEEDING 300mm. ADEQUATELY WATERED AND WELL COMPACTED.
8. ANY INSERTS REQUIRED FOR LIFT INSTALLATION SHALL BE PLACED BEFORE CONCRETING AS PER LIFT SUPPLIER'S DRAWINGS AND MANUALS.
9. SUPPORTS OF CANTILEVER SLAB/BEAM SHALL NOT TO BE REMOVED UNTIL THE SLAB/BEAM & SUPPORTING SLAB/BEAMS/COLUMNS ACHIEVE COMPLETE STRENGTH.
10. DE-SHUTTERING PERIODS: IN NORMAL CIRCUMSTANCES. FORMS SHALL GENERALLY BE REMOVED AFTER EXPIRY OF THE FOLLOWING PERIODS :-
    A). WALLS, COLUMNS AND VERTICAL FACES OF ALL STRUCTURAL MEMBERS INCLUDING SIDES OF BEAMS. ..... 24 HOURS
    B). SLABS:
        1). SPANNING UP TO 4.5 M. ..... 7 DAYS
        2). SPANNING OVER 4.5 M. ..... 14 DAYS
    C). BEAMS AND ARCHES:
        1). SPANNING UP TO 6 M. ..... 14 DAYS
        2). SPANNING OVER 6 M. ..... 21 DAYS
11. REINFORCEMENT SHALL BE ADJUSTED SUITABLY AT SITE FOR PROVIDING CLEAR THE INSERTS. BOLTS, POCKETS ETC. UNLESS SPECIFIED OTHERWISE ON THE DRAWING.
12. SBC OF SOIL IS CONSIDERED AS PER BELOW TABLE AS PER SOIL INVESTIGATION REPORT BY M/S. KCT CONSULTANCY DOCUMENT NO. ST/24/10/19262.


DEPTH FROM N.G.L. (M)	S.B.C. (T/M^2)
2.0	13.00

NOTES FOR STEEL WORKS:-


1. ALL WELD TO BE 6mm FULL FILLET WELD. UNLESS SPECIFIED OTHERWISE.
2. ALL STEEL SHALL BE TESTED QUALITY TO CONFIRM TO I.S. 2062.
3. ALL WELDING SHALL CONFIRM TO I.S. 816 & 1323.
4. ALL FABRICATION SHALL CONFIRM TO I.S. 800.
5. BEFORE COMMENCING FABRICATION THE CONTRACTOR SHALL VARIFY ALL DIMENSIONS AT SITE AS WELL AS WITH THE ARCHITECTURAL DRAWING INCLUDING CLEARANCES, IF ANY.
6. DURING ERECTION, CONTRACTOR SHALL TAKE FULL PRECAUTION TO SUPPORT OR TIE ALL MEMBERS UNTIL FINAL GROUTING/WELDING OR BOLTING AT JOINT IS COMPLETED AS PER DRAWING.
7. ALL STRUCTURAL STEEL WORK SHALL CONFIRM TO FOLLOWING STANDARD CODES:
    (I) FOR STRUCTURAL STEEL (QUALITY) – IS:2062
    (II) FOR METAL ARC WELDING – IS:816
    (III) FOR STRUCTURAL USE OF R.H.S. / S.H.S. – IS 4923
    (IV) FOR GENRAL CONSTRUCTION OF R.H.S. / S.H.S. – IS:806
    (V) FOR TOLERANCES IN STEEL STRUCTURES – IS:7215
    (VI) FOR SAFETY AGAINST ERECTION WORK – IS:7205
    (VII) FOR HEXAGONAL SCREW / NUT / BOLTS – IS: 1363/ IS:1364
    (VIII) FOR PAINTING OF STEEL WORK – IS:1477
    (IX) WASHERS FOR STEEL WORK – IS: 5372/IS:5374
    (X) FOR GENERAL PURPOSE – IS:800
8. HOLES, WHEREVER REQUIRED, SHALL BE MADE BY DRILLING AND HOLES MADE BY GAS CUTTING SHALL NOT BE ALLOWED.
9. PROVIDE WASHERS UNDER ALL NUTS & BOLT HEADS, WHERE THE HEAD IS NOT EMBEDDED.
10. ERECTION JOINT SHALL BE FULLY WELDED AT SITE AFTER ERECTION.
11. DURING ERECTION, TRUSS TO BE LIFTED FROM MINIMUM TWO POINTS/SUPPORTS. A CROSS TIE (PIPE) BETWEEN THE TWO SUPPORTS SHALL BE PROVIDED TO PREVENT LATERAL BUCKLING OF TRUSS.
12. ALL STEEL WORK SHALL BE PAINTED AS PER SPECIFICATIONS.
13. ALL FOUNDATION BOLTS ARE OF 4.6 GRADE & STRUCTURAL CONNECTION BOLTS ARE ON 8.8 GRADE U.N.O.
14. IN CASE OF DISCREPANCY IN MEMBER SIZE SHOWN IN GENERAL ARRAGEMENT DRAWING & STRUCTURAL DRAWING, THE SIZE GIVEN IN STRUCTURAL DRAWING SHALL GOVERN.
15. BUTT WELDS WHERE INDICATED IN THE DRAWINGS ARE TO BE COMPLETE PENETRATION FULL STRENGTH BUTT WELDS.
16. REMOVE ALL WELD SPATTER, FLUX, DAGS AND BURRS FROM STEELWORK. GRIND FLUSH ALL SEALING AND BUTT WELDS.



TYP. DETAILS OF HOOP AND CROSS TIE FOR WALLS



TYP. PERIPHERY WALL SECTION



TYP. WALL SECTION FOR WATER TANK

A :-NOTES FOR R.C.C. WORKS:-

1. ALL CONCRETE SHALL BE MACHINE MIXED & MACHINE VIBRATED.
2. T-INDICATES HIGH YIELD STRENGTH DEFORMED BARS CONFIRMING TO IS:1786 OR EQUIVALENT WITH 0.2% PROOF STRESS OF 500/550 N/mm^2 (Fe500D/Fe550D).
3. CURING OF CONCRETE MEMBERS SHALL BE CARRIED OUT FOR A MINIMUM PERIOD OF 12 DAYS AFTER CASTING BY PONDING OR COVERING SURFACE BY JUTE BAGS KEPT CONSTANTLY WET OR SUCH OTHER MEANS.
4. GROUTING SHALL BE DONE WITH NON-SHRINK GROUT. NO ADDITIONAL MATERIAL/ADMIXTURES SHALL BE ADDED.
5. LEGENDS:-

P.C.C	PLAIN CEMENT CONCRETE
T20-125 C/C	T = BAR GRADE & TYPE 20 = NOMINAL BAR DIA IN mm. 125 = SPACING IN mm. C/C = CENTER TO CENTER DISTANCE

F.G.L	FINISHED GROUND LEVEL
F.P.L	FINISHED PLINTH LEVEL
N.G.L	NATURAL GROUND LEVEL
TYP	TYPICAL
SFR	SIDE FACE REINFORCEMENT
U.N.O.	UNLESS NOTED OTHERWISE

6. MINIMUM CLEAR COVER TO REINFORCEMENT BARS SHALL BE AS FOLLOWS (U.N.O.)

FOOTING/RAFT	:50mm	R.C.C WALL	:30mm		
COLUMNS	:40mm	FLOOR BEAM	:30mm	LIQUID RETAINING STRUCTURE	:45mm
PLINTH BEAM	:30mm	FLOOR SLAB	:25mm		
SLAB ON GRADE	:40mm				

7. GRADE OF R.C.C (U.N.O.)

		FLOOR BEAM	:M25
FOOTING	:M25	FLOOR SLAB	:M25
COLUMNS	:M25	GRADE SLAB	:M25
R.C.C WALL	:M25	LIQUID RETAINING STRUCTURE	:M30

8. LAP LENGTH FOR REINFORCEMENT
   Ld = DEVELOPMENT LENGTH d = DIA. OF BAR

CONCRETE GRADE	REINFORCEMENT GRADE Fe-500 D
M20	60d
M25	50d
M30	46d
M35	40d
M40 & ABOVE	36d

B :-NOTES FOR R.C.C. COLUMN:-

1. SUSPENDER BARS SHALL NOT BE LAPPED. THE BARS SHALL BE ANCHORED IN TO THE SUPPORTING BEAM BY FULL DEVELOPMENT LENGTH. SUPPORT OF BEAMS SUPPORTED BY SUSPENDER MEMBERS SHALL NOT BE REMOVED UNTIL THE SUPPORTING BEAM HAS ACHIEVED FULL SPECIFIED STRENGTH. (i.e. AFTER 28 DAYS.)
2. WHEN BARS OF TWO DIFFERENT DIAMETERS ARE TO BE SPLICED,THE LAP LENGTH SHALL BE CALCULATED ON THE BASIS OF DIAMETER OF THE SMALLER BAR.
3. NOT MORE THAN 50% OF THE BARS SHALL BE LAPPED AT A SECTION.

C :-NOTES FOR R.C.C WALL:-

1. HORIZONTAL STEEL LINKS TO BE PROVIDED TO KEEP WALL STEEL IN PROPER POSITION.
2. CLEAR COVER AT ALL FACE IN CONTACT WITH LIQUID SHALL BE 45mm.

D :-NOTES FOR R.C.C BEAM/SLAB:-


1. PROPS. FOR INVERTED BEAM AND SLAB BEAM TO BE KEPT AS PER REGULAR BEAMS.
2. STEEL CHAIRS SHALL BE PROVIDED TO KEEP TOP STEEL OF SLAB IN PROPER POSITION.

E :-NOTES FOR WATER RETAINING STRUCTURE:-

1. HORIZONTAL STEEL LINKS TO BE PROVIDED TO KEEP WALL STEEL IN PROPER POSITION.


F :-NOTES FOR BRICK MASONRY WORK:-

1. ALL MASONRY WORKS ARE NON-STRUCTURAL EXCEPT WHERE STATED.
2. ALL BRICK MASONRY SHALL BE DONE IN 1:4 C.M. BELOW PLINTH & 1:6 C.M. (CEMENT:MORTAR) ABOVE PLINTH.
3. MIN. CRUSHING STRENGTH OF BRICK USED FOR MASONRY WORK OF THE BUILDING SHALL BE 35 KG/CM^2.
4. FOR PLASTER DETAILS REFER TENDER SPECIFICATIONS.




FOUNDATION FOR 230 TH. BRICK WALL ON GRADE SLAB

FOR WALL UP TO +2.40 mt.




FOUNDATION FOR 115 TH. BRICK WALL ON GRADE SLAB


FOR WALL UP TO +2.40 mt.




TYP. LINTEL & RUNNER JUNCTION DETAILS




PLAN OF REINFORCEMENT AT WALL CORNERS AND JUNCTIONS FOR COPING, RUNNER & LINTEL




TYP. DETAILS FOR GRADE SLAB



TYP. STEEL CHAIR DETAILS IN SLAB




TYP. HOOP DETAILS IN BEAM




TYPICAL DETAILS OF LAP IN MAIN BEAM STEEL

ONLY 50% OF BARS SHALL BE LAPPED AT SAME LOCATION.

LAP LENGTH = DEVELOPMENT LENGTH OF LARGER DIA BAR.



DETAILS OF EXTRA STIRRUPS IN MAIN BEAM AT SECONDARY BEAM JUNCTION




DETAIL-A


TYPICAL DETAILS AT BEAM TO COLUMN JUNCTION

CONTRACTOR SHALL SELECT SUITABLE OPTION AS PER SITE CONDITION.


BEAM R/F SHALL BE EXTENDED UP TO OPPOSITE FACE OF COLUMN BY MAINTAINING COVER.




TYP. DETAIL OF STIRRUPS AT LAP IN BEAM STEEL




TYP. JUNCTION DETAILS OF MAIN BEAM & SECONDARY BEAM



TYP. DETAIL OF HOOP AND CROSS TIE IN COLUMN



TYP. END DETAILS OF SECONDARY BEAM



TYP. SECTION FOR FOOTING & PEDESTAL

THIS DRAWING & DESIGN IS THE SOLE PROPERTY OF VMS & SHALL NOT BE COPIED, TRACED OR REPRODUCED BY ANY MEANS WITHOUT PRIOR WRITTEN CONSENT OF THE FIRM.

GENERAL NOTES :

NO.	DATE	DESCRIPTION	DRAWN BY	CHECKED BY

REVISION HISTORY

KEY PLAN
SCALE : N.T.S.

REFERENCE DRAWINGS :

01. ARCHITECTURAL :	-
02. STRUCTURAL :	-
03. HVAC :	-
04. ELECTRICAL :	-
05. UTILITIES :	-

GENERAL NOTES, SPECIFICATION & DETAILS

AGRAWAL METAL WORKS(P) LTD.

PROJECT NO. 3824	SCALE : 1:100	DRAWN :	SHYAM
		CHECKED:	SMIT
	DATE : 05-12-2024	APPROVED :	MAULESH
		COORDINATION CHECKED:	DARSH

VMS ENGINEERING + ARCHITECTURE
VMS ENGINEERING & DESIGN SERVICES (P) LTD.
CHITRAKOOT FLATS, B/H TIMES OF INDIA, OFF ASHRAM ROAD,
AHMEDABAD-380 009. PHONE: +91 (079) 2658-8829, 4003-8236
WWW.VMSCONSULTANTS.COM

SHEET SIZE	DRAWING NO.	TENDER	REVISION:
600x 1000	S.G.101	T	R0