NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

NIHVA Sales Quotation

Fabtech
502, Vishakha Archade, Opp. Coutyard Hotel,
Behind Mogaveera Bhavan, Off Veera Desai Road,
Andheri (W), Mumbai - 400058, INDIA

Date : 21.08.2019
Quote NO : SQT.19.20.1955
Kind Attn : Mr. Shaikh Azhar
Email Id : azhar.shaikh@fabtechnologies.com
Contact No: 9664786331

Project Name & Location:

Subject : Quotation for High Speed Door

Dear Sir,

Thank you for your opportunity and trust shown on "NIHVA" your preferred partner for innovative solutions. This has reference to your above mentioned requirement, please find below our Solutions.

Sr. No	Description	Pages
A.	Commercial Offer	1
B.	Technical Specification	2
C.	General Conditions	3
D.	Terms & Condtions	3

A) Commercial Offer

Sr No	Description	Size		Qty	Supply Charges in INR		Installation Charges in INR	
		Clear Width (mm)	Clear Length (mm)	(Nos)	Unit Price	Total Amount	Unit Price	Total Amount
1	**High Speed Door - RR300+ Stainless Steel (Sealed)**	4200	2400	2	6,90,000	13,80,000	20,000	40,000
2	**High Speed Door - RR300+ Stainless Steel (Sealed)**	5000	2400	6	7,08,000	42,48,000	20,000	1,20,000
3	**High Speed Door - RR300+ Alu**	1500	2400	4	5,46,000	21,84,000	20,000	80,000
				Total		**78,12,000**		**2,40,000**
4	P&F Charges			3%		**2,34,360**		
	Total Without Taxes					**80,46,360**		**2,40,000**
	GST Extra @ 18%			18%		14,48,345		43,200
	Total With Taxes					**94,94,705**		**2,83,200**
5	Transportation Charges					**Extra at Actual**		
6	Unloading Charges @ Site					**At Client Scope**		

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

B) Technical Specification

NIHVA ASSA ABLOY High Speed Door - Air Tight Doors (Sealed)

Sr. No	Description	Specifications
1	Model No	RR300+ Stainless Steel
2	Door Opening	Flexible High-performance door, opening in vertical direction for interior use in wind-protected areas
3	Self-supporting side frames	made of stainless steel
4	Door curtain	made of transparent PVC with fabric reinforcement stripes, ultramarine (similar to RAL 5002) or red (similar to RAL 3002).
5	Wind protection	through wind tabs on the door curtain
6	Bottom Profile	Stainless Steel
7	Protection	IP55
8	Control system:	Frequency converter control system Albany MCC, based on vector control including boost function at start-up. Graphic display and foil keypad for easy guided operation. Easy access to all important information for operation and service
9	Opening & Closing Speed	Max. 2.2/0.9 m/s
10	Supply voltage	3L(N)PE/380/400/415/440/480V;50/60Hz
11	Safety devices	electrical safety contact edge, Photocell
12	Top Cover	Top Cover Stainless Steel
13	Motor Cover	Motor cover in plastic grey (similar RAL 7040)

B) Technical Specification

NIHVA ASSA ABLOY High Speed Door - Warehouse application

Sr. No	Description	Specifications
1	Model No	RR300+ Alu
2	Door Opening	Flexible High-performance door, opening in vertical direction for interior use in wind-protected areas
3	Self-supporting side frames	made of Alu anodised
4	Door curtain	made of transparent PVC with fabric reinforcement stripes, ultramarine (similar to RAL 5002) or red (similar to RAL 3002).
5	Wind protection	through wind tabs on the door curtain
6	Bottom Profile	made of Alu anodised
7	Protection	IP55
8	Control system:	Frequency converter control system Albany MCC, based on vector control including boost function at start-up. Graphic display and foil keypad for easy guided operation. Easy access to all important information for operation and service
9	Opening & Closing Speed	Max. 2.2/0.9 m/s
10	Supply voltage	3L(N)PE/380/400/415/440/480V;50/60Hz
11	Safety devices	electrical safety contact edge, Photocell
12	Top Cover	made of Alu anodised
13	Motor Cover	Motor cover in plastic grey (similar RAL 7040)

NIHVA Technologies Pvt. Ltd.
187, G-Block, 1st Floor, Above Renault Showroom, Thermax chowk, MIDC,
Chinchwad.
Pune – 411019

An ISO 9001:2015 Certified Company

GST Pune : 27AAECN0437H1ZM

C) General Conditions

1 Installation will start after receiving of Site Readyness Photographs or written Email communication.

2 We will mobilize the Installation Team in 3 - 4 working days, after reciept of Site Readyness Confirmation

3 For any reason if we need to stop our Installation and demobilize the Team without completing the Work, then extra cost will be applicable for Remobilizing the Team.

4 If Lifting Equipements are in NIHVA Scope, then those will be used for Installation purpose only and not for any other works.

Note: Please find below List which are in Client Scope

Sr. No	Description	Remark
1	Secured and fully covered Store area to keep the material	In Client Scope
2	Scaffolding/Hydra/Crane/Forklift etc - Required for Installation at Site	NIHVA Scope
3	Electrical Supply on the site single phase/three phase points at different places.	In Client Scope
4	Any civil / masonry/structural work required	In Client Scope
5	All structure support required	In Client Scope
6	In Case of any changes in the layout as per site requirements after the shipment of material , the additional quantities and the wastage.	In Client Scope
7	Conduits, Cables required	In Client Scope

D) Terms & Conditions

Price : Ex Works Pune

Delivery : 11-12 Weeks from the date of receipt of confirmed purchase order, Advance Payment & Drawing approval.

Payment : 80% Advance along with Confirmed Purchase Order & Balance before dispatch.

Validity : Validity of Offer is 15 days from the date of quotation

Warranty : 12 months from the date of supply.

For any further Clarification /Information in this Concern, Please feel free to Contact **Mr.Arjun Patil on 8551096333**

With Best Regards
Varsha
8551091333
For NIHVA Technologies Pvt Ltd