WORK ORDER

Client- T&R
NTPL- 244-PM
Address:

PO Number:	MPROJ0177	W. O. No	SO/24-25/007
PO Dated :	26-Jul-24	W. O. Date	01.08.2024
PO Received Date:	30-Jul-24	Sales Co ordinator	Ganesh Kulkarni
Ref. Quotation:	RR_23.24.0213R5	Front Sales Person	Pranav Marne

Contact Details		Billing Address:	Dispatch Address:
Contact Person:			
Email ID:			
Mobile:			

Sr. No	Description of Goods	Technical Details	UOM	Qty.	Rate	Amount	Dwg. Approval
1	Customized Design, Manufacturing and Installation of RR for Vertical machine winding shop	•(W)14m X (L)34m X (H)5m	NO	1	0	0	Not yet
2	Customized Design, Manufacturing Process and Installation of Horizontal Machine winding shop	(W)14m X (L)40m X (H)5m		1		0	
3	Customized Design, Manufacturing Process and Installation of Assembly Shop (Motorised)	(W)7.5m X (L)12m X (H)6.5 m at Center X 6 panel (One side opening and stacking)		4		0	
4	Customized Design, Manufacturing Process and Installation of Tanking Pit (Operation- Manual)	(W)8.7m X (L)23.4m X (H)3.5 m at center X 8 Panel (Centre opening and stack at both end)		1		0	

*** Scope of Work**

Sr no	Machines	Sizes	Customized Design, Manufacturing Process and Installation of,	Qty of Set
1	Vertical machine winding shop	(W)14m X (L)34m X (H)5m	Motorized Retractable Sliding Roof with push button size (W) 3.5m x (L) 3.5m	9
			Installation of High speed door along with MS mounting frame (w)3m x (h)3m	4
			Strenthening of exsisting structure with paint touch up.	1
			All Polycorbonate sheet change (Use exisiting Vertical AL profile and Top new NIHVA AL profile)	1
2	Horizontal Machine windding shop	(W)14m X (L)40m X (H)5m	Motorized Retractable Sliding Roof with push button size (W) 2.8m x (L) 4.4m (from CTC loading side)	6
			Motorized Retractable Sliding Roof with push button size (W) 4.4m x (L) 2.8m (from Formar side)	6
			Installation of High speed door along with MS mounting frame (w)3m x (h)3m	4
			Strenthening of exsisting structure with paint touch up.	1
			Only top Polycorbonate sheet change with new NIHVA AL profile	1
3	Assembly Shop (Motorised)	(W)7.5m X (L)12m X (H)6.5 m at Center X 6 panel (One side opening and stacking)	Motorized Retractable Roof (only top portion) size (w)7.5) x (L) 13m x Height at center 6.5m and side Height 3m	4
			Require MS structure for Reactrable roof	4
			Side Enclosure required MS Structure+Aluminium+PC	4
			Walk way platform and side railing protection	4
			Installation of High speed door along with MS mounting frame (w)3m x (h)3m	4
4	Tanking Pit (Operation-Manual)	(W)8.7m X (L)23.4m X (H)3.5 m at center X 8 Panel (Centre opening and stack at both end)	Manual Retractable Enclosure	1
			Installation of High speed door along with MS mounting frame (w)2m x (h)2.5m	3

A) Commerical Terms

1)	**Payment Terms:**	15% Advance, Remaining amount should be divide in 9 part and will be release partwise upon dispatch of the material form NIHVA factory at Pune.
2)	**Delivery Date as per PO:**	As per STD
3)	**Transportation:**	1)Form NIHVA shop to T&R 2) Local Supplier to NIHVA 3) NIHVA to local supplier
4)	**P&F Charges:**	Included
5)	**Loading:**	In NIHVA scope
6)	**Unloading:**	In Client Scope
7)	**Lifting Equipments:**	In Client Scope
8)	**Warranty:**	12 months from the date of installation
9)	**Height arrangement:**	NA
10)	**Electricity Supply:**	In Client scope
11)	**GST:**	Extra @ 18%
12)	**Installation Scope:**	In NIHVA scope
13)	**Mode of import:**	Road
14)	**HSN:**	
15)	**Documentation Required:**	Standard Handover Documents